



Solar Energy Corporation of India Limited
(A Government of India Enterprise)
CIN: U40106DL2011GOI225263

D - 3, 1st Floor, Wing - A, Prius Platinum, District Centre,
Saket, New Delhi - 110 017
Tel: 011 - 71989200, Fax: 011 - 71989243
E mail: contracts@seci.co.in

Notice Inviting Tender
On behalf of



Bharat Dynamics Limited (BDL)

For

Tender for Design, Engineering, Supply, Construction, Erection,
Testing & Commissioning of 5 MW (AC) Solar PV Power Plant
with Indigenous Cells & Modules including 5 Years Plant
O&M under Domestic Competitive bidding

At

Bharat Dynamics Limited, Ibrahimpatnam (Telangana)

Tender No. [SECI/C&P/NIT/2017/BDL/5MW-2](#)

Dated: 25/09/2017

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>COVER PAGE</u> <u>Page 1 of 3</u>	<u>Signature of Bidder</u>

TABLE OF CONTENTS

DESCRIPTION	PAGE NO.
SECTION - I : Invitation for Bids (IFB)	1 - 10
SECTION - II : Instructions to Bidders (ITB)	1 - 51
SECTION - III : Bid Data Sheets (BDS)	1 - 3
Annexure to Bid Data Sheet (BDS) : Qualifying Requirements (QR)	1 - 8
SECTION - IV : General Conditions of Contract (GCC)	1 - 59
SECTION - V : Special Conditions of Contract (SCC)	1 - 15
SECTION - VI : Sample Forms & Formats	1 - 39
SECTION - VII : Scope of Work & Technical Specifications	1 - 118
SECTION - VIII : Schedule of Rates (SOR)/ Price Schedule (PS)/ Format for Price Bid	1 - 5

DISCLAIMER

1. Though adequate care has been taken while preparing the tender document, the bidder(s) shall satisfy themselves that the document is complete in all respect. Intimation regarding any discrepancy shall be given to the office of Employer/ Owner immediately. If no intimation is received from any bidder within **10 (Ten) days from the date of issuance of Tender documents**, it shall be considered that the document is complete in all respect and has been received/ acknowledged by the bidder(s).
2. Solar Energy Corporation of India Ltd (SECI) reserves the right to modify, amend or supplement this document.
3. While this tender document has been prepared in good faith, neither SECI nor their employees or advisors make any representation or warranty, express or implied, or accept any responsibility or liability, whatsoever, in respect of any statements or omissions herein, or the accuracy, completeness or reliability of information, and shall incur no liability under any law, statute, rules or regulations as to the accuracy, reliability or completeness of this document, even if any loss or damage is caused by any act or omission on their part.

Place: New Delhi

Date: 25/09/2017

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>COVER PAGE</u> Page 3 of 3	<u>Signature of Bidder</u>



SECTION - I

INVITATION FOR BIDS (IFB)

INVITATION FOR BIDS (IFB)

FOR

TENDER FOR DESIGN, ENGINEERING, SUPPLY, CONSTRUCTION, ERECTION, TESTING & COMMISSIONING OF 5 MW (AC) SOLAR PV POWER PLANT WITH INDIGENOUS CELLS & MODULES INCLUDING 05 YEARS PLANT O&M AT BHARAT DYNAMICS LIMITED, IBRAHIMPATNAM TELANGANA UNDER DOMESTIC COMPETITIVE BIDDING

(SINGLE STAGE TWO ENVELOPE BIDDING)

Under e-Tendering

- 1.0 Bharat Dynamics Limited (BDL), a Government of India Enterprise under the Ministry of Defence was established in Hyderabad in the year 1970 to be a manufacturing base for guided missiles and allied defence equipment. Nurtured by a pool of talented engineers drawn from DRDO and aerospace industries, BDL began its journey by producing the 1st Generation Anti -Tank Guided Missile (ATGM) - the French SS11B1.
- 2.0 Bharat Dynamics Limited (BDL), envisages the execution of Green Energy by way of implementing Solar PV Power Plant at Bharat Dynamics Limited, Ibrahimpatnam, in the State of Telangana. This would not only be a leap towards the use of Green Energy for BDL but also be means of self-reliant and Economical Energy which would capitalize the abundance of Solar Energy.
- 3.0 The EPC/ Tender activities in respect of the aforesaid Project has been entrusted to Solar Energy Corporation of India Limited (A Government of India Enterprise) incorporated under the Companies Act, 2013, having its Registered Office at D - 3, 1st Floor, Wing - A, Prius Platinum Building, District Centre, Saket, New Delhi - 110 017 (hereinafter referred to as 'SECI'/ EMPLOYER). For the purpose of all procurement activities related to the said works, SECI shall be referred to as 'Employer'.
- 4.0 Employer (SECI), therefore on behalf of the "Owner" Bharat Dynamics Limited (BDL), invites bids from eligible bidders to participate in the Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Ibrahimpatnam, Telangana under Domestic Competitive bidding.
- 5.0 **VOID**
- 6.0 The complete Bidding Documents are available at TCIL portal <https://www.tcil-india-electronictender.com> as well as on SECI's website <http://www.seci.co.in>. Interested bidders shall download the Bidding Documents from the portal <https://www.tcil-india-electronictender.com> as per the provisions available therein.
- 7.0 Interested bidders have to necessarily register themselves on the portal <https://www.tcil-india-electronictender.com>

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	IFB Page 2 of 9	Signature of Bidder

india-electronictender.com through M/s Telecommunications Consultants India Limited (TCIL), New Delhi to participate in the bidding under this invitation for bids. It shall be the sole responsibility of the interested bidders to get themselves registered at the aforesaid portal for which they are required to contact M/s TCIL, New Delhi to complete the registration formalities. The address of M/s TCIL is mentioned on the Bid Information Sheet. All required documents and formalities for registering on TCIL are mentioned in the subsequent bidding documents.

They may obtain further information regarding this IFB from the registered office of SECI at the address given on the Bid Information Sheet from 10:00 hours to 17:00 hours on all working days.

For proper uploading of the bids on the portal namely <https://www.tcil-india-electronictender.com> (hereinafter referred to as the 'portal'), it shall be the sole responsibility of the bidders to apprise themselves adequately regarding all the relevant procedures and provisions as detailed in the portal as well as by contacting M/s Telecommunications Consultants India Limited, New Delhi directly, as and when required, for which contact details are also mentioned on the Bid Information Sheet. The Employer in no case shall be responsible for any issues related to timely or properly uploading/ submission of the bid in accordance with the relevant provisions of Section II - ITB of the Bidding Documents.

- 8.0 While submitting/ uploading the bids, the system through portal asks to key in the pass-phrase for encryption of the documents. The pass-phrase is required by Employer for opening the bids (Separate for both First Envelopes as well as Second Envelopes). **The same may be submitted on the portal as per the provisions existing for submission of the pass-phrase and as per the details given in ITB.**

In the event of not opening of the bid with the pass-phrase provided by the bidder, Employer on its discretion may give an option through the portal, to the bidder to open its bid as per provisions available on the portal. However, Employer shall not be responsible if bid could not be opened within reasonable time for what so ever reason. In such a case, the bid shall be sent unopened to 'Archive' on the portal and shall not be considered at all any further.

- 9.0 A Single Stage Two Envelope Bidding Procedure will be adopted and will proceed as detailed in the Bidding Documents. Bidding will be conducted through the competitive bidding procedures as per the provisions of ITB/ BDS and the contract shall be executed as per the provisions of the Contract. It shall be noted that the respective rights of the Employer and the Bidder/ Contractor shall be governed by the Bidding Documents/ Contract signed between the Employer and the Contractor for the package.
- 10.0 Bidders should submit their bid proposal online complete in all aspect on or before last date and time of Bid Submission as mentioned on ETS Portal of TCIL (<https://www.tcil-india-electronictender.com>), SECI website <http://www.seci.co.in> and as indicated in the Bid Information Sheet.
- 11.0 Bidder shall submit bid proposal along with non-refundable Tender Processing Fees, Earnest Money Deposit (EMD) complete in all respect as per the Bid Information Sheet. Techno-

Commercial bids will be opened as per the Bid Information Sheet in offline/ online presence of authorised representatives of bidders who wish to be present offline/ online. Bid proposals received without the prescribed Tender Processing Fees and Earnest Money Deposit (EMD) will be rejected. **In the event of any date indicated is a declared Holiday, the next working day shall become operative for the respective purpose mentioned herein.**

- 12.0 Tender documents which include Eligibility Criteria, Technical Specifications, various Conditions of Contract, Formats etc. can be downloaded from ETS Portal of TCIL (<https://www.tcil-india-electronictender.com>) or from SECI website (<http://www.seci.co.in>). **It is mandatory to download official copy of Tender Document from Electronic Tender System (ETS) Portal of TCIL to participate in the Tender.** Any amendment(s)/ corrigendum(s)/ clarification(s) with respect to this Tender shall be uploaded on TCIL website. The Bidder should regularly check for any Amendment(s)/ Corrigendum(s)/ Clarification(s) on the above mentioned TCIL website. The same may also be uploaded on SECI website <http://www.seci.co.in> also. **However, in case of any discrepancy, the information available on TCIL website shall prevail.**

- 13.0 The detailed scope of work includes :

- 13.1 Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant at Bharat Dynamics Limited, Ibrahimpatnam, Telangana

- 13.2 Comprehensive operation & maintenance of the Solar PV Power Plant for 5 (Five) years as mentioned in detailed scope of work after successful commissioning and performance demonstration, as detailed in technical specification including supply and storage of all mandatory spare parts, consumables, repairs/ replacement of any defective equipment etc

The above scope of work is indicative and the detailed scope of work is given in the Scope of Work and Technical Specification (Section - VII) of the Tender Documents.

- 14.0 In case a Tender provides provision for multiple bids by a common bidder, then separate EMD(s) and Tender Processing Fees shall be furnished for all the bids as listed out in the Tender along with the response to Tender. Kindly refer the Clause of Bid Information Sheet for details. EMD shall be enclosed in a sealed envelope and shall be submitted in the office of Employer (offline) whose mailing address is mentioned in the Bid Information Sheet.

- 15.0 For multiple packages, separate Performance Securities shall be furnished against each package being executed under this Tender (*indicating the list of Packages as per Tender where project(s) are to be executed*) by the successful bidder after issuance of Notification of Award (NOA)/ Letter of Intent (LOI)/ Letter of Allocation (LOA) by Employer/ Owner.

- 16.0 The detailed Qualifying Requirements (QR) are given in the Annexure to BDS.

- 17.0 The Employer shall conduct e-Reverse Auction (e-RA), if required or as per provisions of **Special Conditions of Contract (SCC) /Instructions to Bidders (ITB)** of Tender documents.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>IFB</u> Page 4 of 9	<u>Signature of Bidder</u>

18.0 ***Employer/ Owner reserves the right to cancel/ withdraw this invitation for bids without assigning any reason and shall bear no liability whatsoever consequent upon such a decision.***

INTERPRETATIONS

1. Words comprising the singular shall include the plural & vice versa.
2. An applicable law shall be construed as reference to such applicable law including its amendments or re-enactments from time to time.
3. A time of day shall save as otherwise provided in any agreement or document be construed as a reference to Indian Standard Time.
4. Different parts of this contract are to be taken as mutually explanatory and supplementary to each other and if there is any differentiation between or among the parts of this contract, they shall be interpreted in a harmonious manner so as to give effect to each part.
5. The table of contents and any headings or sub headings in the contract has been inserted for case of reference only & shall not affect the interpretation of this agreement.

BID INFORMATION SHEET

The brief details of the tender are as under:

(A)	NAME OF WORK/ BRIEF SCOPE OF WORK/ JOB	Design & engineering, procurement & supply of equipment and materials, testing at manufacturers works, multi – level inspections, packing and forwarding, supply, receipt, unloading and storage at site, associated civil works, services, permits, licences, installation and incidentals, insurance at all stages, erection, testing and commissioning of 5 MW (AC) Grid Interactive Solar PV Power Plant with Indigenously manufactured Cells and Modules ad performance demonstration with associated equipment and materials on turnkey basis at Bharat Dynamics Limited, Ibrahimpatnam, Telangana along with 5 (Five) years comprehensive operation and maintenance from the date of commissioning or Operational Acceptance, whichever is later. 1. Design, Procurement & Supply and erection of the following, in all respect: 1.1 Solar panels including module mounting structures and fasteners 1.2 All power conditioning systems including junction boxes, Inverters/ PCU, DC and AC circuit breaker(s).

		1.3 All associated electrical works and equipment required for interfacing line/ cable (i.e. transformer(s) – power and auxiliary, breakers, isolators, lightning arrestor(s), LT/other panels, protection system, cables, metering etc., but not limited to) as per technical specifications. 1.4 Design, supply, erection, testing & commissioning Cabling/ TL at voltage level defined in scope of work/ TS as per project requirement and associated switchgear equipment and metering equipment as per technical specification and state regulations. 1.5 All associated civil works, including design and Engineering, for: Earthwork for Site grading, cutting, filling, levelling & compacting in requisite project land as required for development of this Rooftop Solar PV Power Plant 1.6 Construction of module mounting structure as per ground conditions and other power equipment foundations, cable trenches for cable routing and earthing pits. 1.7 Construction of Passage for Cleaning of Solar PV (SPV) Project 1.8 Construction of rain water drainage, as required 1.9 Setting up of a comprehensive Fire Protection system as per the Hazardous area classification for the site 1.10 Supply of mandatory spares 1.11 Demonstration of performance of the plant as per the requirement specified in the bidding documents. 1.12 Comprehensive operation & maintenance of the SPV plant for 5 (Five) years as mentioned in detailed scope of work from the date of commissioning or Operational Acceptance, whichever is later, as detailed in technical specification including supply and storage of all spare parts, consumables, repairs/ replacement of any defective equipment etc 1.13 Obtaining all associated statutory and regulatory compliances and approvals for successful construction, commissioning and operation of plant 1.14 The detailed scope of work is given in Section VII : Scope of Work, specifications and Drawings of this bidding documents.				
(B)	TENDER NO. & DATE	SECI/C&P/NIT/2017/BDL5MW-2 dated 25/09/2017				
(C)	MULTIPLE BIDDING SYSTEM	<table><tr><td>ALLOWED</td><td> </td></tr><tr><td>NOT ALLOWED</td><td> Yes </td></tr></table>	ALLOWED		NOT ALLOWED	Yes
ALLOWED						
NOT ALLOWED	Yes					

(D)	TYPE OF TENDER	E-TENDER	Yes
		MANUAL	
(E)	COMPLETION/ CONTRACT PERIOD	As mentioned in Special Conditions of Contract (SCC).	
(F)	TENDER PROCESSING FEE	APPLICABLE	Yes
		NOT APPLICABLE	
		Amount: INR 1,56,350/- (Indian Rupees One Lacs & Fifty Six thousand and Three fifty only) inclusive of GST @ 18%	
(G)	EARNEST MONEY DEPOSIT (EMD)	APPLICABLE	Yes
		NOT APPLICABLE	
		Amount: INR 53, 00,000/- (Indian Rupees Fifty Three lacs only).	
(H)	CONTRACT PERFORMANCE SECURITY	APPLICABLE	Yes
		NOT APPLICABLE	
(I)	DATE, TIME & VENUE OF PRE-BID MEETING	1100 HRS (IST) on 09/10/2017 at Bharat Dynamics Limited, Kanchanbagh Hyderabad (Dist.), Telangana(State) - 500058 Kind Attn.: Shri CH Ramesh Babu (AGM) Telephone Nos.: - 0091-(0) 040-24587104/24587124 Fax No.: - 0091-(0) 040-24340464 E mail: tsdkbc.bdl@bdl-india.com	

(J)	OFFLINE & ONLINE BID-SUBMISSION DEADLINE	30/10/2017 up to 1800 HRS
(K)	OFFLINE & ONLINE BID OPENING	31/10/2017, 1100 HRS onwards
(L)	FINANCIAL BID OPENING	To be intimated subsequent to the shortlisting of Techno Commercial Bids
(M)	TECHNICAL QUERIES CONTACT DETAILS	Dr YBK Reddy Deputy General Manager (Solar) OR Mr. Debajyoti Bordoloi Manager (Projects) Solar Energy Corporation of India Limited (A Government of India Enterprise) D - 3, 1 st Floor, Wing - A, Prius Platinum Building, District Centre, Saket, New Delhi - 110 017 E mail: debajyoti.b@seci.co.in Phone: 011-71989200/ 71989296/ 71989230
(N)	CONTACT DETAILS OF TCIL	M/s Telecommunications Consultants India Limited 6 th Floor, TCIL Bhawan, Greater Kailash - 1 New Delhi - 110 048 Contact Person : ETS Support Team Contact No. : 011 26202699 (Multiline) / 26241790 / 26202661 Email : ets_support@tcil-india.com

- 1.0 Bids must be submitted strictly in accordance with Clause no. 11 of ITB depending upon Type of Tender as mentioned at Clause no. (D) of Bid Information Sheet. The IFB is an integral and inseparable part of the Tender document.
- 2.0 Bidder(s) are advised to quote strictly as per terms and conditions of the tender documents and not to stipulate any deviations/ exceptions.
- 3.0 Any bidder, who meets the Qualifying Requirement and wishes to quote against this tender, may download the complete bidding document along with its amendment(s) if any from ETS Portal of TCIL (<https://www.tcil-india-electronictender.com>) and/ or SECI website (www.seci.co.in) and submit their Bid complete in all respect as per terms & conditions of Tender Document on or before the due date of bid submission.
- 4.0 Clarification(s)/ Corrigendum(s) if any shall also be available on above referred websites.
- 5.0 NOA/ LOI/ LOA for LSTK (Lump Sum Turn Key)/ EPC (Engineering, Procurement & Commissioning) job shall be issued to successful bidder(s). The NOA/ LOI/ LOA for LSTK/ EPC job shall be awarded in following respective parts as mentioned briefly below: -

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	IFB <u>Page 8 of 9</u>	<u>Signature of Bidder</u>

- (i) **First Contract:** FOR destination basis Supply including Transportation for delivery at site and Insurance of all Equipments and materials including mandatory spares and any other supplies specified in the Contract Documents.
- (ii) **Second Contract:** For providing all services i.e., including Unloading, Storage, Handling at Site, Civil Works, Erection, Installation, Testing and Commissioning including Performance Testing in respect of all the Equipments supplied under the "First Contract" and any other services specified in the Contract Documents.

Both contracts will contain a cross fall breach clause specifying that breach of one will constitute breach of the other

- (iii) **Third Contract:** For providing Comprehensive operation & maintenance of the Solar PV plant for 5 (Five) years from the date of commissioning or Operational Acceptance, whichever is later, as detailed in technical specification including supply and storage of all spare parts, consumables, repairs/ replacement of any defective equipment etc

6.0 However, the above-mentioned contract award methodology may be modified/ changed based on specific project requirements and upon sole discretion of Employer/ Owner.



SECTION - II

INSTRUCTION TO BIDDERS (ITB)

TABLE OF CONTENTS

[A] GENERAL:

1. SCOPE OF BID
2. ELIGIBLE BIDDERS
3. BIDS FROM CONSORTIUM/ JOINT VENTURE
4. NUMBER OF BIDS PER BIDDER
5. COST OF BIDDING & TENDER PROCESSING FEE
6. SITE-VISIT

[B] BIDDING DOCUMENTS:

7. CONTENTS OF TENDER DOCUMENTS
8. CLARIFICATION OF TENDER DOCUMENTS
9. AMENDMENT OF TENDER DOCUMENTS

[C] PREPARATION OF BIDS:

10. LANGUAGE OF BID
11. DOCUMENTS COMPRISING THE BID
12. SCHEDULE OF RATES/ PRICE SCHEDULE/ BID PRICES
13. GOODS & SERVICE TAX
14. BID CURRENCIES
15. BID VALIDITY
16. EARNEST MONEY DEPOSIT
17. PRE-BID MEETING
18. FORMAT AND SIGNING OF BID
19. ZERO DEVIATION & REJECTION CRITERIA
20. E-PAYMENT

[D] SUBMISSION OF BIDS:

21. SUBMISSION, SEALING AND MARKING OF BIDS
22. DEADLINE FOR SUBMISSION OF BIDS
23. LATE BIDS
24. MODIFICATION AND WITHDRAWAL OF BIDS

[E] BID OPENING AND EVALUATION:

25. EMPLOYER'S RIGHT TO ACCEPT ANY BID AND TO REJECT ANY OR ALL BIDS
26. BID OPENING
27. CONFIDENTIALITY
28. CONTACTING THE EMPLOYER/ OWNER
29. EXAMINATION OF BIDS AND DETERMINATION OF RESPONSIVENESS
30. CORRECTION OF ERRORS
31. CONVERSION TO SINGLE CURRENCY FOR COMPARISON OF BIDS
32. EVALUATION OF BIDS & e-REVERSE AUCTION
33. COMPENSATION FOR EXTENDED STAY
34. PURCHASE PREFERENCE

[F] NOTIFICATION OF AWARD/ LETTER OF INTENT/ CONTRACT AGREEMENT:

35. AWARD
36. NOTIFICATION OF AWARD/ LETTER OF INTENT/ LETTER OF ALLOCATION
37. SIGNING OF CONTRACT AGREEMENT
38. CONTRACT PERFORMANCE SECURITY
39. PROCEDURE FOR ACTION IN CASE CORRUPT/ FRAUDULENT/ COLLUSIVE/ COERCIVE PRACTICES
40. PUBLIC PROCUREMENT POLICY FOR MICRO AND SMALL ENTERPRISE (MSEs)
41. AHR ITEMS
42. RISK OF REJECTION
43. INCOME TAX & CORPORATE TAX
44. SETTLEMENT OF DISPUTES BETWEEN GOVERNMENT DEPARTMENT AND ANOTHER AND ONE GOVERNMENT DEPARTMENT AND PUBLIC ENTERPRISE AND ONE PUBLIC ENTERPRISE AND ANOTHER
45. DISPUTE RESOLUTION

[G] ANNEXURES:

1. ANNEXURE-I: PROCEDURE FOR ACTION IN CASE CORRUPT/ FRAUDULENT/ COLLUSIVE/ COERCIVE PRACTICES
2. ANNEXURE-II: ADDENDUM TO INSTRUCTIONS TO BIDDERS (INSTRUCTION FOR PARTICIPATION IN E-TENDER)

Preamble

This part (Section - II) of the Tender Documents provides the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Employer/ Owner. It also provides information on bid submission and uploading the bid on portal <https://www.tcil-india-electronictender.com>, bid opening, evaluation and on contract award. This Section (Section - II) contains provisions that are to be used unchanged unless Section - III (Bid Data Sheets) and Section - V (Special Conditions of Contract), which consists of provisions that supplement, amend, or specify in detail, information or requirements included in ITB and that are specific to each procurement, states otherwise. If there is a conflict between the provisions of Section – II, Section – III and Section - V, the provisions of Section - V shall prevail.

However, provisions governing the performance of the Contractor, payments under the contract or matters affecting the risks, rights and obligations of the parties under the contract are not included in this section but instead under Section - IV (General Conditions of Contract) and/ or Section - V (Special Conditions of Contract).

Bidders may note that the respective rights of the Employer/ Owner and Bidders/ Contractors shall be governed by the Tender Documents/ Contracts signed between the Employer/ Owner and the Contractor for the respective package(s). The provisions of Tender Documents shall always prevail over any other documents in case of contradiction.

Further in all matters arising out of the provisions of this Section - II, Section - III and the Section - V of the Tender Documents, the laws of the Union of India shall be the governing laws and courts of New Delhi shall have exclusive jurisdiction.

[A] - GENERAL

1 SCOPE OF BID

- 1.1 The Employer/ Owner, wishes to receive Bids as described in the Bidding documents/ Tender documents issued by Employer/ Owner.
- 1.2 SCOPE OF BID : The scope of work/ Services shall be as defined in the Tender documents.
- 1.3 The successful bidder will be expected to complete the entire scope of work within the period stated in Section - V, Special Conditions of Contract.
- 1.4 Throughout the Tender Documents, the terms 'Bid', 'Tender' & 'Offer' and their derivatives [Bidder/ Tenderer, Bidding Documents/ Tender Documents, Bid/ Tender/ Offer etc.] are synonymous. Further, 'Day' means 'Calendar Day' and 'Singular' also means 'Plural'.

2 ELIGIBLE BIDDERS

- 2.1 The Bidder shall not be under a declaration of ineligibility by Employer for Corrupt/ Fraudulent/ Collusive/ Coercive practices, as defined in "Instructions to Bidders [ITB], Clause no. 39" (Action in case Corrupt/ Fraudulent/ Collusive/ Coercive Practices).
- 2.2 The Bidder shall not be debarred by Employer/ Owner/ Ministry of New & Renewable Energy (MNRE) for future bidding due to "poor performance" or "corrupt and fraudulent practices" or any other reason in the past. Further, neither bidder nor their allied agency(ies) (as defined in the Procedure for Action in case of Corrupt/ Fraudulent/ Collusive/ Coercive Practices) should be on the banning list of Employer/ Owner or the Ministry of New & Renewable Energy (MNRE).

If the tender documents were issued inadvertently/ downloaded from website, offers submitted by such bidders shall not be considered for opening/ evaluation/ Award and will be returned immediately to such bidders.

In case there is any change in status of the declaration prior to award of contract, the same has to be promptly informed to Employer/ Owner by the bidder.

It shall be the sole responsibility of the bidder to inform Employer/ Owner/ MNRE in case the bidder is debarred from bidding by Employer/ Owner/ MNRE or Public Sector Project

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 5 of 54	<u>Signature of Bidder</u>

Management Consultant. Concealment of the facts shall tantamount to misrepresentation of facts and shall lead to action against such Bidders as per clause no. 39 of ITB.

- 2.3 The Bidder should not be under any liquidation court receivership or similar proceedings on due date of submission of bid.

In case there is any change in status of the declaration prior to award of contract, the same has to be promptly informed to Employer/ Owner by the bidder.

It shall be the sole responsibility of the bidder to inform Employer/ Owner in case the bidder is under any liquidation court receivership or similar proceedings on due date of submission of bid and during the course of finalization of the tender. Concealment of the facts shall

tantamount to misrepresentation of facts and shall lead to action against such Bidders as per clause no. 39 of ITB.

2.4 Bidder shall not be affiliated with an entity:

- (i) that has provided consulting services related to the work to the Employer/ Owner during the preparatory stages of the work or of the project of which the works/ services forms a part of or
- (ii) that has been hired (proposed to be hired) by the Employer/ Owner as an Engineer/ Consultant for the contract.

2.5 Neither the entity [appointed as the Project Management Consultant (PMC) for a contract] nor its affiliates/ JV's/ Subsidiaries shall be allowed to participate in the tendering process.

2.6 Pursuant to qualification criteria set forth in the bidding document, the Bidder shall furnish all necessary supporting documentary evidence to establish Bidder's claim of meeting qualification criteria as mentioned in the Annexure to BDS.

3 BIDS FROM CONSORTIUM/ JOINT VENTURE

3.1 Bids from Consortium/ Joint Venture are allowed. However, the eligibility criteria along with other terms and conditions (as mentioned in clause no. 1.4 of Annexure - A to BDS) shall be complied upon.

4 NUMBER OF BIDS PER BIDDER

4.1 Unless specified otherwise, a Bidder shall submit only 'one [01] Bid' in the same Bidding Process. A Bidder who submits or participates in more than 'one [01] Bid' will cause all the proposals in which the Bidder has participated to be disqualified.

However multiple bids from a single bidder can be considered depending upon project specific requirement as mentioned in BDS.

5 COST OF BIDDING & TENDER PROCESSING FEE

5.1 COST OF BIDDING

The Bidder shall bear all costs associated with the preparation and submission of the Bid including but not limited to Bank charges, all courier charges including taxes & duties etc. incurred thereof. Further, Employer/ Owner will in no case, be responsible or liable for these costs, regardless of the outcome of the bidding process.

5.2 TENDER PROCESSING FEE (NON-REFUNDABLE)

5.2.1 A non- refundable, Tender Processing Fee, if applicable, is to be submitted in the form of 'crossed payee accounts only' Demand Draft/ Banker's Cheque in favour of "Solar Energy Corporation of India Limited, New Delhi" payable at New Delhi. The Tender Processing Fee is to be submitted along with the bid for the amount as mentioned in the Bid Information Sheet

attached under Section - I (Invitation for Bids, IFB) . Bids submitted without payment of requisite Tender Processing Fee will be treated as non-responsive and shall be liable for rejection.

5.3 The Tender Processing Fee is exempted for MSME Vendors registered under NSIC/ Udyog Aadhaar/DIC Category only. In order to avail the exemption in Tender Processing Fee in case of consortium/ JV, all the members should be registered as MSME Vendors under NSIC/ Udyog Aadhaar Category/DIC.

5.4 In case of any discrepancy/ non-submission of either offline or online bid documents by the bidder, the tender processing fee will be deemed as bidder's consent for participation in the bidding process. Henceforth, the tender processing fee shall be retained by Employer and shall not be returned under any circumstances. No plea in this regard shall be entertained by the Employer/ Owner.

5.5 In the event of a particular tender being cancelled, the tender processing fee will be refunded to the concerned bidders without any interest charges within 30 days from the date of notification of cancellation of tender. No plea in this regard shall be entertained by the Employer/ Owner.

6 SITE VISIT

6.1 The Bidder is advised to visit and examine the site of works and its surroundings and obtain for itself on its own responsibility all information that may be necessary for preparing the Bid and entering into a Contract for the required job. The costs of visiting the site shall be borne by the Bidder.

6.2 The Bidder or any of its personnel or agents shall be granted permission by the Employer/ Owner to enter upon its premises and land for the purpose of such visits, but only upon the express conditions that the Bidder, its personnel and agents will release and indemnify the Employer/ Owner and its personnel, agents from and against all liabilities in respect thereof, and will be responsible for death or injury, loss or damage to property, and any other loss, damage, costs, and expenses incurred as a result of inspection.

6.3 The Bidder shall not be entitled to hold any claim against Employer/ Owner for non-compliance due to lack of any kind of pre-requisite information as it is the sole responsibility of the Bidder

to obtain all the necessary information with regard to site, surrounding, working conditions, weather etc. on its own before submission of the bid.

[B] - BIDDING DOCUMENTS

7 CONTENTS OF TENDER DOCUMENTS

7.1 The contents of Tender Documents are those stated below, and should be read in conjunction with any 'Addendum/ Corrigendum' issued in accordance with "ITB: Clause-9":

- Section-I : Invitation for Bids [IFB]
- Section-II : Instructions to Bidders [ITB]
- Section-III : Bid Data Sheets [BDS]
Annexure to Bid Data Sheets [Qualifying Requirements]
- Section-IV : General Conditions of Contract [GCC]
- Section-V : Special Conditions of Contract [SCC]
- Section-VI : Sample Forms and Formats
- Section-VII : Scope of Work & Technical Specifications
- Section-VIII : Schedule of Rates [SOR]/ Price Schedule [PS]/ Format for Price Bid

7.2 The Bidder is expected to examine all instructions, forms, terms & conditions in the Tender Documents. The entire Tender Documents together with all its amendments, clarifications and attachments thereto, shall be considered to be read, understood and accepted by the Bidders. Failure to furnish all information required by the Tender Documents or submission of a Bid not substantially responsive to the Tender Documents in every respect will be at Bidder's risk and may result in the rejection of his Bid. However, Employer/ Owner at its sole discretion may seek clarifications from the Bidders to adjudge the exact content and facts of the Tender Documents.

8 CLARIFICATION OF TENDER DOCUMENTS

8.1 A prospective Bidder requiring any clarification(s) of the Tender Documents may notify Employer in writing by E-mail or at Employer's mailing address indicated in the Bid Information Sheet no later than 02 (Two) working days after the pre-bid meeting (in cases where pre-bid meeting is scheduled) or 15 (Fifteen) days prior to the bid closing date (in cases where pre-bid meeting is not held). Employer reserves the right to ignore the bidders request for clarification if received beyond the aforesaid period. Employer may respond in writing to the request for clarification. Employer's response including an explanation of the query, but

without identifying the source of the query will be uploaded on ETS Portal of TCIL <https://www.tcil-india-electronictender.com> and/ or Employer's website www.seci.co.in.

- 8.2 Any clarification or information required by the Bidder but same not received by the Employer at clause 8.1 above is liable to be considered as "no clarification/ information required".

9 AMENDMENT OF TENDER DOCUMENTS

- 9.1 At any time prior to the 'Bid Due Date', Employer/ Owner may, for any reason, whether at its own initiative or in response to a clarification requested by a prospective Bidder, modify the Tender Documents by addenda/ corrigendum.
- 9.2 Any addendum/ corrigendum thus issued shall be part of the Tender Documents and shall be hosted on ETS Portal of TCIL <https://www.tcil-india-electronictender.com> and/ or Employer's website www.seci.co.in. Bidders have to take into account all such addendum/ corrigendum before submitting their bid.
- 9.3 The Employer, if consider necessary, may extend the date of submissions of Bid in order to allow the Bidders a reasonable time to furnish their most competitive bid taking into account the amendment issued thereof.

[C] - PREPARATION OF BIDS

10 LANGUAGE OF BID:

The bid prepared by the bidder and all correspondence/ drawings and documents relating to the bid exchanged by bidder and Employer/ Owner shall be written in English language alone. Any printed literature furnished by the bidder may be written in another language as long as accompanied by an ENGLISH translation duly authenticated by the Chamber of Commerce/ Certified Translator of bidder's country, in which case, for the purpose of interpretation of the bid, the ENGLISH translation shall govern.

In the event of submission of any document/ certificate by the Bidder in a language other than English, the English translation of the same duly authenticated by Chamber of Commerce/ Certified Translator of Bidder's country shall be submitted by the Bidder.

11. DOCUMENTS COMPRISING THE BID

The bid shall be submitted by the Bidder under "Single Stage - Two Envelope" procedure of bidding. Under this procedure, the bid submitted by the Bidder in two envelopes - First

Envelope (also referred to as Techno - Commercial Part) and Second Envelope (also referred to as Price Part) shall comprise of the following documents:

I. Hard Copy

Hard copy of the bid shall comprise of following documents/ programmed file-Attachments to be submitted in sealed envelope, as part of First Envelope. **The envelope shall bear {the name of Tender, the Tender No. and the words 'DO NOT OPEN BEFORE' (due date & time)}.**

Contact Persons Name: Shri Sandeep Kumar

- Original Non-Refundable Tender Processing Fee as per clause no. 05 of ITB
- Original Non-Refundable Cost of Tender Document, if applicable
- 'Covering Letter' on Bidder's 'Letterhead' (in Original) clearly specifying the enclosed contents, as per 'Form F-0'
- EMD in original as per Clause 16 of ITB as per 'Form F-4' or as prescribed.
- In case of Bid from Joint Venture, the Joint Venture Agreement (as per 'Form F-17') and Power of Attorney for Joint Venture Agreement (as per 'Form F-17A') (both in Original)
- In case of Bid from Consortium, the Consortium Agreement (as per 'Form F-18') and Power of Attorney for Consortium Agreement (as per 'Form F-18A') (both in Original)
- Power of Attorney for authorized signatory in non-judicial stamp paper (as per 'Form F-24')
- Copy of Board Resolution
- The Pass-Phrase to decrypt the relevant Bid-Parts (for both Techno-Commercial and Financial) in separate sealed envelopes before the start date and time of the Tender Opening Event (TOE)

Bidder shall also upload the scanned copies of all the above mentioned original documents as Programmed File Attachments during online Bid Submission as a part of First envelope.

"Bidder should explicitly note that no hard copies are to be submitted as a part of Second envelope".

II. Soft Copy

Soft copy of the bid shall comprise of following documents to be uploaded on the TCIL portal <https://www.tcil-india-electronictender.com> as per provisions therein.

5 MW (AC) Solar PV Power Plant Project	Tender No SECI/C&P/NIT/2017/BDL5MW-2	ITB Page 11 of 54	Signature of Bidder

(a) As part of First Envelope

- I. The Electronic Form of the bid for First Envelope (Techno-Commercial), as available on the TCIL portal, shall be duly filled.
- II. Programmed file - Attachments (as detailed against clause no. 11.I) and Bid Form for first envelope.
- III. Certificate of Incorporation
- IV. 'Bidder's General Information', as per 'Form F-1'.
- V. Shareholding Certificate (as per 'Form F-23')
- VI. 'No Deviation Confirmation', as per 'Form F-6'
- VII. 'Bidder's Declaration regarding Banning, Liquidation etc.', as per 'Form F-7'
- VIII. 'Bidders Experience as per 'Form F-13'
- IX. E-Banking Format (as per 'Form F-19')
- X. Documents in accordance with the "Qualifying Requirements (QR)" establishing the qualification
- XI. Document showing annual turnover for the financial years as required in Qualifying Requirements (QR) such as annual reports, profit and loss account, net worth etc. along with information as sought in enclosed Format F-16
- XII. Tender Document. (Only First and Last Pages of Original Tender Document duly sealed and signed/ digitally signed and all pages of amendments and clarifications to Tender Documents duly sealed and signed/ digitally signed by the Authorized Signatory).
- XIII. Sealed and signed/ digitally signed, Blank copies **(WITHOUT PRICES)** of SOR-1 & SOR-2 mentioning **"QUOTED"** for all the items of Respective SORs.

Bidder should explicitly note that no prices are to be mentioned in any of the SOR here & only needs to write "QUOTED".

(b) As part of Second Envelope

- I. The Electronic Form of the bid for Second Envelope (Price - Part), as available on the TCIL portal, shall be duly filled. "Termed as **ELECTRONIC FORM**"

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 12 of 54</u>	<u>Signature of Bidder</u>

- II. Main Price Bid comprising of SOR-1 & SOR-2 of the Price Schedule (available in Section - VIII, SOR), duly completed, sealed and signed/ digitally signed shall be uploaded. "Termed as **MAIN BID**".

SOR -1 is the Schedule and Breakup of Lump sum Price (Supply, Service and NPV of O&M) of the Tender. SOR -2 comprises of the yearly Breakup of the NPV of O&M price for 5 years period.

12 SCHEDULE OF RATES (SOR)/ PRICE SCHEDULE (PS)/ BID PRICES

- 12.1 Unless stated otherwise in the Tender Documents, the Contract shall be for the whole works as described in Tender Documents, based on the rates and prices submitted by the Bidder and accepted by the Employer/ Owner. The prices quoted by the Bidders should indicate clearly the Goods & Service Tax (GST) components as also mentioned under the SoR.
- 12.2 Prices must be filled in format for "Schedule of Rates [SOR]/ Price Schedule [PS]/ Bid Prices" enclosed as part of Tender documents under Section - VIII. If quoted in separate typed sheets and any variation in item description, unit or quantity is noticed, such bids may be rejected.
- 12.3 Bidder shall quote for all the items of "SOR/ PS" after careful analysis of cost involved for the performance of the completed item considering all parts of the Tender Document. In case any activity though specifically not covered in description of item under "SOR/ PS" but is required to complete the works as per Specifications, Scope of Work/ Service, Standards, "GCC", "SCC" or any other part of Bidding Document, the prices quoted shall deemed to be inclusive of cost incurred for such activity.
- 12.4 All Goods & Service Tax (GST) components [applicable for both Centre and state] payable by the Contractor under the Contract, or for any other cause, shall be mentioned as per the SOR formats SOR-1 & SOR-2.
- 12.5 Prices quoted by the Bidder, shall remain FIRM and Fixed and valid until completion of the Contract and will not be subject to variation on any account.
- 12.6 In case of any variation (positive/ negative) in existing rates of taxes/ duties/ levies or a new tax/ duty/ levy is introduced or any existing tax/ duty/ levy is abolished or application of any Tax in the course of the performance of this Contract, which will/ may impact the overall pricing in connection with performance of the Contract, an equitable adjustment of the Contract Price shall be made to factor any such change by addition to the Contract Price or deduction therefrom, as the case may be.

All these adjustments would be carried out by considering the base price of taxes equivalent to the amount mentioned under taxes and duties column of the SOR/ PS.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 13 of 54	Signature of Bidder

- 12.7 The Bidder shall quote the prices in 'figures' & words. There should not be any discrepancy between the prices indicated in figures and the price indicated in words. In case of any discrepancy, the same shall be dealt as per clause no. 30 of ITB.
- 12.8 **Bidder need to submit the detailed break-up of Goods & Service Tax (GST) (applicable for both Central and State) in the SOR formats viz SOR-1 & SOR-2. This data is required to ascertain the**
- Computation of taxes assumed at the time of bidding.**
 - The total impact due to revision in applicable tax rate or introduction of new tax, if any.**

Bidders are required to ascertain the correctness of amount related to Goods & Service Tax (GST) as mentioned in the SOR/ PS as on the date of techno-commercial bid opening as it will impact the Price assessment part at the time of evaluation of price bid.

13 Goods & Service Tax (GST)

Contractor shall mandatorily obtain the registration under GST Law at Central level and/or in respective State as may be required. Further, Contractor shall mandatorily file returns under GST before their due date & comply with the requirements of the Law within timelines. Before releasing the payment to the Contractor, SECI shall ensure that the Contractor has complied with all the required statutory requirements under GST. SECI shall not be responsible for any delay in payment release to the contractor in case the GST compliance is not fulfilled from the contractor side in any manner.

Contractor shall be responsible to comply with all the requirements of applicable provisions of GST. Contractor has to mandatorily get registered under GST at Central and relevant State(s). Contractor shall file all the returns on timely basis and upload all the Invoices and acceptance thereof as may be required under the provisions of GST. In case, it is found that Owner is not able to take CENVAT benefit of the taxes due to fault of the Contractor, Owner shall be constrained to deduct the amount from the payments to be made to the Contractor or recover the same in any other manner..

- 13.1 Bidders are required to submit a copy of the GST Registration Certificate or GST provisional certificate while submitting the bids wherever GST tax is applicable.
- 13.2 The responsibility of payment of GST lies with the Service Provider only. Contractor providing taxable service shall issue an Invoice, a Bill or as the case may be, a Challan which is signed,

serially numbered and in accordance with rule GST Law. The invoice shall also contain the following:

- (a) Name, Address & Registration No. of such Person/ Contractor
- (b) Name & Address of the Person/ Contractor receiving Taxable Service
- (c) Description, Classification & Value of Taxable Service provided
- (d) GST Amount, if any.
- (e) HSN code of the Goods/Services.

Payments to Service Provider for claiming GST amount will be made provided the above formalities are fulfilled. Further, Employer/ Owner may seek copies of challan and certificate from Chartered Accountant for deposit of GST collected from Employer/ Owner.

13.3 In case CBIC (Central Board of Indirect Taxes) brings to the notice of Employer/ Owner that the contractor has not remitted the amount towards GST collected from Employer/ Owner to the government exchequer, then, that contractor may be debarred from bidding in future tenders of Employer/ Owner for given period as per the sole discretion of Employer/ Owner.

13.4 In case of statutory variation in GST during currency of the Contract, the Contractor shall submit a copy of the 'Government Notification' to evidence the rate as applicable on the date of submission of Bid and on the date of revision. Claim for payment of GST / Statutory variation in GST, should be raised within two [02] months from the date of issue of 'Government Notification' for payment of differential (in %) GST, otherwise claim in respect of above shall not be entertained for payment of arrears. The following may also be noted: -

- a) Any increase in the rate of non-cenvatable GST beyond the contractual completion period shall be to contractor's account whereas any decrease in the rate shall be passed on to the Employer/ Owner.
- b) The base date for the purpose of applying statutory variation shall be the date of techno-commercial bid opening.

13.5 **Void**

13.6 Where the Employer/ Owner is entitled to avail/ take the CENVAT credit of GST:

13.6.1 Owner/ Employer will reimburse the GST to the Contractor at actuals against submission of cenvatable invoices issued in accordance with GST rules to enable Owner/ Employer to claim cenvat credit of GST paid. In case of any variation in the executed quantities, the amount on which the GST is applicable shall be modified in same proportion.

13.6.2 **Void**

13.7 Where the Employer/ Owner is not entitled to avail/ take the CENVAT credit of GST:

13.7.1 Owner/ Employer will reimburse the GST to the Contractor at actuals against documentary evidence subject to the ceiling amount of GST as quoted by the bidder, subject to any statutory variations. In case of any variation in the executed quantities (If directed and/ or certified by

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>ITB</u> Page 15 of 54	<u>Signature of Bidder</u>

the Engineer-In-Charge) the ceiling amount on which GST is applicable will be modified on pro-rata basis.

13.8 **Void**

- 13.9 Contractor shall ensure timely submission of correct invoice(s) with all required supporting document(s) within a period specified in NOA/ LOI/ LOA/ CA to enable Employer/ Owner to avail CENVAT credit, If applicable.

If CENVAT credit with respect to GST tax is not available to Employer/ Owner for any reason which is not attributable to Employer/ Owner, then Employer/ Owner shall not be obligated or liable to pay or reimburse GST charged in the invoice(s) or shall be entitled to deduct/ setoff/ recover such GST together with all penalties and interest if any, against any amounts paid or payable by Employer/ Owner to Contractor.

14 **BID CURRENCIES:**

Bidders must submit bid in Indian Rupees (INR) only.

15 **BID VALIDITY**

- 15.1 Bids shall be kept valid for period specified in BDS from the final 'Bid Opening Date'. A Bid valid for a shorter period may be rejected by Employer as 'non-responsive'.

- 15.2 In exceptional circumstances, prior to expiry of the original 'Bid Validity Period', the Employer may request the Bidders to extend the 'Period of Bid Validity' for a specified additional period. The request and the responses thereto shall be made in writing or by email. A Bidder may refuse the request without forfeiture of his 'EMD'. A Bidder agreeing to the request will not be required or permitted to modify his Bid, but will be required to extend the validity of its 'EMD' for the period of the extension and in accordance with "ITB: Clause-16" in all respects.

Note: Incase of extension(s) of last due date of the Tender submission, the latest extension issued shall be considered as the final due date of Tender submission and accordingly the Tender validity should be calculated and sufficed. The validity of the Tender need to be revised by respective bidders, in case the bids are already submitted prior to the last due date of the initial Tender submission deadline.

16 **EARNEST MONEY DEPOSIT (EMD)**

- 16.1 Bids must be accompanied with '**Earnest Money Deposit (EMD)**' in the form of '**Demand Draft**' or '**Banker's Cheque**' [in favour of **Solar Energy Corporation of India limited, New Delhi payable at New Delhi**] or '**Bank Guarantee**' as per the format given in **Form F - 4 of the bidding documents**. Bidders shall ensure that EMD, having a validity of at least 30 (Thirty) Days beyond the validity of the bid, must accompany the Bid in the format(s) made

available in the Tender Document. In case of any extension in validity of bid, the EMD shall be extended suitably. The EMD shall be submitted in Indian Rupees only.

- 16.2 The '**EMD**' is required to protect Employer/ Owner against the risk of Bidder's conduct, which would warrant the EMD's forfeiture, pursuant to "ITB: Clause-16.7".
- 16.3 Employer/ Owner shall not be liable to pay any Bank charges, commission or interest etc. on the amount of 'EMD'. In case 'EMD' is in the form of a 'Bank Guarantee', the same shall be from any scheduled Bank as specified in the List of Banks enclosed at Form F-22, Section-VI of Tender documents or a branch of an International Bank situated in India and registered with 'Reserve Bank of India' as Scheduled Foreign Bank. However, in case of 'Bank Guarantee' from Banks other than the Nationalized Indian Banks, the Bank must be commercial bank having net worth in excess of INR 500 Crores (Indian Rupees Five Hundred Crores Only).
- 16.4 Bid not accompanied with required amount of EMD or required validity or not in requisite format shall be liable for rejection.
- 16.5.1 'Earnest Money Deposit' of unsuccessful Bidders disqualified at the stage of Techno-Commercial evaluation will be discharged/ returned as promptly as possible, but not later than '30 [thirty] days' after intimation of their disqualification.
- Xzc
- 16.5.2 'Earnest Money Deposit' of unsuccessful Bidders excluding L-2 bidder will be discharged/ returned as promptly as possible, but not later than '30 [thirty] days' after issuance of NOA/ LOI/ LOA to successful bidder.
- 16.5.3 'Earnest Money Deposit' of L-2 bidder will be discharged against the acceptance and signing of Contract Agreement with successful bidder. This process shall be completed not later than '30 [thirty] days' after issuance of NOA/ LOI/ LOA to successful bidder.
- 16.6 The successful bidder's 'Earnest Money Deposit' will be discharged upon the Bidder's acknowledging the 'Award' and signing the 'Agreement' and furnishing the 'Performance Security' pursuant to clause nos. 37 & 38 of ITB.
- 16.7 Notwithstanding anything contained herein, the 'EMD' may also be forfeited in any of the following cases:

- (a) If a Bidder withdraws or varies his Bid during the 'Period of Bid Validity'
- (b) If a Bidder has indulged in corrupt/ fraudulent/ collusive/ coercive practice
- (c) If the Bidder modifies bids during the period of bid validity (after last date of submission).
- (d) Violates any other condition, mentioned elsewhere in the tender document, which may lead to forfeiture of EMD.
- (e) In the case of a successful Bidder, if the Bidder fails to:
 - (i) acknowledge receipt the NOA/ LOI/ LOA within 15 (Fifteen) days from issuance of same.
 - (ii) to furnish "Performance Security in accordance with "ITB : Clause-38"

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 17 of 54</u>	<u>Signature of Bidder</u>

(iii) to accept 'arithmetical corrections' as per provision of the clause 30 of ITB.

16.8 In case EMD is in the form of 'Bank Guarantee', the same must indicate the Bid Document No. and the Work for which the Bidder is quoting. This is essential to have proper correlation at a later date. The 'EMD' should be in the form provided at 'Form F-4'.

16.9 **MSMEs (Micro, Small and Medium Enterprises) registered under NSIC/ Udyog Aadhar/DIC Only are exempted from submission of EMD. In order to avail the exemption in EMD in case of Consortium/ JV, all the members of the Consortium/ JV should be registered as MSME Vendors under NSIC/ Udyog Aadhaar Category/DIC.**

Note: Incase of extension(s) of last due date of the Tender submission, the latest extension issued shall be considered as the final due date of Tender submission and accordingly the Earnest Money Deposit validity should be calculated and sufficed. The validity of the submitted EMD need to be revised by respective bidders, in case the bids are already submitted prior to the last due date of the initial Tender submission deadline.

17 PRE-BID MEETING

17.1 The Bidder(s) or his designated representative are invited to attend a "Pre-Bid Meeting" which will be held at address specified in Bid Information Sheet under Section - I, Invitation for Bids, IFB. It is expected that a bidder shall not depute more than 02 representatives for the meeting.

17.2 Purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.

17.3 Text of the questions raised and the responses given, together with any responses prepared after the meeting, will be uploaded on TCIL website against the Tender. Any modification of the Contents of Tender Documents listed in "ITB: Clause-7.1", that may become necessary as a result of the Pre-Bid Meeting shall be made by the Employer/ Owner exclusively through the issue of an Addendum/ Corrigendum pursuant to "ITB: Clause-9", and not through the minutes of the Pre-Bid Meeting.

17.4 Non-attendance of the Pre-Bid Meeting will not be a cause for disqualification of Bidder.

18 FORMAT AND SIGNING OF BID

18.1 The First and Last Pages of original tender documents including amendments, clarifications if any shall be typed or written in indelible ink [in the case of copies, photocopies are also acceptable] and shall be signed by a person or persons duly authorized to sign on behalf of the Bidder (as per POA). The name and position held by each person signing, must be typed or printed below the signature.

19 ZERO DEVIATION AND REJECTION CRITERIA

19.1 **ZERO DEVIATION :** Deviation to terms and conditions of Tender Documents may lead to rejection of bid. Employer/ Owner will accept bids based on terms & conditions of Tender Documents only. Bidder may note Employer/ Owner will determine the substantial

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 18 of 54</u>	<u>Signature of Bidder</u>

responsiveness of each bid to the Tender Documents pursuant to provision contained in clause 29 of ITB. For purpose of this, a substantially responsive bid is one which conforms to all terms and conditions of the Tender Documents without deviations or reservations. Employer's/ Owner's determination of a bid's responsiveness is based on the content of the bid itself without recourse to extrinsic evidence. Employer/ Owner reserves the right to raise technical and/ or commercial query(ies), if required. The response(s) to the same shall be in writing, and no change in the price(s) or substance of the bids shall be sought, offered or permitted. The substance of the bid includes but not limited to prices, completion, scope, technical specifications, etc. Bidders are requested to not to take any deviation.

19.2 **REJECTION CRITERIA:** Notwithstanding the above, deviation to the following clauses of Tender document shall lead to summarily rejection of Bid:

- (a) Eligibility Criteria including General, Technical and Financial Qualifying Requirements
- (b) Firm Price
- (c) Tender Processing Fees and Earnest Money Deposit
- (d) Tender Document Fees, if applicable
- (e) Specifications & Scope of Work
- (f) Schedule of Rates (SOR)/ Price Schedule (PS)
- (g) Duration/ Period of Contract/ Completion schedule
- (h) Period of Validity of Bid
- (i) Warrantee/Guarantee/ Defect Liability Period
- (j) Arbitration/ Resolution of Dispute/ Jurisdiction of Court
- (k) Force Majeure & Applicable Laws
- (l) Any other condition specifically mentioned in the tender document elsewhere that non-compliance of the clause lead to rejection of bid

Note: Further, it is once again reminded not to mention any condition in the Bid which is contradictory to the terms and conditions of Tender document.

20 **E-PAYMENT**

Employer/ Owner has initiated payments to Suppliers and Contractors electronically, and to facilitate the payments electronically through '**e-banking**'. The successful bidder should give

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>ITB</u> Page 19 of 54	<u>Signature of Bidder</u>

the details of his bank account as per the bank mandate form enclosed at Format F-19 in Section-VI, Sample Forms and Formats of the Tender documents.

[D] - SUBMISSION OF BIDS

21 SUBMISSION, SEALING AND MARKING OF BIDS

- 21.1 Bids shall be submitted through e-tender mode in the manner specified elsewhere in tender document.
- 21.2 Hard Copies (Specific documents only) as mentioned in clause no. 11.I of Section - II, Instructions to Bidders (ITB) of the Tender document shall be submitted in a Sealed Covering Envelope. The Covering Envelope shall have the following Sticker

Offline Tender Document for “Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding”	
Tender Document No.	SECI/C&P/NIT/2017/BDL5MW-2
Last Date of Submission	
Bids Submitted by	(Enter Full name and address of the Bidder)
Authorized Signatory	(Signature of the Authorized Signatory) (Name of the Authorized Signatory) (Stamp of the Bidder)
Bid Submitted to	Solar Energy Corporation of India Limited (A Government of India Enterprise) D - 3, 1 st Floor, Wing - A, Prius Platinum Building District Center, Saket New Delhi - 110 017

21.3 All the bids shall be addressed to the Employer at address specified in the Bid Information Sheet in Section - I, Invitation for Bids (IFB).

21.4 Bids submitted under the name of AGENT/ CONSULTANT/ REPRESENTATIVE/ RETAINER/ ASSOCIATE etc. on behalf of a bidder/ affiliate shall not be accepted.

22 DEADLINE FOR SUBMISSION OF BIDS

22.1 The bids must be submitted through e-tender mode not later than the date and time specified in the Bid Information Sheet in Section - I, Invitation for Bids (IFB).

22.2 The hard copies of required specific documents must be submitted through courier/ registered post/ by hand not later than the date and time specified in the Bid Information Sheet in Section - I, Invitation for Bids (IFB).

22.3 Employer/ Owner may, in exceptional circumstances and at its discretion, extend the deadline for submission of Bids (clause 9 of ITB refers). In which case all rights and obligations of Employer/ Owner and the Bidders, previously subject to the original deadline will thereafter be subject to the deadline as extended. Notice for extension of bid submission date will be uploaded on ETS Portal of TCIL <https://www.tcil-india-electronictender.com> and/ or Employer's website www.seci.co.in.

23 LATE BIDS

23.1 Any bids received after the notified date and time of closing of tenders will be treated as late bids.

23.2 E-tendering system shall close immediately after the deadline for submission of bid and no bids can be submitted thereafter.

23.3 Unsolicited Bids or Bids received to address other than one specifically stipulated in the tender document will not be considered for evaluation/ opening/ award if not received to the specified destination within stipulated date & time.

24 MODIFICATION AND WITHDRAWAL OF BIDS

24.1 Modification and withdrawal of bids shall be as follows: -

The bidder may withdraw or modify its bid after bid submission but before the due date and time for submission as per tender document.

24.2 The modification shall also be prepared, sealed, marked and dispatched in accordance with the provision of the clause 22 of ITB, with the outer and inner envelopes additionally marked modification or withdrawal as appropriate. A withdrawal notice may also be sent by e-mail or fax but followed by a signed confirmation copy post not later than the deadline for submission of bids. No bid shall be modified/ withdrawn after the deadline for submission of bids.

24.3 No bid shall be allowed to be withdrawn/ modified/ substitute in the interval between the deadline for submission of bids and the expiration of the period of bid validity specified by the

bidder on the Bid Form. Withdrawal/ Modification/ Substitution of a bid during this interval shall result in the forfeiture of bidder's EMD pursuant to clause 16 of ITB and rejection of bid.

- 24.4 The latest bid hence submitted shall be considered for evaluation and all other bids shall be considered to be unconditionally withdrawn.
- 24.5 In case after price bid opening the lowest evaluated bidder (L1) is not awarded the job for any mistake committed by him in bidding or withdrawal of bid or modification of bid or varying any term in regard thereof leading to re-tendering, Employer shall forfeit EMD paid by the bidder and such bidders shall be debarred from participation in re-tendering of the same job(s)/ item(s). Further, such bidder will be debarred for a given period as decided by Employer/ Owner after following the due procedure.

25 **EMPLOYER'S RIGHT TO ACCEPT ANY BID AND TO REJECT ANY OR ALL BIDS**

Employer/ Owner reserves the right to accept or reject any Bid, and to annul the Bidding process and reject all Bids, at any time prior to award of Contract, without thereby incurring any liability to the affected Bidder or Bidders or any obligations to inform the affected Bidder or Bidders of the ground for Employer's/ Owner's action. However, Bidder if so desire may seek the reason (in writing) for rejection of their Bid to which Employer/ Owner shall respond quickly.

[E] - BID OPENING AND EVALUATION

26 **BID OPENING**

26.1 ***Unpriced Bid Opening:***

As the case may be, Employer will open bids, in the presence of bidders' designated representatives who choose to attend, at date, time and location stipulated in the BDS. The bidders' representatives, who are present shall sign a bid opening register evidencing their attendance. However the presence of bidder(s) during unpriced bid opening is subjective and will depend on case to case basis against the sole discretion of Employer/ Owner.

26.2 ***Priced Bid Opening:***

- 26.2.1 Employer will open the price bids of those bidders who meet the qualification requirement and whose bids are determined to be technically and commercially responsive.
- 26.2.2 The price bids of those bidders who were not found to be techno-commercially responsive shall not be opened and returned unopened after opening of the price bids of techno-commercially responsive bidders.

27 **CONFIDENTIALITY**

Information relating to the examination, clarification, evaluation, and comparison of Bids, and recommendations for the award of a Contract, shall not be disclosed to Bidders or any other persons not officially concerned with such process. Any effort by a Bidder to influence the

Employer's/ Owner's processing of Bids or award decisions may result in the rejection of the Bidder's Bid and action shall be initiated as per procedure in this regard.

28 CONTACTING THE EMPLOYER/ OWNER

- 28.1 From the time of Bid opening to the time of award of Contract, if any Bidder wishes to contact the Employer/ Owner on any matter related to the Bid, it should do so in writing. Information relating to the examination, clarification, evaluation & recommendation for award shall not be disclosed.
- 28.2 Any effort by the Bidder to influence the Employer/ Owner in the Employer's 'Bid Evaluation', 'Bid Comparison', or 'Contract Award' decisions may result in the rejection of the Bidder's Bid and action shall be initiated as per procedure in this regard.

29 EXAMINATION OF BIDS AND DETERMINATION OF RESPONSIVENESS

- 29.1 The owner's determination of a bid's responsiveness is based on the content of the bid only. Prior to the detailed evaluation of Bids, the Employer will determine whether each Bid: -
- (a) Meets the "Bid Evaluation Criteria" of the Bidding Documents;
 - (b) Has been properly signed;
 - (c) Is accompanied by the required 'Earnest Money Deposit' and 'Tender Processing Fees', if applicable
 - (d) Is substantially responsive to the requirements of the Tender Documents; and
 - (e) Provides any clarification and/ or substantiation that the Employer/ Owner may require to determine responsiveness pursuant to "ITB: Clause-29.2"
- 29.2 A substantially responsive Bid is one which conforms to all the terms, conditions and specifications of the Tender Documents without material deviations or reservations or omissions for this purpose employer defines the foregoing terms below: -
- a) "Deviation" is departure from the requirement specified in the tender documents.
 - b) "Reservation" is the setting of limiting conditions or withholding from complete acceptance of the requirement in the tender documents.
 - c) "Omission" is the failure to submit part or all of the information or documentation required in the tender document.
- 29.3 A material deviation, reservation or omission is one that,
- a) If accepted would,
 - i) Affect in any substantial way the scope, quality, or performance of the job as specified in tender documents.
 - ii) Limit, in any substantial way, inconsistent with the Tender Document, the Employer's rights or the tenderer's obligations under the proposed Contract.
 - b) If rectified, would unfairly affect the competitive position of other bidders presenting substantially responsive bids.

- 29.4 The Employer shall examine all aspects of the bid to confirm that all requirements have been met without any material deviation, reservation or omission.
- 29.5 If a Bid is not substantially responsive, it may be rejected by the Employer and may not subsequently be made responsive by correction or withdrawal of the of material deviation, reservation or omission.

30 **CORRECTION OF ERRORS**

- 30.1 If there is a discrepancy between the unit price and the total price, which is obtained by multiplying the unit price and quantity specified by the Employer, or between subtotals and the total price, the unit or subtotal price shall prevail, and the quantity and the total price shall be corrected. However, in case of items quoted without indicating any quantity or the items for which the quantities are to be estimated by the Bidder, the total price quoted against such items shall prevail. If there is a discrepancy between words and figures, the amount in words will prevail.

The prices of all such item(s) against which the Bidder has not quoted rates/ amount (viz., items left blank or against which '-' is indicated) in the Price Schedules will be deemed to have been included in other item(s).

The subtotal, total price or the total bid price to be identified in Bid Form for this purpose, irrespective of the discrepancy between the amount for the same indicated in words or figures shall be rectified in line with the procedure explained above.

The Bidder should ensure that the prices furnished in various price schedules are consistent with each other. In case of any inconsistency in the prices furnished in the specified price schedules to be identified in Bid Form for this purpose, the Employer shall be entitled to

consider the highest price for the purpose of evaluation and for the purpose of award of the Contract use the lowest of the prices in these schedules.

- 30.2 The amount stated in the bid will be adjusted by the Employer in accordance with the above procedure for the correction of errors. If the bidder does not accept the corrected amount of bid, its bid will be rejected.

31 CONVERSION TO SINGLE CURRENCY FOR COMPARISON OF BIDS

All bids submitted must be in the currency specified at clause 14 of ITB.

32 EVALUATION OF BIDS & E REVERSE AUCTION

Bid shall be evaluated as per evaluation criteria mentioned below on the total cost including GST. The Employer shall only use the criteria and methodology indicated in the Tender documents. No other criteria/ methodology shall be permitted.

32.1 Evaluation of Techno - Commercial Part (First Envelope)

The Employer will carry out a detailed evaluation of the bids of the qualified bidders in order to determine whether the technical aspects are in accordance with the requirements set forth in the Bidding Documents. In order to reach such a determination, the Employer will examine the information supplied by the bidders, pursuant to ITB Clause 11, and other requirements in the Bidding Documents, taking into account the following factors:

- overall completeness and compliance with the Technical Specifications and Drawings to the bid. The bid that does not meet minimum acceptable standards of completeness, consistency and detail may be rejected for non-responsiveness.
- compliance with the time schedule
- any other relevant technical factors that the Employer/ Owner deems necessary or prudent to take into consideration.
- any deviations to the commercial and contractual provisions stipulated in the Tender Documents.
- details furnished by the bidder in response to the requirements specified in the Tender Documents.

32.2 Opening of Second Envelope by Employer

The Second Envelope i.e., Price Part of only those Bidders shall be opened who are determined as having submitted substantially responsive bids and are ascertained to be qualified to satisfactorily perform the Contract, pursuant to ITB Clause 32.1. A negative determination of the bids pursuant to ITB Clause 32.1 the Second Envelope submitted by such

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 25 of 54</u>	<u>Signature of Bidder</u>

bidders shall be sent to archive unopened and the EMD shall be returned as per the Tender provisions.

The prices and details as filled up in Electronic Form by the bidder and opened during the bid opening and recorded in the Bid Opening Statement would not be construed to determine the relative ranking amongst the Bidders, or the successful Bidder, and would not confer any right or claim whatsoever on any Bidder. The successful Bidder (also referred to as the L1 Bidder) shall be determined as per the provisions of this Section - II and considered for award of contract as provided in ITB.

Bids not opened and read out at bid opening shall not be considered for evaluation, irrespective of the circumstances except bids received by Employer within due date and time of bid submission deadline.

32.3 Evaluation of Financial Part (Second Envelope)

32.3.1 The Employer will examine the Price Parts (Second Envelopes) to determine whether they are complete, whether any computational errors have been made, whether the documents have been properly signed, and whether the bids are generally in order.

32.3.2 The Price Part containing any deviations and omissions from the contractual and commercial conditions and the Technical Specifications which have not been identified in the First Envelope are liable to be rejected.

32.3.3 Arithmetical errors will be rectified in line with Clause no. 30 of ITB.

32.3.5 The comparison shall also include the impact of Goods & Service Tax (GST) in line with the provisions of the Bidding Documents.

32.3.6 The Employer's comparison will also include the costs resulting from application of the evaluation procedures described below:

a. The Evaluated Bid Value (EBV) shall be calculated using the following method:

- i. EPC/ LSTK Contract Value i.e., Total sum of the price comprising of FOR destination basis Supply including Transportation for delivery at site and Insurance of all Equipments and materials including mandatory spares and any other supplies specified in the Contract Documents, providing all services i.e. unloading, storage, handling at site, Civil works, Erection, Installation, Testing and Commissioning, performance testing in respect of all the equipment's supplied and

any other services specified in the Contract Documents including Goods & Service Tax as per the Technical Scope of Work.

- ii. Net Present Value (NPV) of O&M Contract Price including GST for the entire period in years to be calculated at a discounting rate as mentioned in the Section - VIII, Schedule of Rates (SOR) of the Tender documents..

The exact format for sharing the base price and all Goods & Service Tax is attached in SOR 1& SOR 2.

SOR -1 is the Schedule and Breakup of Lump sum Price (Supply, Service and NPV of O&M) of the Tender. SOR -2 comprises of the yearly Breakup of the NPV of O&M price for 5 years period.

Bidder to mention the NPV of O&M amount for total 5 years in CELL NO I 21 OF SOR-1 which should match with the NPV of O&M amount for total 5 years in CELL NO J 18 of SOR 2.

- b. **Evaluated Bid Value (EBV)** = (1) EPC/ LSTK Price as quoted by the bidder + (2) O & M Contract Price for the entire period in years on NPV basis.

Detailed Taxation Break up for this purpose is also given in the SOR-1 & SOR-2 of the SOR for the EBV calculation purpose.

Discounting Rate for NPV calculation considered is 9.08%

32.4 Evaluation of Price Bid

32.4.1 Following factors shall be considered for evaluation of Price Bids:

- Total Evaluated Bid Values (TEBV) for all the Bidders shall be compared to determine the lowest Total Evaluated Bid Value (TEBV) as given under SOR- 1 Format of Schedule of Rates & the lowest (L1) evaluated Bid as such, will be selected for the Notification of Award (NOA) subject to the successful bidder selected after E-Ra (Clause 32.4.2).
- The mentioned Total Evaluated Bid Value will be considered up to 2 decimal places only.
- Bidder with Total lowest EBV shall be L-1, Bidder with Second lowest EBV shall be L-2 & so on subject to the successful bidder selected after E-Ra (Clause 32.4.2)
- The Total Evaluated Bid Value shall be inclusive of Goods & Service Tax (GST) as quoted by the bidder. However, the award shall be placed excluding of GST as against the taxation bifurcation submitted by the successful bidder in the SOR format.
- SOR -1 is the Schedule and Breakup of Lump sum Price (Supply, Service and NPV of O&M) of the Tender. SOR -2 comprises of the yearly Breakup of the NPV of O&M price for 5 years period.

- f) Bidder to mention the NPV of O&M amount for total 5 years in CELL NO I 21 of SOR-1 which should match with the NPV of O&M amount for total 5 years in CELL NO J 18 of SOR 2.
- g) In case of any variation of the total NPV of O&M price, the NPV of O&M amount for total 5 years mentioned at CELL NO J 18 of SOR 2 will be considered for evaluation purpose.

32.4.2 Procedure for e- Reverse Auction (e-RA):

1. The e-auctioning shall be conducted on www.tcil-india-electronictender.com. E-Auctioning shall be carried out on the day as intimated by SECI to the eligible bidders.
2. After financial bid evaluation, the bidders shall be shortlisted in the ascending order of price bid quoted. Of this top 50% of the bidders starting from the LI Bid subject to minimum of 3 bids shall only be eligible for e-RA. If the price bid quoted is same for two or more bidders, then all the bidders with same price bid shall be considered of equal rank/ standing in the order. The e-RA shall be conducted as follows:
 - At least one week prior to e-RA, an advance intimation regarding the date and time of the e-RA will be sent to by email to all bidders whose technical bids have been opened and found to be qualified. However from this advance intimation it shall not be construed by the bidders that they have been shortlisted for e-RA. Further at least two hours before the schedule start time of e-Auctioning, a system generated email for invitation for e-Auctioning will be sent to all those bidders only who have been shortlisted based on the criteria mentioned.
 - Shortlisted bidders for e-Auctioning will be able to login into the TCIL website of eauctioning 15 minutes before the start time of e-auctioning.
 - At the start of e-auctioning process, the bid along with the list of short listed bidders shall be displayed with their pseudo names as their first round bid along with the NPV value of O&M quotation per year submitted and calculated as per SoR. The auctioning shall be on the EPC price quoted by the bidder only. The NPV value of O&M price Bid shall remain fixed.
 - The minimum decrement step for e-Auctioning is **Rs. 50,000/- (INR Fifty Thousand only)** in EPC Price bid (Firm value of the financial proposal as the sum of individual bid value of supply, erection and civil works including GST), i.e. each decrement shall be in multiples of Rs. Rs. 50,000/- (INR Fifty Thousand only). The multiples of bid decrement are 1, 2, 3...10, 15, 20, 25...50,100 (as per TCIL ETS). Further to the above, the prospective bidders may also note that whatever the discount offered by the bidder during the e – RA process on the price quoted by them during financial bid, the same shall be applied proportionately to the prices of items quoted by them initially in the financial bid, for making payments if such bidder is concluded as the successful bidder for the Notification of Award (NOA).

- L2, L3, L4.... LN Bidders have to mandatorily apply their decrements suitably so as to beat the L1 price in the first go itself, else system will not accept their respective Bids. However, at no stage, increase in EPC price will be permissible.
 - During E- Auctioning, no revision in total price for which a bidder is considered qualified after evaluation of Technical Bid is allowed.
 - The initial auctioning period will be of one (01) hour with a provision of auto extension by eight minutes from the scheduled/ extended closing time if any fresh bid is received in last eight minutes of auctioning period or extended auctioning period. If no valid bid is received during last eight minutes of auctioning period or extended auctioning period, then the e-auctioning process will get closed.
3. Following information will be displayed in the bidder's bidding window:
- First round EPC and O&M price as their start price initially and thereafter last quoted EPC Price
 - The O&M price (mentioned with NPV) shall remain fixed throughout the process.
 - The list of last quoted EPC price (i.e. last Bid Value) along with NPV of O&M price (fixed) of all bidders with their Pseudo Identities and their time of quote.
4. Selection of Successful Bidders
- The bidders shall be selected in the ascending order with lowest quoted Total Price (EPC + NPV of O&M price) (being L1).
- a. The final price arrived by adding the EPC price (as a result of e-auctioning process) and the NPV of O&M price (fixed during e-auctioning).
 - b. The bidder with lowest sum quoted at the end of E-Auctioning will be considered L1.
 - c. In case of tie in Total Price (i.e. the sum of their last quoted discounted EPC price and the NPV of O&M price), among two or more bidders being the same at the end of e-Reverse Auction, they will be considered in the chronological order of their last bid with preference to the bidder who has quoted his last bid earlier than others.
 - d. In the above case, if the time of quote also become exactly same among the bidders at a tie, then the ranking among these bidders shall be done as follow:
 - The bidder who has quoted lowest Total Price in their Price BID before commencement of E-Auction shall be considered as L-1.
 - If there is also a tie among any of these bidders, then L-1 will be the bidder who has the highest average annual turnover as per the documents submitted as a part of their bid.

5. At the end of selection process, a Notification of Award (NOA) will be issued to the successful bidder (L1).
6. In all cases, SECI's decision regarding selection of bidder through E-Auctioning or other-wise based on First Round quotation or annulment of tender process shall be final and binding on all participating bidders.

32.4.3 Other Instructions

- For further instructions, the vendor should visit the home-page of the portal www.tcil-india-electronictender.com and go to the User-Guidance Centre.

- The help information provided through 'ETS User-Guidance Centre' is available in three categories –

Users intending to Register / First-Time Users, Logged-in users of Buyer organizations, and Logged-in users of Supplier organizations. Various links (including links for User Manuals) are provided under each of the three categories.

- Important Note: It is strongly recommended that all authorized users of Supplier organizations should thoroughly peruse the information provided under the relevant links, and take appropriate action. This will prevent hiccups, and minimize teething problems during the use of ETS.

33 COMPENSATION FOR EXTENDED STAY

NOT APPLICABLE

34 PURCHASE PREFERENCE

NOT APPLICABLE

[F] - NOTIFICATION OF AWARD/ LETTER OF INTENT/ CONTRACT AGREEMENT

35 AWARD

Subject to "ITB: Clause-29", Employer/ Owner will award the Contract to the successful Bidder whose Bid has been determined to be substantially responsive and has been determined as the lowest provided that bidders, is determined to be qualified to satisfactorily perform the Contract.

36 NOTIFICATION OF AWARD/ LETTER OF INTENT/ LETTER OF ALLOCATION

- 36.1 Prior to the expiry of 'Period of Bid Validity', Employer/ Owner will notify the successful bidder in writing, in the form of "Notification of Award (NOA)"/ "Letter of Intent (LOI)"/ "Letter of

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 30 of 54	Signature of Bidder

Allocation (LOA)" through e-mail/ courier/ registered post, that his Bid has been accepted. The notification of award will constitute the formation of the Contract.

- 36.2 Contract Period shall commence from the date of "Notification of Award"/ "Letter of Intent"/ "Letter of Allocation" or as mentioned in the Notification of Award/ Letter of Intent/ Letter of Allocation. The "Notification of Award"/ "Letter of Intent"/ "Letter of Allocation" will constitute the formation of a Contract, until the Contract has been effected pursuant to signing of Contract as per "ITB: Clause-37".
- 36.3 The of "Notification of Award (NOA)"/ "Letter of Intent (LOI)"/ "Letter of Allocation (LOA)" shall be issued to successful bidder in duplicate. The successful bidder is required to return its duplicate copy duly signed and stamped on each page including all the Appendix, Annexures as a token of acknowledgement within 15 (Fifteen) days from the date of its issuance.
- 36.4 Incase the successful bidder fails to acknowledge the acceptance of "Notification of Award (NOA)"/ "Letter of Intent (LOI)"/ "Letter of Allocation (LOA)" as mentioned above vide clause no. 36.3, same will be treated as a case of non-responsiveness & default and Employer/ Owner may take suitable action to get the project successfully executed
- 36.5 In case of Non-response/acceptance to the NOA or CA or non-submission of timely Performance Security by the successful bidder, SECI at its sole discretion may take appropriate actions by annulling the entire Tendering process.

37 SIGNING OF CONTRACT AGREEMENT

- 37.1 The successful Bidder/ Contractor shall be required to execute the 'Contract Agreement' on a 'non-judicial stamp paper' of appropriate value [cost of the 'stamp-paper' shall be borne by the successful Bidder/ Contractor] and of 'state' specified in Bidding Data Sheet (BDS) only, within '30 [Thirty] days' of issuance of the "Notification of Award [NOA]"/ "Letter of Intent [LOI]"/ "Letter of Allocation [LOA]".
- 37.2 Incase the successful bidder fails to execute the 'Contract Agreement' as mentioned above vide clause no. 37.1, same will be treated as a case of non-responsiveness & default and Employer/ Owner may take suitable action to get the project successfully executed. Same may constitute sufficient grounds for the forfeiture of EMD.
- 37.3 In case of Non-response/acceptance to the NOA or CA or non-submission of timely Performance Security by the successful bidder, SECI at its sole discretion may take appropriate actions by annulling the entire Tendering process.

CONTRACT PERFORMANCE SECURITY

38.1 Against EPC/ LSTK Contract & Comprehensive Annual maintenance contract (CAMC) of the project, within 30 (Thirty) days from the issuance of the Notification of Award/ Letter of Intent/ Letter of Allocation from Employer/ Owner, the successful bidder shall furnish an unconditional and irrevocable Contract Performance Security in accordance with Special Conditions of the Contract. The Contract Performance Security shall be in the form of either Banker's Cheque or Demand Draft or Bank Guarantee and shall be in the currency of the Contract and will be issued in the name of the owner as **"Bharat Dynamics Limited, Telangana"**. The Contract Performance Security shall be for an amount equal to specified in Special Conditions of Contract (SCC) towards faithful performance of the contractual obligations, performance of equipment and shall cover entire Contract. The validity of Contract Performance Security shall be in conjunction with the provisions mentioned under Section - V, Special Conditions of Contract (SCC).

38.2 Bank Guarantee towards Contract Performance Security shall be from any scheduled bank as specified in the List of Banks enclosed at Form F-22, Section - VI, Sample Forms and Formats of Tender documents or a branch of an International Bank situated in India and registered with Reserve Bank of India as scheduled foreign bank in case of Indian bidder. However, in case of Bank Guarantees from Banks other than the Nationalized Indian banks, the Bank must be a commercial Bank having net worth in excess of INR 500 Crores and a declaration to this effect should be made by such commercial bank either in the Bank Guarantee itself or separately on its letterhead. This Bank Guarantee shall be valid for a period in conjunction with the provisions mentioned under Section - V, Special Conditions of Contract (SCC).

The Contract Performance Security may also be submitted in the form of 'crossed payee accounts only' Demand Draft/ Banker's Cheque in favour of **"Bharat Dynamics Limited, Telangana"**.

38.3 In case of default or failure of the successful bidder to comply with the requirements of this article shall constitute sufficient grounds for the annulment of the award and forfeiture of the EMD.

38.4 ***In case of default or failure of the Contractor to comply with the requirements of any of the Obligations covered under this Tender Document and/ or Contract Agreement shall constitute sufficient grounds for forfeiture of the Contract Performance Security.***

38.5 The Contract Performance Security has to cover the entire contract value including extra works/ services also. As long as the Contract Performance Security submitted at the time of award takes care the extra works/ services executed and total executed value are within the awarded contract price, there is no need for additional Contract Performance Security. As soon as the total executed value is likely to burst the ceiling of awarded contract price, the contractor should furnish additional Contract Performance Security on proportionate basis of

the percentage as defined in the Special Conditions of Contract (SCC) for the additional amount in excess to the original contract value.

- 38.6 Further, any delay beyond 30 (Thirty) days shall attract interest @ 1.25% per month on the total Contract Performance Security amount, calculated on pro-rata basis accordingly. Employer/ Owner at its sole discretion may cancel the Contract Agreement/ NOA/ LOI/ LOA & forfeit 100% of EMD, in case Contract Performance Security is not submitted within 40 (Forty) days from issuance of NOA/ LOI/ LOA. However, total project completion period shall remain same. Part Security shall not be accepted.
- 38.7 If the Contractor/ Sub-Contractor or their employees or the Contractor's agents and representatives shall damage, break, deface or destroy any property belonging to the Employer or others during the execution of the Contract, the same shall be made good by the Contractor at his own expenses and in default thereof, the Engineer-in-Charge may cause the same to be made good by other agencies and recover expenses from the Contractor (for which the certificate of the Engineer-in-Charge shall be final).
- 38.8 All compensation or other sums of money payable by the Contractor to the Employer/ Owner under terms of this Contract may be deducted from or paid by the encashment or sale of a sufficient part of his Contract Performance Security or from any sums which may be due or may become due to the Contractor by the Employer/ Owner of any account whatsoever and in the event of his Contract Performance Security being reduced by reasons of any such deductions or sale of aforesaid, the Contractor shall within 10 (Ten) days thereafter make good in cash, bank drafts as aforesaid any sum or sums which may have been deducted from or realized by sale of his Contract Performance Security, or any part thereof. No interest shall be payable by the Employer for sum deposited as Contract Performance Security.

39 PROCEDURE FOR ACTION IN CASE CORRUPT/ FRAUDULENT/ COLLUSIVE/ COERCIVE PRACTICES

- 39.1 Procedure for action in case Corrupt/ Fraudulent/ Collusive/ Coercive Practices is enclosed at Annexure-I along with this ITB document.

- 39.2 Annexure-I deliberates in detail the all consequences pertaining to clause no. 39.

39.3 NON-APPLICABILITY OF ARBITRATION CLAUSE IN CASE OF BANNING OF VENDORS/ SUPPLIERS/ CONTRACTORS/ BIDDERS/ CONSULTANTS INDULGED IN FRAUDULENT/ COERCIVE PRACTICES

Notwithstanding anything contained contrary in GCC and other "CONTRACT DOCUMENTS", in case it is found that the Vendors/ Suppliers/ Contractors/ Bidders/ Consultants indulged in fraudulent/ coercive practices at the time of bidding, during execution of the contract etc., and/ or on other grounds as mentioned in Employer's/ Owner's "Procedure for action in case Corrupt/ Fraudulent/ Collusive/ Coercive Practices" (Annexure-I), the contractor/ bidder shall be banned (in terms of aforesaid procedure) from the date of issuance of such order by Employer/ Owner, to such Vendors/ Suppliers/ Contractors/ Bidders/ Consultants.

The Vendor/ Supplier/ Contractor/ Bidder/ Consultant understands and agrees that in such cases where Vendor/ Supplier/ Contractor/ Bidder/ Consultant has been banned (in terms of

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 33 of 54	Signature of Bidder

aforesaid procedure) from the date of issuance of such order by Employer/ Owner, such decision of Employer/ Owner shall be final and binding on such Vendor/ Supplier/ Contractor/ Bidder/ Consultant and the 'Arbitration clause' in the GCC and other "CONTRACT DOCUMENTS" shall not be applicable for any consequential issue/ dispute arising in the matter.

40 PUBLIC PROCUREMENT POLICY FOR MICRO AND SMALL ENTERPRISES (MSEs)

- 40.1 As per the Public Procurement Policy for Micro and Small Enterprise (MSEs) order 2012, issued vide Gazette Notification number 503, dated 23.03.2012 by Ministry of Micro, Small and Medium Enterprise of Govt. of India, and specific to this tender, MSEs must be registered

with any of the following agencies/ bodies shall be exempted from Tender Processing Fees and EMD submission upon production of valid registration certificate.

- (i) District Industries Centre (DIC)
- (ii) National Small Industries Corporation (NSIC)
- (iii) Udyog Aadhaar Memorandum

MSEs participating in the tender must submit the certificate of registration with any one of the above agencies. The registration certificate issued from any of the above agencies must be valid as on close date of the tender.

The MSEs, who have applied for registration or renewal of registration with any of the above agencies/ bodies, but have not obtained the valid certificate as on close date of the tender, are not eligible for exemption/ preference.

40.2 In case of JV/ Consortium, in order to avail the exemption to Tender Processing Fees and Earnest Money Deposit (EMD), all the members of JV/ Consortium should be registered under any of the Categories mentioned under clause 40.1 above.

40.3 In case the bidder is falling under above category, the bidder shall submit the documentary evidence satisfying the same.

If the bidder does not provide the above confirmation or appropriate document or any evidence, then it will be presumed that they do not qualify for any preference admissible in the tender.

41 AHR ITEMS

NOT APPLICABLE

42 RISK OF REJECTION

Any Conditional Bid will straight away run into risk of rejection.

43 INCOME TAX & CORPORATE TAX

43.1 Income tax deduction shall be made from all payments made to the contractor as per the rules and regulations in force and in accordance with the Income Tax Act prevailing from time to time.

43.2 Corporate Tax liability, if any, shall be to the contractor's account.

43.3 TDS under GST as may be applicable shall be deducted as per law of Government of India in vogue.

43.4 MENTIONING OF PAN NO. IN INVOICE/ BILL

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>ITB</u> <u>Page 35 of 54</u>	<u>Signature of Bidder</u>

As per CBDT Notification No. 95/2015 dated 30.12.2015, mentioning of PAN no. is mandatory for procurement of goods/ services/ works/ consultancy services exceeding INR 2 Lacs per transaction.

Accordingly, supplier/ contractor/ service provider/ consultant should mention their PAN no. in their invoice/ bill for any transaction exceeding INR 2 Lacs. As provided in the notification, in case supplier/ contractor/ service provider/ consultant do not have PAN no., they have to submit declaration in Form 60 along with invoice/ bill for each transaction.

Payment of supplier/ contractor / service provider/ consultant shall be processed only after fulfilment of above requirement

44. SETTLEMENT OF DISPUTES BETWEEN GOVERNMENT DEPARTMENT AND ANOTHER AND ONE GOVERNMENT DEPARTMENT AND PUBLIC ENTERPRISE AND ONE PUBLIC ENTERPRISE AND ANOTHER

In the event of any dispute or difference relating to the interpretation and application of the provisions of the contracts, such dispute or difference shall be referred by either party for Arbitration to the sole Arbitrator in the Department of Public Enterprises to be nominated by the Secretary to the Government of India in-charge of the Department of Public Enterprises. The Arbitration and Conciliation Act, 1996 shall not be applicable to arbitrator under this clause. The award of the Arbitrator shall be binding upon the parties to the dispute, provided, however, any party aggrieved by such award may make a further reference for setting aside or revision of the award to the Law Secretary, Department of Legal Affairs, Ministry of Law & Justice, Government of India. Upon such reference the dispute shall be decided by the Law Secretary or the Special Secretary/ Additional Secretary, when so authorized by the Law Secretary, whose decision shall bind the Parties finally and conclusively. The parties to the dispute will share equally the cost of arbitration as intimated by the Arbitrator.

45 DISPUTE RESOLUTION (PROVISION REGARDING APPLICABLE LAWS AND SETTLEMENT OF DISPUTES)

- 45.1 Unless otherwise specified, the matters where decision of the Engineer-in-Charge is deemed to be final and binding as provided in the Agreement and the issues/ disputes which cannot be mutually resolved within a reasonable time, all disputes shall be settled in accordance with the Conciliation Rules.
- 45.2 Any dispute(s)/ difference(s)/ issue(s) of any kind whatsoever between/ amongst the Parties arising under/ out of/ in connection with this contract shall be settled in accordance with the laid down rules.
- 45.3 In case of any dispute(s)/ difference(s)/ issue(s), a Party shall notify the other Party (ies) in writing about such a dispute(s)/ difference(s)/ issue(s) between/ amongst the Parties and that such a Party wishes to refer the dispute(s)/ difference(s)/ issue(s) to Conciliation. Such Invitation for Conciliation shall contain sufficient information as to the dispute(s)/ difference(s)/

issue(s) to enable the other Party(ies) to be fully informed as to the nature of the dispute(s)/ difference(s)/ issue(s), the amount of monetary claim, if any, and apparent cause(s) of action.

- 45.4 Conciliation proceedings commence when the other Party(ies) accept(s) the invitation to conciliate and confirmed in writing. If the other Party(ies) reject(s) the invitation, there will be no conciliation proceedings.
- 45.5 If the Party initiating conciliation does not receive a reply within thirty days from the date on which he/she sends the invitation, or within such other period of time as specified in the invitation, he/she may elect to treat this as a rejection of the invitation to conciliate. If he/she so elects, he/she shall inform the other Party(ies) accordingly.
- 45.6 Where Invitation for Conciliation has been furnished, the Parties shall attempt to settle such dispute(s) amicably under Part-III of the Indian Arbitration and Conciliation Act, 1996. It would be only after exhausting the option of Conciliation as an Alternate Dispute Resolution Mechanism that the Parties hereto shall go for Arbitration. For the purpose of this clause, the option of 'Conciliation' shall be deemed to have been exhausted, even in case of rejection of 'Conciliation' by any of the Parties.
- 45.7 The cost of Conciliation proceedings including but not limited to fees for Conciliator(s), Airfare, Local Transport, Accommodation, cost towards conference facility etc. shall be borne by the Parties equally.
- 45.8 The Parties shall freeze claim(s) of interest, if any, and shall not claim the same during the pendency of Conciliation proceedings. The Settlement Agreement, as and when reached/agreed upon, shall be signed between the Parties and Conciliation proceedings shall stand terminated on the date of the Settlement Agreement.

===== X =====

Annexure-I

PROCEDURE FOR ACTION IN CASE CORRUPT/ FRAUDULENT/ COLLUSIVE/ COERCIVE PRACTICES

A Definitions:

- A.1 “Corrupt Practice” means the offering, giving, receiving or soliciting, directly or indirectly, anything of value to improperly influence the actions in selection process or in contract execution.

“Corrupt Practice” also includes any omission for misrepresentation that may mislead or attempt to mislead so that financial or other benefit may be obtained or an obligation avoided.

- A.2 “Fraudulent Practice” means and include any act or omission committed by an agency or with his connivance or by his agent by misrepresenting/ submitting false documents and/ or false

information or concealment of facts or to deceive in order to influence a selection process or during execution of contract/ order.

- A.3 “Collusive Practice amongst bidders (prior to or after bid submission)” means a scheme or arrangement designed to establish bid prices at artificial non-competitive levels and to deprive the Employer of the benefits of free and open competition.
- A.4 “Coercive practice” means impairing or harming or threatening to impair or harm directly or indirectly, any agency or its property to influence the improperly actions of an agency, obstruction of any investigation or auditing of a procurement process.
- A.5 “Vendor/ Supplier/ Contractor/ Consultant/ Bidder” is herein after referred as “Agency”
- A.6 “Appellate Authority” shall mean Committee consisting of Authorized Representatives of Employer/ Owner.
- A.7 “Competent Authority” shall mean the authority, who is competent to take final decision for Suspension of business dealing with an Agency/ (ies) and Banning of business dealings with Agency/ (ies) and shall be the “Committee” concerned.
- A.8 “Allied Agency” shall mean all the concerns within the sphere of effective influence of banned/ suspended agencies. In determining this, the following factors may be taken into consideration:
- (a) Whether the management is common;
 - (b) Majority interest in the management is held by the partners or directors of banned/ suspended firm.
 - (c) substantial or majority shares are owned by banned/ suspended agency and by virtue of this it has a controlling voice.
- A.9 “Investigating Agency” shall mean any department or unit of Employer/ Owner investigating into the conduct of Agency/ party and shall include the Vigilance Department of the Employer/

Owner, Central Bureau of Investigation, State Police or any other agency set up by the Central or state government having power to investigate.

B Actions against bidder(s) indulging in corrupt /fraudulent/ collusive/ coercive practice

B.1 Irregularities noticed during the evaluation of the bids:

If it is observed during bidding process/ bids evaluation stage that a bidder has indulged in corrupt/ fraudulent/ collusive/ coercive practice, the bid of such Bidder (s) shall be rejected and its Earnest Money Deposit (EMD) shall be forfeited.

Further, such agency shall be banned for future business with Employer/ Owner for a period specified in para B 2.2 below from the date of issue of banning order.

B.2 Irregularities noticed after award of contract

(i) During execution of contract:

If an agency, is found to have indulged in corrupt/ fraudulent/ collusive/ coercive practices, during execution of contract, the agency shall be banned for future business with Employer/ Owner for a period specified in para B 2.2 below from the date of issue of banning order.

The concerned order(s)/ contract(s) where corrupt/ fraudulent/ collusive practices are observed, shall be suspended with immediate effect by Engineer-in-Charge (EIC)/ Employer/ Owner whereby the supply/ work/ service and payment etc. will be suspended. The action shall be initiated for putting the agency on banning.

After conclusion of process, the order(s)/ contract(s) where it is concluded that such irregularities have been committed shall be terminated and Contract Performance Security submitted by agency against such order(s)/ contract(s) shall also be forfeited. The amount that may have become due to the contractor on account of work already executed by him shall be payable to the contractor and this amount shall be subject to adjustment against any amounts due from the contractor under the terms of the contract.

No risk and cost provision will be enforced in such cases.

(ii) After execution of contract and during Defect liability period (DLP)/ Warranty/ Guarantee Period:

If an agency is found to have indulged in corrupt/ fraudulent/ collusive/ coercive practices, after execution of contract and during DLP/ Warranty/ Guarantee Period, the

agency shall be banned for future business with Employer/ Owner for a period specified in para B 2.2 below from the date of issue of banning order.

Further, the Contract Performance Security submitted by agency against such order(s)/ contract(s) shall be forfeited.

(iii) After expiry of Defect liability period (DLP)/ Warranty/ Guarantee Period

If an agency is found to have indulged in corrupt/ fraudulent/ collusive/ coercive practices, after expiry of Defect liability period (DLP)/ Warranty/ Guarantee Period, the agency shall be banned for future business with Employer/ Owner for a period specified in para B 2.2 below from the date of issue of banning order.

B.2.2 Period of Banning

Banning period shall be reckoned from the date of banning order and shall be for a period as may be decided by the Employer/ Owner based on specific case basis. However, minimum banning shall be for 06 (Six) months from the date of banning order.

In exceptional cases where the act of vendor/ contractor is a threat to the National Security, the banning shall be for indefinite period.

C Effect of banning on other ongoing contracts/ tenders

- C.1 If an agency is put on Banning, such agency should not be considered in ongoing tenders/ future tenders.
- C.2 However, if such an agency is already executing other order(s)/ contract(s) where no corrupt/ fraudulent/ collusive/ coercive practice is found, the agency should be allowed to continue till its completion without any further increase in scope except those incidental to original scope mentioned in the contract.
- C.3 If an agency is put on the Banning List during tendering and no irregularity is found in the case under process:
 - C.3.1 after issue of the enquiry/ bid/ tender but before opening of Technical bid, the bid submitted by the agency shall be ignored.
 - C.3.2 after opening Technical bid but before opening the Price bid, the Price bid of the agency shall not be opened and EMD submitted by the agency shall be returned to the agency.
 - C.3.3 after opening of price, EMD made by the agency shall be returned; the offer of the agency shall be ignored & will not be further evaluated. If the agency is put on banning list for fraud/

mis-appropriation of facts committed in the same tender/ other tender where errant agency emerges as the lowest (L1), then such tender shall also be cancelled and re-invited.

D. Procedure for Suspension of Bidder

D.1 Initiation of Suspension

Action for suspension business dealing with any agency/(ies) shall be initiated by C & P Department when

- (i) Vigilance Department based on the fact of the case gathered during investigation by them recommend for specific immediate action against the agency.
- (ii) Vigilance Department based on the input from Investigating agency, forward for specific immediate action against the agency.
- (iii) Nonperformance of Vendor/ Supplier/ Contractor/ Consultant leading to termination of Contract/ Order.

D.2 Suspension Procedure:

- D.2.1 The order of suspension would operate initially for a period not more than six months and is to be communicated to the agency and also to Vigilance Department. Period of suspension can be extended with the approval of the Competent Authority by one month at a time with a ceiling of six months pending a conclusive decision to put the agency on banning list.
- D.2.2 During the period of suspension, no new business dealing may be held with the agency.
- D.2.3 Period of suspension shall be accounted for in the final order passed for banning of business with the agency.
- D.2.4 The decision regarding suspension of business dealings should also be communicated to the agency.
- D.2.5 If a prima-facie, case is made out that the agency is guilty on the grounds which can result in banning of business dealings, proposal for issuance of suspension order and show cause notice shall be put up to the Competent Authority. The suspension order and show

cause notice must include that (i) the agency is put on suspension list and (ii) why action should not be taken for banning the agency for future business from Employer/ Owner.

The competent authority to approve the suspension will be same as that for according approval for banning.

D 3 Effect of Suspension of business:

Effect of suspension on other on-going/ future tenders will be as under:

- D.3.1 No enquiry/ bid/ tender shall be entertained from an agency as long as the name of agency appears in the Suspension List.
- D.3.2 If an agency is put on the Suspension List during tendering:
 - D.3.2.1 after issue of the enquiry/ bid/ tender but before opening of Technical bid, the bid submitted by the agency shall be ignored.
 - D.3.2.2 after opening Technical bid but before opening the Price bid, the Price bid of the agency shall not be opened and EMD submitted by the agency shall be returned to the agency.
 - D.3.2.3 after opening of price, EMD made by the agency shall be returned; the offer of the agency shall be ignored & will not be further evaluated. If the agency is put on Suspension list for fraud/ mis-appropriation of facts conducted in the same tender/ other tender where errant agency emerges as the lowest (L1), then such tender shall also be cancelled and re-invited.
- D.3.3 The existing contract(s)/ order(s) under execution shall continue.
- D.3.4 Tenders invited for procurement of goods, works and services shall have provision that the bidder shall submit a undertaking to the effect that (i) neither the bidder themselves nor their allied agency/(ies) are on banning list of Employer/ Owner or the Ministry of New

& Renewable Energy (ii) bidder is not banned by any Government Department/ Public Sector.

Annexure-II

ADDENDUM TO INSTRUCTIONS TO BIDDERS (INSTRUCTION FOR PARTICIPATION IN E-TENDER)

1. General

Special Instructions (for e-Tendering).

Submission of Online Bids is mandatory for this Tender.

This section contains detailed instructions regarding bid submission procedure under e-tendering system (e-tender portal). Bidders are required to read the following instructions in addition to various instructions mentioned elsewhere in the bid document for e-tendering. The instructions mentioned herein related to bid submission procedure shall supersede and shall prevail over the conditions enumerated elsewhere in the bid/ tender document.

Bidders who wish to participate in e-tenders must go through the 'instructions in respect of e-Tendering essentially covering security settings required for bidder's PC/ Laptop, uploading and checking the status of digital signature in the bidder's PC/ Laptop, obtaining unique login ID and password, re-setting the password, downloading of Tender document and uploading of Offer/ Bid etc.

2. About E-Tender Portal (Web)

Solar Energy Corporation of India Limited (SECI) has adopted a secured and user friendly e-tender system enabling bidders to Search, View, Download tender document(s) directly from the ETS Portal of TCIL (<https://www.tcil-india-electronictender.com>) a Government of India Undertaking (referred hereunder as "E-Tender Portal") and also enables the bidders to participate and submit online prices directly in the e-tender portal or uploading of SOR/ Price Schedule (Price Bid) in note and attachment folder, as applicable, and technical bids in

secured and transparent manner maintaining absolute confidentiality and security throughout the tender evaluation process and award.

3. Pre-requisite for participation in bidding process

The following are the pre-requisite for participation in e-Tendering Process:

3.1 PC/ Laptop with Windows OS, Internet Explorer

Bidder must possess a PC/ Laptop with Windows 7 professional operating system and Internet Explorer 8 or 9 for hassle free bidding. Bidder is essentially required to effect the security settings as defined in the portal.

3.2 Internet Broadband Connectivity

The Bidder must have a high-speed internet connectivity (preferably Broadband) to access TCIL's e-Tender Portal for downloading the Tender document and uploading/ submitting the Bids.

3.3 A valid e-mail Id of the Organization/ Firm

3.4 E-Tendering is a new methodology for conducting Public Procurement in a transparent and secured manner. Now, the Government of India has made e-tendering mandatory. Suppliers/ Vendors will be the biggest beneficiaries of this new system of procurement. For conducting electronic tendering, SECI has decided to use the portal <https://www.tcil-india-electronictender.com> through TCIL, a Government of India Undertaking. This portal is based on the world's most 'secure' and 'user friendly' software from Electronic Tender®. A portal

built using Electronic Tender's software is also referred to as Electronic Tender System® (ETS).

Benefits to Suppliers are outlined on the Home-page of the portal.

4. Tender Bidding Methodology under Sealed Bid System of Single Stage Two Envelop:

4.1 Broad Outline of Activities from Bidder's Perspective:

- 4.1.1 Procure a Digital Signing Certificate (DSC)-Class II and above.
- 4.1.2 Register on Electronic Tendering System® (ETS)
- 4.1.3 Create Marketing Authorities (MAs), Users and assign roles on ETS
- 4.1.4 View Notice Inviting Tender (NIT) on ETS
- 4.1.5 For this tender -- Assign Tender Search Code (TSC) to a MA
- 4.1.6 Download Official Copy of Tender Documents from ETS
- 4.1.7 Clarification to Tender Documents on ETS

- a) Query to SECI (Optional)
- b) View response to queries posted by SECI

- 4.1.8 Bid-Submission on ETS
- 4.1.9 Respond to SECI Post-TOE queries
- 4.1.10 Participate in reverse auction if invited

For participating in this tender online, the following instructions are to be read carefully. These instructions are supplemented with more detailed guidelines on the relevant screens of the ETS.

4.2 Digital Certificates

For integrity of data and authenticity/ non-repudiation of electronic records, and to be compliant with IT Act 2000, it is necessary for each user to have a Digital Certificate (DC), also referred to as Digital Signature Certificate (DSC), of Class II or above, issued by a Certifying Authority (CA) licensed by Controller of Certifying Authorities (CCA) [refer <http://www.cca.gov.in>]

4.3 Registration

To use the Electronic Tender portal <https://www.tcil-india-electronictender.com>, vendors need to register on the portal. Registration of each organization is to be done by one of its senior persons who will be the main person coordinating for the e-tendering activities. In ETS terminology, this person will be referred to as the Super User (SU) of that organization. For further details, please visit the website/ portal, and click on the 'Supplier Organization' link under 'Registration' (on the Home Page), and follow further instructions as given on the site. Pay Annual Registration Fee as applicable.

After successful submission of Registration details and payment of Annual Registration Fee, please contact TCIL/ ETS Helpdesk (as given below), to get your registration accepted/ activated.

Important Note:

1. Interested bidders have to download official copy of the RfS/ Tender & other documents after login into the ETS Portal of TCIL (<https://www.tcil-india-electronictender.com>). If the official copy of the documents is not downloaded from ETS Portal of TCIL within the specified period

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 47 of 54	Signature of Bidder

of downloading of RfS/ Tender and other documents, bidder will not be able to participate in the tender.

2. To minimize teething problems during the use of ETS (including the Registration process), it is recommended that the user should peruse the instructions given under 'ETS User-Guidance Centre' located on ETS Home Page, including instructions for timely registration on ETS. The instructions relating to 'Essential Computer Security Settings for Use of ETS' and 'Important Functionality Checks' should be especially taken into cognizance.

Please note that even after acceptance of your registration by the Service Provider, to respond to a tender you will also require time to complete activities related to your organization, such as creation of users, assigning roles to them, etc.

TCIL/ ETS Helpdesk	
Telephone/ Mobile	Customer Support: +91-11- 26202699 (Multiple Telephone lines) / 26241790 (Monday to Friday from 10 AM to 6 PM except Government Holidays) Emergency Mobile Numbers: +91-9868393792, 9868393775, 9868393717
Email-ID	ets_support@tcil-india.com

5. Some Bidding Related Information for this Tender (Sealed Bid)

The bid shall be submitted by the Bidder under "Single Stage - Two Envelope" procedure of bidding. Under this procedure, the bid submitted by the Bidder in two envelopes - First Envelope (also referred to as Techno - Commercial Part) and Second Envelope (also referred to as Price Part) shall comprise of the following documents:

5.1 Hard Copy

Hard copy of the bid shall comprise of following documents/ programmed file-Attachments to be submitted in sealed envelope, as part of First Envelope. **The envelope shall bear {the name of Tender, the Tender No. and the words 'DO NOT OPEN BEFORE' (due date & time)}.**

Contact Persons Name: Shri Sandeep Kumar

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>ITB</u> <u>Page 48 of 54</u>	<u>Signature of Bidder</u>

- (a) Original Non-Refundable Tender Processing Fee as per clause no. 05 of ITB
- (b) Original Non-Refundable Cost of Tender Document, if applicable
- (c) 'Covering Letter' on Bidder's 'Letterhead' (in Original) clearly specifying the enclosed contents, as per 'Form F-0'
- (d) EMD in original as per Clause 16 of ITB as per 'Form F-4' or as prescribed.
- (e) In case of Bid from Joint Venture, the Joint Venture Agreement (as per 'Form F-17') and Power of Attorney for Joint Venture Agreement (as per 'Form F-17A') (both in Original)
- (f) In case of Bid from Consortium, the Consortium Agreement (as per 'Form F-18') and Power of Attorney for Consortium Agreement (as per 'Form F-18A') (both in Original)
- (g) Power of Attorney for authorized signatory in non-judicial stamp paper (as per 'Form F-24')
- (h) Copy of Board Resolution
- (i) The Pass-Phrase to decrypt the relevant Bid-Parts (for both Techno-Commercial and Financial) in separate sealed envelopes before the start date and time of the Tender Opening Event (TOE)

Bidder shall also upload the scanned copies of all the above mentioned original documents as Programmed File Attachments during online Bid Submission as a part of First envelope.

"Bidder should explicitly note that no hard copies are to be submitted as a part of Second envelope".

5.2 Soft Copy

Soft copy of the bid shall comprise of following documents to be uploaded on the TCIL portal <https://www.tcil-india-electronictender.com> as per provisions therein.

(A) As part of First Envelope

- I. The Electronic Form of the bid for First Envelope (Techno-Commercial), as available on the TCIL portal, shall be duly filled.
- II. Programmed file - Attachments (as detailed against clause no. 11.I) and Bid Form for first envelope.
- III. Certificate of Incorporation
- IV. 'Bidder's General Information', as per 'Form F-1'.
- V. Shareholding Certificate (as per 'Form F-23')
- VI. 'No Deviation Confirmation', as per 'Form F-6'
- VII. 'Bidder's Declaration regarding Banning, Liquidation etc.', as per 'Form F-7'

- VIII. 'Bidders Experience as per 'Form F-13'
- IX. E-Banking Format (as per 'Form F-19')
- X. Documents in accordance with the "Qualifying Requirements (QR)" establishing the qualification
- XI. Document showing annual turnover for the financial years as required in Qualifying Requirements (QR) such as annual reports, profit and loss account, net worth etc. along with information as sought in enclosed Format F-16
- XII. Tender Document. (Only First and Last Pages of Original Tender Document duly sealed and signed/ digitally signed and all pages of amendments and clarifications to Tender Documents duly sealed and signed/ digitally signed by the Authorized Signatory).
- XIII. Sealed and signed/ digitally signed, Blank copies **(WITHOUT PRICES)** of SOR-1 & SOR-2 mentioning **"QUOTED"** for all the items of Respective SORs.

Bidder should explicitly note that no prices are to be mentioned in any of the SOR here & only need to write "QUOTED".

(B) As part of Second Envelope

- (a) The Electronic Form of the bid for Second Envelope (Price - Part), as available on the TCIL portal, shall be duly filled. "Termed as **ELECTRONIC FORM**"
- (b) Main Price Bid comprising of SOR-1 and SOR-2 of the Price Schedule (available in Section - VIII, SOR), duly Completed, sealed and signed/ digitally signed shall be uploaded. "Termed as **MAIN BID**"

5.3 Special Note on Security and Transparency of Bids

Security related functionality has been rigorously implemented in ETS in a multidimensional manner. Starting with 'Acceptance of Registration by the Service Provider', provision for security has been made at various stages in Electronic Tender's software. Specifically, for Bid Submission, some security related aspects are outlined below:

As part of the Electronic Encrypted™ functionality, the contents of both the 'Electronic Forms' and the 'Main-Bid' are securely encrypted using a Pass-Phrase created by the Bidder himself. Unlike a 'password', a Pass-Phrase can be a multi-word sentence with spaces between words (e.g. I love this World). A Pass-Phrase is easier to remember, and more difficult to break. It is mandatory that a separate Pass-Phrase be created for each Bid-Part. This method of bid-encryption does not have the security and data-integrity related vulnerabilities which are inherent in e-tendering systems which use Public-Key of the specified officer of a Buyer organization for bid-encryption. Bid-encryption in ETS is such that the Bids cannot be decrypted before the Public Online Tender Opening Event (TOE), even if there is connivance

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 50 of 54</u>	<u>Signature of Bidder</u>

between the concerned tender-opening officers of the Buyer organization and the personnel of e-tendering service provider.

CAUTION: All bidders must fill Electronic Form™ for each bid-part sincerely and carefully, and avoid any discrepancy between information given in the Electronic Form™ and the corresponding Main-Bid.

If any variation is noted between the price mentioned in the Electronic Form™ and the Main Bid (Refer Clause No. 5.2 B for the definitions of Electronic Form and Main Bid), the price mentioned in the Main Bid shall prevail.

In case of any discrepancy between the values mentioned in figures and in words, the value mentioned in words will prevail.

The bidder shall make sure that the Pass-Phrase to decrypt the relevant Bid-Part is submitted into the 'Time Locked Electronic Key Box (EKB)' after the deadline of Bid Submission and before the commencement of the Online TOE of Technical Bid. The process of submission of this Pass-Phrase in the 'Time Locked Electronic Key Box' is done in a secure manner by first encrypting this Pass-Phrase with the designated keys provided by the Employer.

Additionally, the bidder shall make sure that the Pass-Phrase to decrypt the relevant Bid-Part is submitted to Employer in a sealed envelope before the start date and time of the Tender Opening Event (TOE).

There is an additional protection with SSL Encryption during transit from the client-end computer of a Supplier organization to the e-tendering server/ portal.

5.4 Other Instructions

For further instructions, the vendor should visit the home-page of the portal <https://www.tcil-india-electronictender.com>, and go to the User-Guidance Centre

The help information provided through 'ETS User-Guidance Centre' is available in three categories – Users intending to Register/ First-Time Users, Logged-in users of Buyer organizations, and Logged-in users of Supplier organizations. Various links (including links for User Manuals) are provided under each of the three categories.

Important Note: It is strongly recommended that all authorized users of Supplier organizations should thoroughly peruse the information provided under the relevant links, and take appropriate action. This will prevent hiccups, and minimize teething problems during the use of ETS.

5.5 SIX CRITICAL DO'S AND DON'TS FOR BIDDERS

Specifically, for Supplier organizations, the following 'SIX KEY INSTRUCTIONS for BIDDERS' must be assiduously adhered to:

1. Obtain individual Digital Signing Certificate (DSC or DC) of Class II or above well in advance of your tender submission deadline on ETS.
2. Register your organization on ETS well in advance of the important deadlines for your first tender on ETS viz 'Date and Time of Closure of Procurement of Tender Documents' and 'Last

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB <u>Page 51 of 54</u>	<u>Signature of Bidder</u>

Date and Time of Receipt of Bids'. Please note that even after acceptance of your registration by the Service Provider, to respond to a tender you will also require time to complete activities related to your organization, such as creation of users, assigning roles to them, etc.

3. Get your organization's concerned executives trained on ETS well in advance of your first tender submission deadline on ETS
4. Submit your bids well in advance of tender submission deadline on ETS (There could be last minute problems due to internet timeout, breakdown, etc)
5. It is the responsibility of each bidder to remember and securely store the Pass-Phrase for each Bid-Part submitted by that bidder. The bidders are required to submit correct, valid and operative Pass-Phrase to decrypt either Technical Bid Part or Financial Bid Part in a separate sealed envelope before due date and time of submission of bid. In the event, the bids are not opened with the pass-phrase submitted by bidder, Employer may ask for re-submission/ clarification for correct pass-phrase. If bidder fails to submit correct pass-phrase immediately as requested by Employer, the Tender Processing Fee and Tender Document Fee, if applicable, shall be forfeited and bid shall not be opened, as EMD shall be refunded. No request on this account shall be entertained by Employer/ Owner.
6. Bids will be made available for opening during the Online Public Tender Opening Event (TOE) 'ONLY IF' the status pertaining Overall Bid-Submission is 'COMPLETE'. For the purpose of record, the bidder can generate and save a copy of 'Final Submission Receipt'. This receipt can be generated from 'Bid-Submission Overview Page' only if the status pertaining overall Bid-Submission' is 'COMPLETE'

5.6 NOTE:

While the first three instructions mentioned above are especially relevant to first-time users of ETS, the fourth, fifth and sixth instructions are relevant at all times.

6. Content of Bid

6.1 Un-Priced Bid

The Un-Priced Bid (i.e. Part I - Technical Bid, refer ITB of tender for details) to be uploaded using Link "TECHNICAL DOCUMENT". ***Bidders are advised to not upload duly filled Schedule of Rates (SOR)/ Price Schedule (PS) at this link.***

Before the bid is uploaded, the bid comprising of all relevant documents mentioned in the tender document should be digitally signed in accordance with the Indian IT Act 2000. If any

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>ITB</u> <u>Page 52 of 54</u>	<u>Signature of Bidder</u>

modifications are required to be made to a document thereafter the modified documents shall be again digitally signed before uploading.

Bidders are required to upload all Tender forms and supporting documents which form part of the bid/ tender in the Collaboration Folder (C-Folder) under tender document of e-tender portal.

Uploading the documents relevant to bid before the bid submission date and time is the sole responsibility of the bidder.

The complete bid (each page) shall be continuously numbered in sequence, from start till end i.e. 1, 2, 3... n. The bid shall be uploaded along with proper index and indicating page numbers against each category of documents. A sample is suggested as under:

Sub-folder in C-Folder	Documents	Page nos. (for ref.)
1. INDEX	Index	1 to a
2. TENDER DOC	Tender Document, Corrigendum etc.	a+1 to b
3. B.E.C	BEC documents (including order, completion/ execution certificate, balance sheet, etc.)	b+1 to c
4. UN-PRICED COMMERCIAL	Un-priced Commercial offer/bid	c+1 to d
5. EMD/POA	Scanned copy of EMD/POA	d+1 to e
6. FORMATS	Formats of tender duly filed-in, signed and stamped and other	e+1 to f
7. TENDER FEE	Scanned copy of Tender Fee/ Integrity Pact (I.P.)	f+1 to f
8. OTHERS	Any other document	g+1 to n

The above shall ensure that there are no missing documents and traceability of relevant section is ensured.

Note:

- Bidder may save/ store the bid documents in the PC/ Laptop before submitting the bid into in e-tender portal.
- Bidder is required to fill up the price(s)/ rate(s) strictly in the Schedule of Rate (SOR)/ Price Schedule (PS) attached with the tender.

Inadvertently, if a document is uploaded in Collaboration Folder (C Folder) by the bidders, such document can be deleted by the bidder and can be replaced by a digitally signed new/ modified document prior to due date & time.

Un-priced techno-commercial bid document should be placed in the private area earmarked in the C-folder of Tender Document in e-tender portal.

6.2 Priced Bid

The Priced Bid (i.e. Part II - Price Bid, refer ITB for details) to be uploaded using Link given under TCIL portals & and NOT using link "TECHNICAL DOCUMENT". **Bidders are advised**

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ITB Page 53 of 54	Signature of Bidder

not to upload any other documents and same shall be ignored. For detailed instructions, refer tender document and instructions as given above.

Employer/ Owner shall not be responsible for any failure on the part of the bidder in submission of Priced Bid.

Instructions mentioned under “PRICE BID [Online]” shall be applicable in case Bidders have been asked to quote their prices on-line directly in the TCIL's e-tender portal in addition to uploading of scanned copy of SOR/ PS or only the on-line price submission in the portal, as the case may be.

7 Submission of documents

Bidders are requested to upload small sized documents preferably (upto 20 MB) at a time to facilitate easy uploading into e-tender portal. Employer/ Owner shall not be responsible in case of failure of the bidder to upload documents/ bids within specified time of tender submission.

8 Last date for submission of bids

System does not allow for submission or modification of bids beyond the deadline for bid submission. However, if the bidder for some reason intends to change the bid already entered, he may change/ revise the same on or before the last date and time of submission. The system time displayed on TCIL's e-tender webpage shall be final and binding on the bidders for all purposes pertaining to various events of the subject tender and no other time shall be taken into cognizance.

Bidders are advised in their own interest to ensure that bids are uploaded in e-tender system well before the closing date and time of bid.

9 Internet connectivity

If bidders are unable to access TCIL's e-tender portal or Bid Documents, the bidders may please check whether they are using proxy to connect to internet or their PC is behind any firewall and may contact their system administrator to enable connectivity. Please note that Port SSL/ 443 should be enabled on proxy/firewall for HTTPS connectivity. Dial-up/ Broad band internet connectivity without Proxy settings is another option.



SECTION - III

BID DATA SHEETS (BDS)

BID DATA SHEETS (BDS)

The following bid specific data for the Plant and Equipment to be procured shall amend and/ or supplement the provisions in the Section - II, Instruction to Bidders (ITB)

Sl. No.	ITB Clause Ref. No.	Bid Data Details
1.	ITB 1.1	The Employer is: Solar Energy Corporation of India Limited, D - 3, 1st Floor, Wing - A, Religare Building, District Centre Saket, New Delhi - 110 017, India Kind Attn.: General Manager (C & P) / Manager (C & P) Telephone Nos.: - 0091-(0)11-71989256/71989290 Fax No.: - 0091-(0)11-71989243 E-mail: - contracts@seci.co.in The Owner is: Bharat Dynamics Limited, Kanchanbagh Hyderabad (Dist.), Telangana(State) - 500058 Kind Attn.: Shri CH Ramesh Babu (AGM) Telephone Nos.: - 0091-(0) 040-24587104/24587124 Fax No.: - 0091-(0) 040-24340464 E mail: tsdkbc.bdl@bdl-india.com
2.	ITB 1.2	The brief Scope of the Tender/ Work is: Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding.
3.	ITB 3.0	Bids from Consortium/ Joint Venture: Allowed
4.	ITB 4.0	Number of Bids per Bidder: Only 01 (One) Bid per bidder are allowed in the Tender Document.
5.	ITB 15.0	Bid Validity: The bid validity period shall be 150 (One Hundred and Fifty) Days from the date of opening of Techno-Commercial Bid (Envelope-I).
6.	ITB 22.2	For hard copies of bid submission purpose, the address of the Employer is: Solar Energy Corporation of India Limited, D - 3, 1st Floor, Wing - A, Religare Building, District Centre Saket, New Delhi - 110 017

Sl. No.	ITB Clause Ref. No.	Bid Data Details
		Kind Attn.: General Manager (C & P) / Manager (C & P) Telephone Nos.: - 0091-(0)11-71989256/ 71989290 Fax No.: - 0091-(0)11-71989243 E-mail: - contracts@seci.co.in
7.	ITB 26.1	The bid opening shall take place at: Solar Energy Corporation of India Limited, D - 3, 1 st Floor, Wing - A, Religare Building, District Centre Saket, New Delhi - 110 017
8.	ITB 35	Award of Contract: Subject to "ITB: Clause-29", the Owner, Bharat Dynamics Limited (BDL) will award the Contract to the successful Bidder whose Bid has been determined to be substantially responsive and has been determined as the lowest (L1) provided that bidder is determined to be qualified to satisfactorily perform the Contract Technically.
9.	ITB 36.1	Prior to the expiry of 'Period of Bid Validity', Employer, Solar Energy Corporation of India Limited, New Delhi will notify the successful bidder in writing, in the form of "Notification of Award (NOA)"/ "Letter of Intent (LOI)"/ "Letter of Allocation (LOA)" through e-mail/ courier/ registered post, that his Bid has been accepted. The notification of award will constitute the formation of the Contract
10.	ITB 37.1	State of which stamp paper is required for Contract Agreement: Telangana



ANNEXURE TO BID DATA SHEET (BDS) QUALIFYING REQUIREMENTS

QUALIFYING REQUIREMENTS (QR)

Qualification of the bidder(s) will be based on meeting the minimum eligibility criteria specified below regarding the Bidder's General Standards, Technical Experience and Financial Position as demonstrated by the Bidder's responses in the corresponding Bid documents. The bid can be submitted by an individual firm or by a Joint Venture of two or more firms. (Specific requirements for Joint Ventures are given under Para 1.4 below).

1.1 GENERAL ELIGIBILITY CONDITIONS

The Bidder should be a body incorporated in India under the Companies Act, 1956 or 2013 including any amendment thereto, Government owned Enterprises who are registered and incorporated in India and engaged in the business of Power/Infrastructure, Limited Liability Partnership Firms, barring Government Department as well as those firms against whom sanction for conducting business is imposed by Government of India and barring those firms with whom business is banned by the Employer.

Proprietorship Firms, Partnership Firms, NGOs, Charitable Trusts, Educational Societies are not allowed to participate in the bidding process (either individually or in Joint Venture/ Consortium). The Bid Processing Fees and EMD are exempted for MSME Vendors/ Developers registered under NSIC/ DIC/ Udyog Aadhaar Category only. As the Proprietorship Firms, Partnership Firms, NGOs, Charitable Trusts, Educational Societies in any form are not allowed to participate in the tendering process, hence forth any Proprietorship Firms, Partnership Firms, NGOs, Charitable Trusts, Educational Societies MSME vendor will also not be eligible to participate in the bidding process (either individually or in Joint Venture/ Consortium)

- 1.1.1 In case the Bidder wishes to incorporate a Project Company, in such case Bidder if selected as a Successful Bidder can incorporate a Project Company. Bidder shall be responsible to get all clearance required/obtained in the name of the Bidding Company transferred in the name of the Project Company.
- 1.1.2 The aggregate equity share holding of the Successful Bidder in the issued and paid up equity share capital of the Project Company shall not be less than fifty-one percent (51%) up to a period of Five (5) years from the date of commissioning of the entire Sanctioned Capacity of the Project Developer.
- 1.1.3 Affiliation shall mean a company that either directly or indirectly controls or is controlled by or is under common control with a Bidding Company. Control means the ownership by one company of at least 26% (Twenty Six Percent) of the voting rights of the other company.

1.2 TECHNICAL ELIGIBILITY CONDITIONS

The bidder should have experience in development of Ground mounted Solar Projects on Turnkey basis including Supply, Installation and Commissioning of Solar PV Power Plant and Solar Systems of cumulative Capacity not less than **2.5 (Two and half) MW** in last Seven Financial years as on last date of bid opening. However, such Solar PV Power Plant and Solar

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>ANNEXURE TO</u> <u>BDS</u> <u>Page 2 of 6</u>	<u>Signature of Bidder</u>

Systems capacity must have been in satisfactory operation for at least six (06) months from the date of commissioning.

AND

The bidder should have experience in development of Ground mounted Solar Projects on Turnkey basis including design, supply, installation & commissioning of at least 02 (Two) Grid connected Solar PV Power Plant Project having an individual capacity of **01 (One) MW or above** in last Seven Financial years and till last date of bid opening. However, such Solar PV Power Plant and Solar Systems capacity must have been in satisfactory operation for at least six (06) months from the date of commissioning.

The list of projects commissioned at least 6 months prior to Techno-Commercial Bid Opening date, indicating whether the project is grid connected, along with a scanned copy of the Commissioning certificate and Work order / Contract / Agreement/LOI from the Client / Owner shall be submitted in support of Clause 1.2 above.

The Performance Certificate must be issued minimum six (06) months from the date of commissioning. The Performance Certificate/Joint meter reading (JMR) reports shall be issued from any state/ central owned agencies or state power departments or authorized representative of Power offtaker (Discom/Private Power purchaser).

The Bidder shall furnish copies of the following documents along with the Bid in support of meeting the above mentioned BEC:

- a. Certificate of incorporation and MoA/AoA in support of 1.1 above

Note: A job executed by a Bidder for its own plant/ projects cannot be considered as experience for the purpose of meeting the Eligibility Conditions of the tender. Also, the jobs executed for Subsidiary/ Fellow subsidiary/ Holding company will not be considered as experience for the purpose of meeting Eligibility Conditions.

1.3 FINANCIAL ELIGIBILITY CONDITIONS

The Minimum Average Annual Turnover (MAAT) of the bidder in the last three financial years (i.e. FY 2014-2015, 2015-2016 and 2016-17) should be **INR 13,25,00,000/- (Indian Rupees Thirteen Crores and Twenty five Lacs only)**. In case the audited annual accounts for the year 2016-17 are not available with the bidder, Minimum Average Annual Turnover shall be considered for the average of its last three preceding years (i.e. FY 2013-14, 2014-2015, and 2015-2016). **MAAT shall mean Revenue from Operations as incorporated in the profit & loss account excluding other income, e.g. sale of fixed assets.** This must be the individual Company's turnover and not that of any group of Companies. A summarized sheet of average turn over certified by a practicing CA/Statutory Auditor should be compulsorily enclosed along with corresponding annual accounts.

AND

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>ANNEXURE TO</u> <u>BDS</u> <u>Page 3 of 6</u>	<u>Signature of Bidder</u>

“Net Worth” of the Bidder shall be calculated as per Company Act 2013. The net worth for the last financial year should be positive.

AND

The bidder should have a minimum Working Capital of **INR 4,40, 00,000/- (Indian Rupees Four Crores and forty Lacs only)** as per the last audited financial statement. If the bidder’s working capital is inadequate, the bidder should supplement this with a letter from the bidder’s bank, having net worth not less than INR 500 Crores, confirming the availability of the line of credit for equal to or more than **INR 4,40, 00,000/- (Indian Rupees Four Crores and forty Lacs only)**.

1.3.1 **Void**

1.3.2 In case the bidder is a holding company, the financial position criteria referred to in clause 1.3 above shall be of that holding company only (i.e. excluding its subsidiary/ group companies). In case bidder is a subsidiary of a holding company, financial position criteria referred to in clause 1.3 above shall be of that subsidiary company only (i.e. excluding its holding company).

1.3.4 The Bidder will provide a copy each of audited annual report of previous three financial years for ascertaining their turnover and Net Worth for the purpose of verification.

1.3.5 The Net Worth of the Bidder as on the last day of the preceding financial year shall not be less than total paid-up share capital.

1.3.6 **Void**

1.3.7 **Void**

1.3.8 The derivation of Net Worth” of the Bidder shall be done as per Company Act 2013.

1.3.9 Other income shall not be considered for arriving at annual turnover.

1.3.10 A scanned copy of certificate of incorporation shall be furnished in the bid (through online mode).

1.3.11 Bidders shall furnish documentary evidence as per the prescribed format (online as well as offline), duly certified by Authorized Signatory and the Statutory Auditor / Practicing Chartered Accountant of the Bidding Company in support of their financial capability.

The Bidder shall furnish the following documentary evidences along with the Bid in support of meeting of above mentioned Financial Eligibility Criteria:

(i) “Details of Financial capability of Bidder” as per format F-16 duly signed and stamped by a Chartered Accountant (format attached).

(ii) Audited financial results i.e. Annual Report including Audited Balance Sheet and Profit &

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	ANNEXURE TO <u>BDS</u> Page 4 of 6	Signature of Bidder

Loss Account Statement for immediate three preceding financial years to meet the above Financial Criteria. In case of tenders having the bid due date up to 30th September of the relevant financial year and audited financial results of immediate 3 preceding financial year being not available, the bidder has an option to submit the audited financial results of three years immediately prior to relevant financial year. Wherever, the bid due date is after 30th September of the relevant financial year, bidder has to compulsorily submit the audited financial results of immediate preceding three financial years.

1.4 JOINT VENTURE CONDITIONS

Incase the bid is submitted by a Joint venture (JV) of two or more firms as partners, they must meet the following requirements: -

- 1.4.1 The Lead partner of the JV shall meet individually not less than 50% of minimum Financial Eligibility Conditions given at para 1.3 above. However, all the JV partners must meet collectively 100% Financial Eligibility Conditions given at para 1.3 above.
- 1.4.2 All the partners of the JV must meet collectively 100% of Technical Eligibility Conditions given at para 1.2 above.
- 1.4.3 The Joint Venture must satisfy collectively the Criterion of clauses 1.2 & 1.3 above for which purpose the relevant figure of average annual turnover and liquid assets/ credit facilities for each of the partners of the JV shall be added together to arrive at Joint Venture total capacity. **The net worth of each Partner of JV should be positive.**
- 1.4.4 A Joint Venture (JV), may or may not be incorporated as a Registered Company.
- 1.4.5 A Joint Venture (JV), if incorporated as a Registered Company, is required to submit EMD and Performance Security in the name of Joint Venture only. In case of Consortium or a JV has not formed a Registered Company, the EMD and Performance Security shall be submitted in the name of Lead Partner only.
- 1.4.6 JV is required to submit Form of Undertaking by the JV Partners (F - 17) and Form of Power of Attorney (F - 17A) as per prescribed formats enclosed in Section - VI (Sample Forms and Formats). Consortium is required to submit Form of Undertaking by the Consortium Partners (F - 18) and Form of Power of Attorney (F - 18A) as per prescribed formats enclosed in Section - VI (Sample Forms and Formats).
- 1.4.7 JV/ Consortium is also required to declare detailed scope of work to be executed by each partner of JV.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>ANNEXURE TO</u> <u>BDS</u> <u>Page 5 of 6</u>	<u>Signature of Bidder</u>

The Employer may assess the capacity and capability of the bidder, to ascertain that the bidder can successfully execute the scope of work covered under the package within stipulated completion period. This assessment shall inter-alia include (i) document verification, (ii) bidder's work/manufacturing facilities visit, (iii) manufacturing capacity, details of works executed, works in hand, anticipated in future & the balance capacity available for the present scope of work, (iv) details of plant and machinery, manufacturing and testing facilities, manpower and financial resources, (v) details of quality systems in place, (vi) past experience and performance, (vii) customer feedback, (viii) banker's feedback etc.

- 1.4.8 In order to avail the benefits of exemptions in JV/ Consortium, all the partners of JV/ Consortium must be MSME Vendors/ Developers registered under NSIC/ Udyog Aadhaar Category only.

Employer/ Owner reserves the right to waive minor deviations if they do not materially affect the capability of the Bidder to perform the contract.



SECTION - IV

GENERAL CONDITIONS OF CONTRACT (GCC)

TABLE OF CONTENTS

[A] DEFINITIONS:

1. DEFINITION OF TERMS

[B] GENERAL INFORMATIONS:

2. GENERAL INFORMATION
 - 2.1.a LOCATION OF SITE
 - 2.1.b ACCESS BY ROAD
 - 2.2 SCOPE OF WORK
 - 2.3 CONSTRUCTION WATER SUPPLY
 - 2.4 CONSTRUCTION POWER SUPPLY
 - 2.5 LAND FOR CONTRACTOR'S FIELD OFFICE, GODOWN & WORKSHOP
 - 2.6 LAND FOR RESIDENTIAL ACCOMODATION

[C] ADDITIONAL GENERAL INSTRUCTION TO BIDDERS:

3. DOCUMENTS
 - 3.1 CORRECTIONS & ERASURES
 - 3.2 WITNESS
 - 3.3 DETAILS OF EXPERIENCE
 - 3.4 LIABILITY OF GOVERNMENT OF INDIA
4. TRANSFER OF TENDER DOCUMENTS
5. RIGHT OF EMPLOYER/OWNER TO ACCEPT OR REJECT TENDER
6. TIME SCHEDULE & PROGRESS REPORTING
7. CONFLICTS OF INTEREST AND BIDDER'S RESPONSIBILITY
8. RETIRED GOVERNMENT OR COMPANY OFFICERS
9. REPRESENTATIVES AND FIELD MANAGEMENT & CONTROLLING/
CO-ORDINATING AUTHORITY
10. NOTE TO SCHEDULE OF RATES
 - 11.1 POLICY FOR TENDERS UNDER CONSIDERATION
 - 11.2 ZERO DEVIATION
12. CLARIFICATION OF TENDER DOCUMENT
13. LOCAL CONDITIONS
14. EXTENSION OF TIME FOR COMPLETION

[D] GENERAL OBLIGATIONS:

- 15.1 PRIORITY OF CONTRACT DOCUMENTS
- 15.2 HEADING & MARGINAL NOTES
- 15.3 SINGULAR AND PLURAL
- 15.4 INTERPRETATION
16. SPECIAL CONDITIONS OF CONTRACT
17. CONTRACTOR TO OBTAIN HIS OWN INFORMATION
18. TIME OF PERFORMANCE
 - 18.1 TIME FOR MOBILIZATION
 - 18.2 TIME SCHEDULE OF CONSTRUCTION
19. FORCE MAJEURE
 - 19.1 CONDITIONS FOR FORCE MAJEURE
 - 19.2 OUTBREAK OF WAR
20. LIQUIDATED DAMAGES (LD)
21. RIGHTS OF EMPLOYER/OWNER TO FORFEIT CONTRACT PERFORMANCE SECURITY

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of
5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant
O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

22. FAILURE BY THE CONTRACTOR TO COMPLY WITH THE PROVISIONS OF THE CONTRACT
23. CONTRACTOR REMAINS LIABLE TO PAY COMPENSATION IF ACTION NOT TAKEN UNDER CLAUSE 29
24. CHANGE IN CONSTITUTION
- 25.1 TERMINATION OF CONTRACT FOR LIQUIDATION, BANKRUPTCY ETC.
- 25.2 TERMINATION OF CONTRACT FOR NON-PERFORMANCE AND SUBSEQUENTLY PUTTING THE CONTRACTOR ON HOLIDAY
26. MEMBERS OF THE EMPLOYER/ OWNER NOT INDIVIDUALLY LIABLE
27. EMPLOYER/OWNER NOT BOUND BY PERSONAL REPRESENTATIONS
28. CONTRACTOR'S OFFICE AT SITE
29. CONTRACTOR'S SUBORDINATE STAFF AND THEIR CONDUCT
30. SUBLETTING OF WORKS
- 30.1 SUB CONTRACTS FOR TEMPORARY WORKS ETC.
- 30.2 LIST OF SUB-CONTRACTORS TO BE SUPPLIED
- 30.3 CONTRACTOR'S LIABILITY NOT LIMITED BY SUB-CONTRACTORS
- 30.4 EMPLOYER/OWNER MAY TERMINATE SUB CONTRACTS
- 30.5 NO REMEDY FOR ACTION TAKEN UNDER THIS CLAUSE
31. POWER OF ENTRY
32. CONTRACTOR'S RESPONSIBILITY WITH OTHER CONTRACTORS & AGENCIES
33. OTHER AGENCIES AT SITE
34. NOTICES
- 34.1 TO THE CONTRACTOR
- 34.2 TO THE EMPLOYER/ OWNER
35. RIGHTS OF VARIOUS INTERESTS
36. PATENTS AND ROYALTIES
37. LIENS
38. DELAYS BY EMPLOYER/OWNER OR HIS AUTHORIZED REPRESENTATIVES
39. PAYMENTS IF CONTRACT IS TERMINATED
40. NO WAIVER OF RIGHTS
41. CERTIFICATE NOT TO AFFECT RIGHT OF EMPLOYER/OWNER AND LIABILITY OF CONTRACTOR
42. LANGUAGES & MEASURES
43. GUARANTEE TEST AND OPERATIONAL ACCEPTANCE AND TRANSFER OF TITLE
44. RELEASE OF INFORMATION
45. OPERATION AND MAINTENANCE
46. COMPLETION OF CONTRACT
47. COMMISSIONING & SPARES

[E] PERFORMANCE OF WORK:

48. EXECUTION OF WORK
49. UNFORESEEN/ DIFFERING SITE CONDITIONS
50. WORK IN MOSOON & DEWATERING
51. CHANGE IN LAWS AND REGULATIONS
52. GENERAL CONDITIONS FOR CONSTRUCTION & ERECTION WORK
53. DESIGN & ENGINEERING
54. DRAWINGS TO BE SUPPLIED BY THE EMPLOYER/OWNER
55. DRAWINGS TO BE SUPPLIED BY THE CONTRACTOR
56. SETTING OUT WORKS
57. GEOLOGICAL DISCOVERIES
58. MATERIALS TO BE SUPPLIED BY CONTRACTOR
59. STORES SUPPLIED BY EMPLOYER/ OWNER
60. CONDITIONS FOR ISSUE OF MATERIAL
61. MATERIALS PROCURED WITH ASSISTANCE OF EMPLOYER/OWNER/

RETURN OF SURPLUS

62. MATERIALS OBTAINED FROM DISMANTLING
63. ARTICLES OF VALUE FOUND
64. DISCREPANCIES BETWEEN INSTRUCTIONS
65. ACTION WHERE NO SPECIFICATION IS ISSUED
66. INSPECTION OF WORKS
67. TESTS FOR QUALITY OF WORKS
68. SAMPLES FOR APPROVAL
69. ACTION & COMPENSATION IN CASE OF BAD WORK
70. SUSPENSION OF WORK
71. EMPLOYER/ OWNER MAY DO PART OF WORK
72. POSSESSION PRIOR TO COMPLETION
73. DEFECTS LIABILITY PERIOD
- 73.1 LIMITATION OF LIABILITY
74. CARE OF WORKS
- 74.1 DEFECTS PRIOR TO TAKING OVER
- 74.2 DEFECTS AFTER TAKING OVER
75. GUARANTEE/ TRANSFER OF GUARANTEE
76. INSTALLATION & TRAINING OF EMPLOYER'S/ OWNER'S PERSONNEL
77. REPLACEMENT OF DEFECTIVE PARTS & MATERIALS
78. INDEMNITY
79. CONSTRUCTIONS AIDS, EQUIPMENTS, TOOLS & TACKLES

[F] CERTIFICATES AND PAYMENTS:

80. SCHEDULE OF RATES AND PAYMENTS
- 80.1 CONTRACTOR'S REMUNERATION
- 80.2 SCHEDULE OF RATES TO BE INCLUSIVE
- 80.3 SCHEDULE OF RATES TO COVER CONSTRUCTION EQUIPMENT, MATERIALS LABOUR ETC.
- 80.4 SCHEDULE OF RATES TO COVER ROYALTIES, RENTS & CLAIMS
- 80.5 SCHEDULE OF RATES TO COVER TAXES AND DUTIES
- 80.6 SCHEDULE OF RATES TO COVER RISK OF DELAY
- 80.7 SCHEDULE OF RATES CANNOT BE ALTERED
81. PROCEDURE FOR MEASUREMENT AND BILLING
- 81.1 BILLING PROCEDURE
- 81.2 SECURED ADVANCE ON MATERIALS
- 81.3 DISPUTE IN MODE OF MEASUREMENT
- 81.4 ROUNDING OF AMOUNTS
82. LUMPSUM IN TENDER
83. RUNNING ACCOUNT PAYMENTS TO BE REGARDED AS ADVANCES
84. NOTICES OF CLAIMS FOR ADDITIONAL PAYMENTS
85. PAYMENT OF CONTRACTOR'S BILLS
86. RECEIPT FOR PAYMENT
87. COMPLETION CERTIFICATE
- 87.1 APPLICATION FOR COMPLETION CERTIFICATE
- 87.2 COMPLETION CERTIFICATE
- 87.3 COMPLETION CERTIFICATE DOCUMENTS
88. FINAL DECISION AND FINAL CERTIFICATE
89. CERTIFICATE AND PAYMENTS ON EVIDENCE OF COMPLETION
90. DEDUCTION FROM CONTRACT PRICE

[G] TAXES AND INSURANCE:

91. GOODS & SERVICE TAX (GST)/TAXES.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 4 of 77</u>	<u>Signature of Bidder</u>

92. GST/ TURNOVER TAX
93. STATUTORY VARIATIONS
94. INSURANCE
 - 94.1 EMPLOYEES STATE INSURANCE ACT
 - 94.2 WORKMEN COMPENSATION AND EMPLOYEE'S LIABILITY INSURANCE
 - 94.3 ACCIDENT OR INJURY TO WORKMEN
 - 94.4 TRANSIT INSURANCE
 - 94.5 AUTOMOBILE
 - 94.6 GENERAL LIABILITY
 - 94.7 ANY OTHER INSURANCE REQUIRED UNDER LAW OR REGULATIONS
95. DAMAGE TO PROPERTY OR TO ANY PERSON OR ANY THIRD PARTY

[H] LABOUR LAWS:

96. LABOUR LAWS & INDEMNITY BOND
97. IMPLEMENTATION OF APPRENTICES ACT 1961
98. CONTRACTOR TO INDEMNIFY THE EMPLOYER/ OWNER
99. HEALTH AND SANITARY ARRANGEMENT FOR WORKERS

[I] APPLICABLE LAWS AND SETTLEMENT OF DISPUTES:

- 100 A & B. ADJUDICATOR & ARBITRATION
101. JURISDICTION

[J] SAFETY CODES:

102. GENERAL
103. SAFETY REGULATIONS
104. FIRST AID AND INDUSTRIAL INJURIES
105. GENERAL RULES
106. CONTRACTOR'S BARRICADES
107. SCAFFOLDING
108. EXCAVATION AND TRENCHING
109. DEMOLITION/ GENERAL SAFETY
110. CARE IN HANDLING INFLAMMABLE GAS
111. TEMPORARY COMBUSTIBLE STRUCTURES
112. PRECAUTIONS AGAINST FIRE
113. EXPLOSIVES
114. MINES ACT
115. PRESERVATION OF PLACE
116. OUTBREAK OF INFECTIOUS DISEASES
117. USE OF INTOXICANTS

Preamble

This Section (Section - IV) of the Bidding Documents [named as General Conditions of Contract (GCC)] provides the performance of the Contractor, payments under the contract or matters affecting the risks, rights and obligations of the parties under the contract. This Section contains provisions that are to be used unchanged unless Section - V [named as Special Conditions of Contract (SCC)] states otherwise as any changes in GCC or any complementary information that may be needed has been shown in SCC. If there is a conflict between the provisions of Section - IV & Section - V, the provisions of Section - V shall prevail.

Bidders may note that the respective rights of the Employer/ Owner and Bidders/ Contractors shall be governed by the Tender Documents/ Contracts signed between the Employer/ Owner and the Contractor for the respective package(s). The provisions of Tender Documents shall always prevail over any other documents in case of contradiction.

Further in all matters arising out of the provisions of this Section - IV and the Section - V of the Tender Documents, the laws of the Union of India shall be the governing laws and courts of Telangana shall have exclusive jurisdiction.

[A] DEFINITIONS

1. Definition of Terms:

- 1.1 In this **TENDER** (as here-in-after defined) the following words and expressions shall have the Meanings hereby assigned to them except where the context otherwise required.
- 1.1.1 **ADJUDICATOR** means the person or persons named as such in the SCC to make a decision on or to settle any dispute or difference between the Employer/Owner and the Contractor.
- 1.1.2 **AFFILIATE** shall mean a company that either directly or indirectly
- controls or
 - is controlled by or
 - is under common control with
- a Bidding Company and "control" means ownership by one company of at least twenty six percent (26%) of the voting rights of the other company.
- 1.1.3 **AFFECTED PARTY** means Employer/Owner or the Contractor whose performance has been affected by an event of Force Majeure
- 1.1.4 **APPLICABLE LAW** means any statute, law, regulation, ordinance, notification, rule, regulation, judgment, order, decree, bye-law, approval, directive, guideline, policy, requirement or other governmental restriction or any similar form of decision of, or determination by, or any interpretation or administration having the force of law in the Republic of India and the State Government, by any Government Authority or instrumentality thereof, whether in effect as of the date of this Contract or thereafter.
- 1.1.5 **APPROVED** shall mean approved in writing including subsequent written confirmation of previous verbal approval and "APPROVAL" means approval in writing including as aforesaid.
- 1.1.6 **APPOINTING AUTHORITY** for the purpose of arbitration shall be the any person so designated by the Employer/ Owner.
- 1.1.7 **ASSOCIATE** means a party who has been conjoined by the Contractor to independently execute a pre-selected part of facilities of the Contract and grant him the associated Contractual rights and obligations, without diluting the overall responsibility of the Contractor in respect of the Facilities under the Contract.
- 1.1.8 **ARBITRATOR** means the person or persons appointed by agreement between the Employer/Owner and the Contractor to make a decision on or to settle any dispute or difference between the Employer/Owner and the Contractor referred to him or her by the parties.
- 1.1.9 **B.I.S.** means specifications of Bureau of Indian Standards (BIS).
- 1.1.10 **BID** means the Techno Commercial and Price Bid submitted by the Bidder along with all documents/ credentials/ attachments/ annexure etc., in response to the Tender, in accordance with the terms and conditions hereof.
- 1.1.11 **BID CAPACITY** means the capacity offered by the bidder in his Bid under Tender Document.

- 1.1.12 **BIDDER** means Bidding Company/ Expert submitting the Bid. Any reference to the Bidder includes Bidding Company/ Experts including its successors, executors and permitted assigns as the context may require.
- 1.1.13 **CAPACITY UTILIZATION FACTOR (CUF)** means the ratio of the actual output from a solar plant over the year (kWh) to the maximum possible output from it for a year (kWh) under ideal conditions.
- CUF = Actual Plant Output in kWh over the year / (Installed Plant Capacity in kW x 365 x 24).
Monthly CUF = Monthly Plant output in kWh / (installed plant capacity in kW x number of days in a month x 24).
- 1.1.14 **CEA** means the Central Electricity Authority.
- 1.1.15 **CHARTERED ACCOUNTANT** means a person practicing in India or a firm whereof all the partners practicing in India as a Chartered Accountant(s) within the meaning of the Chartered Accountants Act, 1949.
- 1.1.16 **COLLABORATOR** or **PARENT COMPANY** means the firms/ corporations who has provided technological support to the manufacturer for establishing production line for the specific Equipment.
- 1.1.17 **COMPANY** means a body incorporated in India under the Companies Act, 1956 or Companies Act, 2013 including any amendment thereto.
- 1.1.18 **CONTRACT** shall mean the Agreement between the Employer/ Owner and the Contractor for the execution of the works including therein all Contract documents.
- 1.1.19 **CONTRACTOR/ SUCCESSFUL BIDDER/ PROJECT DEVELOPER** means the person or the persons, Company or Corporation whose Tender has been accepted by the Employer/ Owner and includes the Contractor's legal representatives his/ her successors and permitted assigns.
- 1.1.20 **CONTRACT DOCUMENTS** mean collectively the Tender Documents, Designs, Drawings, Specification, Schedule of Quantities and Rates, Notification of Award/ Letter of Intent/ Letter of Acceptance and agreed variations if any, and such other documents constituting the Tender and acceptance thereof.
- 1.1.21 **CONTRACTOR'S EQUIPMENT** means all plant, facilities, equipment, machinery, tools, apparatus, appliances or things of every kind required in or for installation, completion and maintenance of Facilities that are to be provided by the Contractor, but does not include Plant and Equipment, or other things intended to form or forming part of the Facilities.
- 1.1.22 **CONTRACTOR'S REPRESENTATIVE** means any person nominated by the Contractor and approved by the Employer/Owner to perform the duties delegated by the Contractor.
- 1.1.23 **CONSULTANT** means Techno-Commercial experts who are the consulting engineer to the Employer/ Owner for this project.
- 1.1.24 **CONSTRUCTION EQUIPMENT** means all appliances/ equipment and things whatsoever nature for the use in or for the execution, completion, operation, or maintenance of the work or temporary works (as here in after defined) but does not include materials or other things intended to form or to be incorporated into the work, or camping facilities.

- 1.1.25 **COMMISSIONING** shall mean pressing into service/ operation of the system including the plant(s), equipment(s), machinery (ies), or any other section or sub-section of installation(s) pertaining to the work of the Contractor after successful testing and trial runs of the same. Commissioning can be either for a completed system or a part of system of a combination of systems or sub-systems and can be performed in any sequence as desired by Employer/ Owner and in a manner established to be made suited according to availability of pre-requisites. Any such readjustments made by Employer/ Owner in performance of Commissioning activity will not be construed to be violating Contract provisions and Contractor shall be deemed to have provided for the same.
- 1.1.26 **COMPLETION** means that the Facilities have been completed operationally and structurally and put in a tight and clean condition and that all works in respect of pre-commissioning of the Facilities has been completed (wherever required, as per Technical Specifications) and Commissioning followed by Trial - Operation has been completed.
- 1.1.27 **COMPLETION CERTIFICATE** shall mean the certificate to be issued when the works have been completed entirely in accordance with Contract Documents.
- 1.1.28 **CONTROLLING OFFICER** means the authorized controlling person/ body of the Contract from respective department appointed by the Employer/ Owner to perform the duties delegated by the Employer/ Owner.
- 1.1.29 **CHANGE ORDER** means an order given in writing by the Engineer-in-Charge/Project Manager to effect additions to or deletion from and alteration in the works.
- 1.1.30 **DAY** means a day of 24 hours from midnight to midnight irrespective of the number of hours worked in that day.
- 1.1.31 **DEFECT LIABILITY PERIOD** in relation to a work/ supply means the specified period from the date of Completion Certificate/ date of receipt of material up to the date of issue of Final Certificate during which the Contractor/ Supplier stands responsible for rectifying all defects/ rejection that may appear in the works executed by the Contractor in pursuance of the Contract and includes warranties against Manufacturing/ Fabrication/ Erection/ Construction defects covering all materials plants, equipment, components and the like supplied by the Contractor, works executed against workmanship defects.
- 1.1.32 **DRAWINGS** shall include maps, plans and tracings or prints or sketches thereof with any modifications approved in writing by the Engineer-in-Charge/Project Manager and such other drawing as may, from time to time, be furnished by the contractor.
- 1.1.33 **EARNEST MONEY DEPOSIT (EMD)** means the unconditional and irrevocable Tender Security in the form of Demand Draft/ Banker's Cheque/ Bank Guarantee to be submitted along with the Bid by the Bidder as prescribed in the Tender.
- 1.1.34 **EMPLOYER** means the Company/ Corporation/ Government Entity, named in the **BDS/ SCC**, who is responsible for getting the Facilities implemented. The Employer may be Owner himself or an agency appointed by the Owner and shall include the legal successors or permitted assigns of the Employer.
- 1.1.35 **ENGINEER/ ENGINEER-IN-CHARGE** shall mean the person designated from time to time by the Employer/ Owner and shall include those who are expressly authorized by him to act for and on his behalf for operation of this Contract.
- 1.1.36 **EFFECTIVE DATE** means the date of issuance of Notification of Award/ Letter of Intent/ Letter of Allocation from which the Time for Completion shall be determined.

- 1.1.37 **EVALUATED BID VALUE (EBV)** means the Evaluated Price derived from the schedule of rates (SOR) as per Section VIII of Tender document.
- 1.1.38 **FACILITY(IES)** means the Plant and Equipment to be supplied and installed, as well as all the Installation Services to be carried out by the Contractor under the Contract.
- 1.1.39 **FINAL CERTIFICATE** in relation to a work means the certificate regarding the satisfactory compliance of various provision of the Contract by the Contractor issued by the Engineer-in- Charge/ Employer after the period of liability is over.
- 1.1.40 **FINAL ACCEPTANCE** means acceptance of Facilities by the Employer/Owner at the end of O&M period, as stated in this NIT, from the date of Commissioning or demonstration of minimum annual CUF whichever comes later which certifies the Contractor's fulfilment of the Contract in respect of Functional and Plant Performance Guarantees of the Facilities
- 1.1.41 **GUARANTEE TEST(S)** means the test(s) specified in the Technical Specifications to be carried out to ascertain whether the Facilities or a specified part thereof is able to attain the Functional Guarantees specified in the Technical Specifications during/ after successful Commissioning followed by Trial - Operation.
- 1.1.42 **GOODS & SERVICE TAX (GST)** is an indirect tax throughout India to replace taxes levied by the central and state governments. Goods & Services Tax is a comprehensive, multi-stage, destination-based tax that will be levied on every value addition.
- 1.1.43 **IEC** means specifications of International Electro-Technical Commission.
- 1.1.44 **INSTALLATION SERVICES** means all those services ancillary to the supply of the Plant and Equipment for the Facilities, to be provided by the Contractor under the Contract; e.g., transportation and provision of marine or other similar insurance, inspection, expediting, site preparation works (including the provision and use of Contractor's Equipment and the supply of all construction materials required), installation, testing, pre-commissioning, commissioning, operations, maintenance, the provision of operations and maintenance manuals, training, etc.
- 1.1.45 **MWp** means Mega-Watt Peak.
- 1.1.46 **kWh** shall mean Kilo-Watt-hour.
- 1.1.47 **LANGUAGE FOR DRAWINGS AND INSTRUCTION** All the drawings, titles, notes, instruction, dimensions, etc. shall be in English Language only.
- 1.1.48 **MNRE** means Ministry of New and Renewable Energy, Government of India.
- 1.1.49 **MOBILIZATION** shall mean establishment of sufficiently adequate infrastructure by the Contractor at Site comprising of construction equipment, aids, tools tackles including setting of site offices with facilities such as power, water, communication etc. establishing manpower organization comprising of Resident Engineers, Supervising Personnel and an adequate strength of skilled, semi-skilled and un-skilled workers, who with the so established infrastructure shall be in a position to commence execution of work at site(s), in accordance with the agreed Time Schedule of Completion of Work. Mobilization shall be considered to have been achieved, if the Contractor is able to establish infrastructure as per Time Schedule, where so warranted in accordance with agreed schedule of work implementation to the satisfaction of Engineer-in-Charge/Project Manager/ Employer/ Owner.
- 1.1.50 **NET-WORTH** shall have same meaning as defined in Company Act 2013 and Amendment, if any.

- 1.1.51 **NOTICE IN WRITING OR WRITTEN NOTICE** shall mean a notice in written, typed or printed characters sent (unless delivered personally or otherwise proved to have been received by the addressee) by registered post to the latest known private or business address or registered office of the addressee and shall be deemed to have been received in the ordinary course of post it would have been delivered.
- 1.1.52 **NOTIFICATION OF AWARD (NOA)** means the official notice issued vide Letter/ E-mail by the Employer notifying the Contractor that his bid has been awarded.
- 1.1.53 **NTP** means Notice to Proceed
- 1.1.54 **OPERATIONAL ACCEPTANCE** means the acceptance by the Employer/Owner of the Facilities (or any part of the Facilities where the Contract provides for acceptance of the Facilities in parts), which certifies the Contractor's fulfilment of the Contract in respect of Functional Guarantees of the Facilities (or the relevant part thereof) after successful Commissioning followed by Trial - Operation.
- 1.1.55 **O & M** means Operation & Maintenance of Commissioned Project/ Work/ Facilities under the Tender.
- 1.1.56 **OWNER** means the Company/ Corporation/ Government Entity, named in the **BDS/ SCC**, who has decided to set up the Facilities and shall include the legal successors or permitted assigns of the Owner.
- 1.1.57 **PARENT COMPANY** means a company that holds at least Fifty Percent (50%) of the paid-up equity capital directly or indirectly in the Bidding Company as the case may be.
- 1.1.58 **PLANT AND EQUIPMENT** means permanent plant, equipment, machinery, apparatus, articles and things of all kinds to be provided and incorporated in the Facilities by the Contractor under the Contract (including the spare parts to be supplied by the Contractor), but does not include Contractor's Equipment.
- 1.1.59 **PRE-COMMISSIONING** means the testing, checking and other requirements specified in the Technical Specifications that are to be carried out by the Contractor in preparation for Commissioning.
- 1.1.60 **PROJECT MANAGER/ OFFICER-IN-CHARGE** means the person appointed by the Employer/ Owner to perform the duties delegated by the Employer/ Owner.
- 1.1.61 **SCC** means the Special Conditions of Contract.
- 1.1.62 **SECI** means Solar Energy Corporation of India Limited, New Delhi (A Government of India Enterprise) under MNRE.
- 1.1.63 **SITE** means the land and other places upon which the Facilities are to be installed, and such other land or places as may be specified in the Contract as forming part of the Site.
- 1.1.64 **SPECIFICATION** shall mean all directions the various Technical Specifications, provisions attached and referred to the Tender Documents which pertain to the method and manner of performing the work or works to the quantities and qualities of the work or works and the materials to be furnished under the Contract for the work or works, as may be amplified or modified by the Employer/ Owner or Engineer-in-Charge/Project Manager during the performance of Contract in order to provide the unforeseen conditions or in the best interests of the work or works. It shall also include the latest

edition of relevant Standard Specifications including all addenda/ corrigenda published before entering into Contract.

- 1.1.65 **SUB-CONTRACTOR** means any person or firm or Company (other than the Principal Contractor) to whom any part of the work has been entrusted by the Principal Contractor, with the written consent of the Engineer-in-Charge/Project Manager.
- 1.1.66 **TAKING OVER** means the Employer's/ Owner's written acceptance of the Facilities under the Contract, after successful Trial - Operation for the specified period in accordance with the Contract
- 1.1.67 **TEMPORARY WORKS** shall mean all temporary works of every kind required in or about the execution, completion or maintenance of works.
- 1.1.68 **TENDER** means the process whereby Employer/ Owner invite bids for Projects/ Works/ Facilities that are submitted within a finite deadline by the Bidder/ Contractor.
- 1.1.69 **TENDER DOCUMENTS/ BIDDING DOCUMENTS** means the entire set of documents vide which Employer/ Owner invite bids for Projects/ Works/ Facilities that are submitted within a finite deadline by the Bidder/ Contractor.
- 1.1.70 **TIME FOR COMPLETION** means the time within which Completion of the Facilities is to be attained in accordance with the specifications, as a whole (or of a part of the Facilities where a separate Time for Completion of such part has been prescribed) and "Taking Over" by the Employer/ Owner is to be attained.
- 1.1.71 **TOTAL CONTRACT PRICE/CONTRACT VALUE** means the sum accepted or the sum calculated in accordance with the prices accepted in Tender and/or the Contract rates as payable to the Contractor for the entire execution and full completion of the work, including change order.
- 1.1.72 **ULTIMATE PARENT COMPANY** shall mean a company which directly or indirectly owns at least twenty-six percent (26%) paid up equity capital in the Bidding Company and/ or in the Financially Evaluated Entity and such Bidding Company and/ or the Financially Evaluated Entity shall be under the direct control or indirectly under the common control of such company.
- 1.1.73 **WEEK** means a period of any consecutive seven days.
- 1.1.74 **WORKING DAY** means any day which is not declared to be holiday or rest day by the Employer/ Owner.

[B] GENERAL INFORMATION

2. General Information

2.1.a Location of Site

The proposed location of Project site(s) is/ are defined in the Scope of work under Technical specifications & also defined under the Special conditions of contract (SCC).

2.1.b Access by Road

Contractor, if necessary, shall build other temporary access roads to the actual site of construction for his own work at his own cost. The Contractor shall be required to permit the use of the roads so constructed by him for vehicles of any other parties who may be engaged on the project site. The Contractor shall also facilitate the construction of any permanent roads should the construction thereof starts while he is engaged on this work. He shall make allowance in his Tender for any inconvenience he anticipates on such account. Non-availability of access roads, railway siding and

railway wagons for the use of the Contractor shall in no case condone any delay in the execution of work nor be the cause for any claim for compensation against the Employer/ Owner.

2.2 Scope of Work

The scope of work is defined in the Section - VII, Scope of Work and Technical Specifications (TS) of the Tender document. In addition, the Contractor shall provide all necessary materials, equipment, labour etc. for the execution and maintenance of the work till completion unless otherwise mentioned in the Tender Document.

2.3 Construction Water Supply

Contractor will have to make his own arrangements for supply of water to his labour camps and for works. All pumping installations, pipe network and distribution system will have to be carried out by the Contractor at his own risk and cost. Alternatively, the Employer/ Owner at his discretion may endeavor to provide water to the Contractor at the Employer's/ Owner's source of supply provided the Contractor makes his own arrangement for the water meter which shall be in custody of the Employer/ Owner and other pipe networks from source of supply and such distribution pipe network shall have prior approval of the Engineer-in-Charge/Project Manager so as not to interfere with the layout and progress of the other construction works. In such case, a separate accounting shall be maintained for billing purpose on monthly basis. However, the Employer/ Owner does not guarantee the supply of water and this does not relieve the Contractor of his responsibility in making his own arrangement and for the timely completion of the various works as stipulated.

2.4 Construction Power Supply

2.4.1 Contractor has to arrange for the construction power supply of their own. However, subject to availability, Employer/ Owner may provide access to the nearest available point in his location for supply power at only one point, from where the Contractor will make his own arrangement for temporary distribution through a temporary energy meter (sealed by Employer/ Owner). All the works will be done as per the applicable regulations with information to the Engineer-in-Charge/Project Manager. The temporary line will be removed forthwith after the completion of work or if there is any hindrance caused to the other works due to the alignment of these lines, the Contractor will re-route or remove the temporary lines at his own cost. The Contractor at his own cost will also provide suitable electric meters, fuses, switches, etc. for purposes of payment to the Employer/ Owner which should be in the custody and control of the Employer/ Owner. The cost of power supply shall be payable to the Employer/ Owner by the contractor. The Employer/ Owner shall not, however, guarantee the supply of electricity nor have any liability in respect thereof. No claim for compensation for any failure or short supply of electricity will be admissible.

2.4.2 It shall be the responsibility of the Contractor to provide and maintain the complete installation on the load side of the supply with due regard to safety requirement at site. All cabling, equipment, installations etc. shall comply in all respects with the latest statutory requirements and safety provisions i.e., as per the Central/ State Electricity Acts and Rules etc. The Contractor will ensure that his equipment and Electrical Wiring etc., are installed, modified, maintained by a licensed Electrician/ Supervisor.

2.4.3 At all times, IEA regulations shall be followed failing which the Employer/ Owner has a right to disconnect the power supply without any reference to the Contractor. No claim shall be entertained for such disconnection. Power supply will be reconnected only after production of fresh certificate from authorized electrical supervisors.

2.4.4 The Employer/ Owner is not liable for any loss or damage to the Contractor's equipment as a result of variation in voltage or frequency or interruption in power supply or other loss to the Contractor arising therefrom.

2.4.5 The Contractor will have to provide and install his own lights and power meters which will be governed as per Central/ State Government Electricity Rules.

2.4.6 In case of damage of any of the Employer's/ Owner's equipment on account of fault, intentional or unintentional on the part of the Contractor, the Employer/ Owner reserves the right to recover the cost of such damage from the Contractor's bill. Cost of HRC Fuses replaced at the Employer's/ Owner's terminals due to any fault in the Contractor's installation shall be to Contractor's account at the rates decided by the Engineer-in-Charge/Project Manager.

2.5 Land for Contractor's Field Office, Godown and Workshop

The Employer/ Owner will, at his own discretion and convenience and for the duration of the execution of the work make available near the site, land for construction of Contractor's Temporary Field Office, godowns, workshops and assembly yard required for the execution of the Contract. The Contractor shall at his own cost construct all these temporary buildings and provide suitable water supply and sanitary arrangement. On completion of the works undertaken by the Contractor, he shall remove all temporary works erected by him and have the Site cleaned as directed by Engineer-in-Charge/Project Manager. If the Contractor shall fail to comply with these requirements, the Employer/Owner may, at the expenses of the Contractor remove such surplus and rubbish materials and dispose off the same as he deems fit and get the site cleared as aforesaid; and Contractor shall forthwith pay the amount of all expenses so incurred and shall have no claim in respect of any such surplus materials disposed off as aforesaid. But the Employer/ Owner reserves the right to ask the Contractor any time during the pendency of the Contract to vacate the land by giving 07 (Seven) day notice on security reasons or on national interest or otherwise. The Contractor shall put up temporary structures as required by them for their office, fabrication shop and construction stores only in the area allocated to them on the project site by the Employer/ Owner or his authorized representative. No tea stalls/ canteens should be put up or allowed to be put up by any Contractor in the allotted land or complex area without written permission of the Employer/ Owner. No unauthorized buildings, constructions or structures should be put up by the Contractor anywhere on the project site. For uninterrupted fabrication work, the Contractor shall put up temporary covered structures at his cost within Area in the location allocated to them in the project site by the Employer/ Owner or his authorized representative. No person except for authorized watchman shall be allowed to stay in the plant area/ Contractor's area after completion of the day's job without prior written intimation to Engineer-in-Charge/Project Manager.

2.6 Land for Residential Accommodation

No Land shall be made available for residential accommodation for staff and labour of Contractor.

[C] ADDITIONAL GENERAL INSTRUCTIONS TO BIDDERS

3. Documents

3.1 Corrections and Erasures: All correction(s) and alteration(s) in the entries of Tender paper shall be signed in full by the bidder with date. No erasure or over writing is permissible.

3.2 Witness: Witness and sureties shall be persons of status and property and their names, occupation and address shall be stated below their signature.

3.3 Details of Experience: The bidder should furnish, along with his Tender, details of previous experience in having successfully completed in the recent past works of this nature, together with the names of Employers/ Owners, location of sites and value of Contract, date of commencement and completion of work, delays if any, reasons of delay and other details along with documentary evidence(s).

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 14 of 77</u>	<u>Signature of Bidder</u>

3.4 Liability of Government of India: It is expressly understood and agreed by and between bidder or/ Contractor and Employer/ Owner that, Employer/ Owner is entering into this agreement solely on its own behalf. In particular, it is expressly understood and agreed that the Government of India has no liabilities, obligations or rights hereunder. It is expressly understood and agreed that Employer/ Owner is an independent legal entity with power and authority to enter into Contracts solely on its own behalf under the applicable Laws of India and general principles of Contract Law. It is further understood and agreed that the Government of India is not and shall not be liable for any acts, omissions, commissions, breaches or other wrongs arising out of the Contract. Accordingly, bidder/ Contractor hereby expressly waives, releases and foregoes any and all actions or claims, including cross claims, impleader claims or counter claims against the Government of India arising out of this Contract and covenants not to sue to Government of India as to any manner, claim, cause of action or thing whatsoever arising of or under this agreement.

4. Transfer of Tender Documents

4.1 Transfer of Tender Documents purchased by one intending bidder to another is not permissible.

5. Right of Employer/Owner to Accept or Reject Tender

5.1 The right to accept the Tender will rest with the Employer/ Owner. The Employer/ Owner, however, does not bind himself to accept the lowest Tender, and reserves to itself the authority to reject any or all the Tenders received without assigning any reason whatsoever. At the option of the Employer/ Owner, the work for which the Tender had been invited, may be awarded to one Contractor or split between more than one bidders, in which case the award will be made for only that part of the work, in respect of which the bid has been accepted. The quoted rates should hold good for such eventualities. Tenders in which any of the particulars and prescribed information are missing or are incomplete in any respect and/ or the prescribed conditions are not fulfilled are liable to be rejected. The Tender containing uncalled for remarks or any additional conditions are liable to be rejected. Canvassing in connection with Tenders is strictly prohibited and Tenders submitted by the Tenderers who resort to canvassing will be liable to rejection.

6. Time Schedule & Progress Reporting

6.1 The work shall be executed strictly as per the Time Schedule specified in Section - V, Special Conditions of Contract (SCC). The period of construction given in Time Schedule includes the time required for mobilization as well as testing, rectifications if any, retesting and completion in all respects to the entire satisfaction of the Engineer-in- Charge.

6.2 A joint program of execution of the work will be prepared by the Engineer-in- Charge and Contractor based on priority requirement of this project. This program will take into account the time of completion mentioned above and the time allowed for the priority works by the Engineer-in- Charge.

6.3 Monthly/ Weekly construction program will be drawn up by the Engineer-in- Charge jointly with the Contractor, based on availability of work fronts and the joint construction program as per above. The Contractor shall scrupulously adhere to these targets/ programs by deploying adequate personnel, construction tools and tackles and he shall also supply himself all materials of his scope of supply in good time to achieve the targets/ programs. In all matters concerning the extent of targets set out in the weekly and monthly programs and the degree of achievements the decision of the Engineer-in- Charge will be final and binding on the Contractor.

6.4 The Contractor shall monitor progress of all the activities specified in the work schedule referred in GCC above, and submit the progress report to the Project Manager as per the Contract Co-ordination procedure.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 15 of 77</u>	<u>Signature of Bidder</u>

- 6.5 The progress report shall be in a form acceptable to the Project Manager/EIC and shall also indicate: (a) percentage completion achieved compared with the planned percentage completion for each activity; and (b) where any activity is behind the program, giving comments and likely consequences and stating the corrective action being taken.
- 6.6 If at any time the Contractor's actual progress falls behind the scheduled program, or it becomes apparent that it will so fall behind, the Contractor shall, at the request of the Employer/Owner or the Project Manager/ EIC, prepare and submit to the Project Manager/ EIC a revised program, taking into account the prevailing circumstances, and shall notify the Project Manager/ EIC, of the steps being taken to expedite progress so as to attain Completion of the Facilities within the Time for Completion. If any extension thereof entitled under GCC Clause, or any extended period as may otherwise be agreed upon between the Employer/Owner and the Contractor, Contractor shall submit the revised plan for completion of Facility accordingly.
- 6.7 Maintenance of Records of Weekly Progress Review Meeting at Site
The Contractor shall be required to attend all weekly site progress review meetings organized by the 'Project Manager/ EIC' or his authorized representative. The deliberations in the meetings shall inter-alia include the weekly program, progress of work (including details of manpower, material, tools and plants deployed by the Contractor vis-à-vis agreed schedule), inputs to be provided by Employer/Owner, delays, if any and recovery program, specific hindrances to work and work instructions by Employer/Owner. The minutes of the weekly meetings shall be recorded in triplicate in a numbered register available with the 'Project Manager/ EIC' or his authorized representative. These recordings shall be jointly signed by the 'Project Manager/ EIC' or his authorized representative and the Contractor and one copy of the signed records shall be handed over to the Contractor.

7. Conflict of Interest and Bidder's Responsibility

- 7.1 A bidder shall not have a Conflict of Interest. All bidders found to have Conflict of Interest shall be disqualified. A bidder may be considered to have a Conflict of Interest with one or more parties in this bidding process, if:
- (a) They have a controlling partner in common ; or
 - (b) They receive or have received any direct or indirect subsidy from any of them ; or
 - (c) They have the same legal representative for the purposes of this bid ; or
 - (d) They have a relationship with each other, directly or through common third parties, that puts them in a position to have access to information about or influence on the bid of another bidder, or influence the decision of the Employer/ Owner regarding this bidding process ; or
 - (e) A bidder submits more than one bid in this bidding process, either individually [including bid submitted as an agent/ authorized representative on behalf of one or more bidders or through license - licensor route, wherever permitted as per the provision of the Qualification Requirement for the bidders in the Annexure to Bid Data Sheet (BDS)] or as a partner in a Joint Venture/ Consortium, except for alternative offers permitted under Tender. This will result in the disqualification of all such bids ; or
 - (f) A bidder or any of its Affiliates participated as a consultant in the preparation of the Design or Technical Specification or Detailed Project Report (DPR) of the Plant and Installation of services*/ goods and related services** that are the subject of the bid ; or
 - (g) A bidder or any of its Affiliate has been hired (or is proposed to be hired) by the Employer/ Owner as a Project Manager for the Contract

Unquote:

* Applicable for Supply & Installation Contracts

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 16 of 77</u>	<u>Signature of Bidder</u>

**** Applicable for Supply & Supply cum Supervision of Installation Contracts**

- 7.2 The intending Tenderers shall be deemed to have visited the Site and familiarized submitting the Tender. Non-familiarity with the site conditions will not be considered a reason either for extra claims or for not carrying out the works in strict conformity with the Drawings and Specifications or for any delay in performance.

8. Retired Government or Company Officers

- 8.1 No Engineer of Gazetted rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the States/ Central Government or of the Employer/ Owner is allowed to work as a Contractor for a period of two years after his retirement from Government Service, or from the employment of the Employer/ Owner without the previous permission of the Employer/ Owner. The Contract, if awarded, is liable to be cancelled if either the Contractor or any of his employees is found at any time to be such a person, who has not obtained the permission of the State/ Central Government or of the Employer/ Owner as aforesaid before submission of Tender, or engagement in the Contractor's service as the case may be.

9. Representatives and Field Management & Controlling/ Coordinating Authority

- 9.1 **Project Manager / Engineer- In –Charge (EIC):**
If the Project Manager/ EIC is not named in the Contract, then within seven (7) days of the Effective Date, the Owner/Employer shall appoint and notify the Contractor in writing of the name of the Project Manager/ EIC. The Owner/Employer may from time to time appoint some other person as the Project Manager/ EIC in place of the person previously so appointed, and shall give a notice of the name of such other person to the Contractor without delay. The Owner/Employer shall take reasonable care, unless unavoidable to see that no such appointment is made at such a time or in such a manner as to impede the progress of work on the Facilities. The Project Manager/EIC shall represent and act for the Owner/Employer at all times during the currency of the Contract. All notices, instructions, orders, certificates, approvals and all other communications under the Contract shall be given by the Project Manager/ EIC, except as herein otherwise provided. All notices, instructions, information and other communications given by the Contractor to the Employer under the Contract shall be given to the Project Manager/ EIC, except as herein otherwise provided.
- 9.2 **Contractor's Representative & Construction Manager**
If the Contractor's Representative is not named in the Contract, then within seven (07) days of the Effective Date, the Contractor shall appoint the Contractor's Representative and shall request the Owner/ Employer in writing to approve the person so appointed. If the Owner/ Employer makes no objection to the appointment within seven (07) days of submission, the Contractor's Representative shall be deemed to have been approved. If the Employer objects to the appointment within seven (07) days giving the reason therefor, then the Contractor shall appoint a replacement within seven (07) days of such objection, and the foregoing provisions of this GCC clause shall apply thereto.
- 9.3 The Contractor's Representative shall represent and act for the Contractor at all times during the tenure of the Contract and shall give to the Project Manager/ EIC all the Contractor's notices, instructions, information and all other communications under the Contract.
- 9.4 All notices, instructions, information and all other communications given by the Owner/ Employer or the Project Manager/ EIC to the Contractor under the Contract shall be given to the Contractor's Representative or, in its absence, its deputy, except as herein otherwise provided.
- 9.5 The Contractor shall not revoke the appointment of the Contractor's Representative without the Owner/ Employer prior written consent, which shall not be unreasonably withheld. If the Owner/

Employer consents thereto, the Contractor shall appoint some other person as the Contractor's Representative, pursuant to the procedure set out in GCC Clauses.

- 9.6 The Contractor's Representative may, subject to the approval of the Owner/ Employer (which shall not be unreasonably withheld), at any time delegate to any person any of the powers, functions and authorities vested in him or her. Any such delegation may be revoked at any time. Any such delegation or revocation shall be subject to a prior notice signed by the Contractor's Representative, and shall specify the powers, functions and authorities thereby delegated or revoked. No such delegation or revocation shall take effect unless and until a copy thereof has been delivered to the Employer and the Project Manager/EIC.
- 9.7 Any act or exercise by any person of powers, functions and authorities so delegated to him or her in accordance with this GCC Clause shall be deemed to be an act or exercise by the Contractor's Representative.
- 9.8 Notwithstanding anything stated in GCC Clause above, for the purpose of execution of contract, the Owner/ Employer and the Contractor shall finalize and agree to a Contract Co-ordination Procedure and all the communication under the Contract shall be in accordance with such Contract Co-ordination Procedure.
- 9.9 From the commencement of installation of the Facilities at the Site until Final Acceptance, the Contractor's Representative shall appoint a suitable person as the construction manager (hereinafter referred to as "the Construction Manager"). The Construction Manager shall supervise all work done at the Site by the Contractor and shall be present at the Site throughout normal working hours except when on leave, sick or absent for reasons connected with the proper Performance of the Contract. Whenever the Construction Manager is absent from the Site, a suitable person shall be appointed to act as his or her deputy.
- 9.10 The Owner/ Employer may by notice to the Contractor object to any representative or person employed by the Contractor in the execution of the Contract who, in the reasonable opinion of the Owner/ Employer, may behave inappropriately, may be in- competent or negligent, or may commit a serious breach of the Site regulations and safety. The Employer shall provide evidence of the same, whereupon the Contractor shall remove such person from the Facilities.
- 9.11 If any representative or person employed by the Contractor is removed in accordance with GCC Clause, the Contractor shall, where required, promptly appoint a replacement. The field management will be the responsibility of the Engineer-in-Charge/Project Manager, who will be nominated by the Employer/ Owner. The Engineer-in-Charge/Project Manager may also authorize his representatives to assist in performing his duties and functions.
- 9.12 The Engineer-in-Charge/Project Manager shall coordinate the works of various agencies engaged at site to ensure minimum disruption of work carried out by different agencies. It shall be the responsibility of the Contractor to plan and execute the work strictly in accordance with site instructions to avoid hindrance to the work being executed by other agencies.

9.13 Hindrance Register

The Contractor may also maintain a Hindrance Register where reasons for delay/ fault may be recorded from time to time and at the time of occurrence of the hindrance and get it duly certified by the Project Manager or his authorized representative.

10. Note to Schedule of Rates

- 10.1 The Schedule of Rates should be read in conjunction with Section - VIII of the Tender documents.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 18 of 77</u>	<u>Signature of Bidder</u>

- 10.2 The bidder shall be deemed to have studied the Drawings (if any), Specifications and details of work to be done within Time Schedule and to have acquainted himself of the condition prevailing at site.
- 10.3 Rates must be filled in the Schedule of Rates of original Tender Documents. If quoted in separate typed sheets no variation in item description or specification shall be accepted. Any exceptions taken by the bidder to the Schedule of Rates shall be brought out in the terms and conditions of the bid.

11. Policy for Tenders under Consideration

- 11.1 Only Those Tenders which are complete in all respects and are strictly in accordance with the Terms and Conditions and Technical Specifications of Tender Document, shall be considered for evaluation. Such Tenders shall be deemed to be under consideration immediately after opening of Tender and until such time an official intimation of acceptance/ rejection of Tender is made by Employer to the Bidder.
- 11.2 Zero Deviation: Bidders to note that this is a Zero Deviation Tender. Employer/ Owner will appreciate submission of bids based on the terms and conditions in the enclosed General Conditions of Contract (GCC), Special Conditions of Contract (SCC), Instructions to Bidders (ITB), Scope of Work, technical specifications etc. to avoid wastage of time and money in seeking clarifications on technical/ commercial aspects of the bids. Bidder may note that no technical and commercial clarifications will be sought for after the receipt of the bids. In case of any deviation/ nonconformity observed in the bid, it will be liable for rejection.

12. Clarification of Tender Document

- 12.1 Verbal clarification and information given by Employer/ Owner or its employee(s) or its representatives shall not in any way be binding on Employer/ Owner.

13. Local Conditions

- 13.1 It will be imperative on each bidder to inform himself of all local conditions and factors which may have any effect on the execution of work covered under the Tender Document. In their own interest, the bidder(s) is/ are requested to familiarize themselves with the Indian Income Tax Act 1961, Indian Companies Act 1956, and Indian Customs Act 1962 and other related Acts and Laws and Regulations of India with their latest amendments, as applicable Employer/ Owner shall not entertain any requests for clarifications from the bidder regarding such local conditions.
- 13.2 It must be understood and agreed that such factors have properly been investigated and considered while submitting the Tender. No claim for financial or any other adjustments to Value of Contract, on lack of clarity of such factors shall be entertained.

14. Extension of Time for Completion

- 14.1 The Time(s) for Completion specified in the SCC shall be extended if the Contractor is delayed or impeded in the Performance of any of its obligations under the Contract by reason of any of the following:
- 14.1.1 Any occurrence of Force Majeure as provided in the Tender for Force Majeure, unforeseen/ differed site conditions (Unforeseen/ differed site Conditions).
- 14.1.2 Any changes in laws and regulations as provided in GCC (Change in Laws and Regulations) or by such period as shall be fair and reasonable in all the circumstances and as shall fairly reflect the delay or impediment sustained by the Contractor.

- 14.2 Except where otherwise specifically provided in the Contract, the Contractor shall submit to the Project Manager a notice of a claim for an extension of the Time for Completion, together with particulars of the event or circumstance justifying such extension as soon as reasonably practicable after the commencement of such event or circumstance. As soon as reasonably practicable after receipt of such notice and supporting particulars of the claim, the Employer/Owner and the Contractor shall agree upon the period of such extension. In the event that the Contractor does not accept the Employer's/Owner's estimate of a fair and reasonable time extension, then the matter will be settled in accordance with the provisions of GCC Clause (Adjudicator).
- 14.3 The Contractor shall at all times use its reasonable efforts to minimize any delay in the Performance of its obligations under the Contract.
- 14.4 The Contractor shall be required to attend all weekly site progress review meetings organized by the 'Project Manager' or his authorized representative. The deliberations in the meetings shall include the weekly program, progress of work (including details of manpower, tools and plants deployed by the Contractor vis-à-vis agreed schedule), inputs to be provided by Employer/Owner, delays, if any and recovery program, specific hindrances to work and work instructions by Employer/Owner. The minutes of the weekly meetings shall be recorded in triplicate in a numbered register available with the 'Project Manager' or his authorized representative. These recordings shall be jointly signed by the 'Project Manager' or his authorized representative and the Contractor and one copy of the signed records shall be handed over to the Contractor.

[D] GENERAL OBLIGATIONS

15.1 Priority of Contract Documents

Several documents forming the Contract are to be taken as mutually explanatory of one another, but in case of ambiguities or discrepancies the same shall be explained and adjusted by the Engineer-in-Charge/Project Manager who shall thereupon issue to the Contractor instructions thereon and in such event, unless otherwise provided in the Contract, the priority of the documents forming the Contract shall be as follows:

- 1) The Contract Agreement and any change order in the CA. if any;
- 2) The Notification of Award/ Letter of Intent/ Letter of Allocation;
- 3) Special Conditions of Contract (SCC);
- 4) Bid Data Sheet (BDS) and Instructions to Bidders (ITB);
- 5) General Conditions of Contract (GCC);
- 6) Any other document forming part of the Contract.

Works shown in the Drawing but not mentioned in the Specifications or described in the Specifications without being shown in the Drawings shall nevertheless be deemed to be included in the same manner as if they had been specifically shown upon the Drawings and described in the Specifications.

15.2 Headings and Marginal Notes

All headings and marginal notes to the clauses of these General Conditions of Contract or to the Specifications or to any other Tender Document are solely for the purpose of giving a concise indication and not a summary of the contents thereof, and they shall never be deemed to be part thereof or be used in the interpretation or construction thereof the Contract.

15.3 Singular and Plural

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 20 of 77</u>	<u>Signature of Bidder</u>

In Contract Documents unless otherwise stated specifically, the singular shall include the plural and vice versa wherever the context so requires.

15.4 Interpretation

Words implying 'Persons' shall include relevant Corporate Companies/ Registered Associations/ Body of Individuals/ Firm of Partnership' as the case may be.

16 Special Conditions of Contract (SCC)

- 16.1 Special Conditions of Contract shall be read in conjunction with the General Conditions of Contract, Specification of Work, Drawings and any other documents forming part of this Contract wherever the context so requires.
- 16.2 Notwithstanding the sub-division of the documents into these separate sections and volumes every part of each shall be deemed to be supplementary to and complementary of every other part and shall be read with and into the Contract so far as it may be practicable to do so.
- 16.3 Where any portion of the General Condition of Contract is repugnant to or at variance with any provisions of the Special Conditions of Contract, unless a different intention appears the provisions of the Special Conditions of Contract shall be deemed to over-ride the provisions of the General Conditions of Contract and shall to the extent of such repugnancy, or variations, prevail.
- 16.4 Wherever it is mentioned in the specifications that the Contractor shall perform certain Work or provide certain facilities, it is understood that the Contractor shall do so at his cost and the Value of Contract shall be deemed to have included cost of such performance and provisions, so mentioned.
- 16.5 The materials, design and workmanship shall satisfy the relevant Indian Standards, the Job Specifications contained herein and Codes referred to. Where the job specification stipulate requirements in addition to those contained in the standard codes and specifications, these additional requirements shall also be satisfied.

17 Contractor to obtain his own Information

- 17.1 The Contractor in fixing his rate shall for all purpose whatsoever reason may be, deemed to have himself independently obtained all necessary information for the purpose of preparing his tender and his tender as accepted shall be deemed to have taken into account all contingencies as may arise due to such information or lack of same. The correctness of the details, given in the Tender Document to help the Contractor to make up the tender is not guaranteed. The Contractor shall be deemed to have examined the Contract Documents, to have generally obtained his own information in all matters whatsoever that might affect the carrying out of the works at the schedules rates and to have satisfied himself to the sufficiency of his tender. Any error in description of quantity or omission therefrom shall not vitiate the Contract or release the Contractor from executing the work comprised in the Contract according to Drawings and Specifications at the scheduled rates. He is deemed to have known the scope, nature and magnitude of the Works and the requirements of materials and labour involved etc., and as to what all works he has to complete in accordance with the Contract documents whatever be the defects, omissions or errors that may be found in the Documents. The Contractor shall be deemed to have visited surroundings, to have satisfied himself to the nature of all existing structures, if any, and also as to the nature and the conditions of the Railways, Roads, Bridges and Culverts, means of transport and communication, whether by land, water or air, and as to possible interruptions thereto and the access and egress from the site, to have made enquiries, examined and satisfied himself as to the sites for obtaining sand, stones, bricks and other materials, the sites for disposal of surplus materials, the available accommodation as to whatever required, depots and such other buildings as may be necessary for executing and completing the works, to have made local independent enquiries as to the sub-soil, subsoil water

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

and variations thereof, storms, prevailing winds, climatic conditions and all other similar matters effecting these works. He is deemed to have acquainted himself as to his liability of payment of Government Taxes, Customs duty and other charges, levies etc. Any neglect or omission or failure on the part of the Contractor in obtaining necessary and reliable information upon the foregoing or any other matters affecting the Contract shall not relieve him from any risks or liabilities or the entire responsibility from completion of the works at the scheduled rates and times in strict accordance with the Contract. It is, therefore, expected that should the Contractor have any doubt as to the meaning of any portion of the Contract Document he shall set forth the particulars thereof in writing to Employer/Owner in duplicate, before submission of tender. The Employer/Owner may provide such clarification as may be necessary in writing to Contract, such clarifications as provided by Employer/Owner shall form part of Contract Documents. No verbal agreement or inference from conversation with any effect or employee of the Employer/Owner either before, during or after the execution of the Contract Agreement shall in any way affect or modify and of the terms or obligations herein contained. Any change in layout due to site conditions or technological requirement shall be binding on the Contractor and no extra claim on this account shall be entertained.

18 Time of Performance

18.1 Time for Mobilization

The work covered by this Contract shall be commenced immediately upon issuance of the NOA/ LOI/ LOA and be completed in stages on or before the dates as mentioned in the Time Schedule of Completion of Work under Section - V, Special Conditions of Contract (SCC). The Contractor should bear in mind that time is the essence of this contract agreement. Request for revision of construction time after tenders are opened will not receive consideration. The mobilization period is included within the overall Completion Schedule, not over and above the completion time to any additional work or any other reasons.

18.2 Time Schedule of Construction

18.2.1 The general time schedule of construction is given in the Section - V, Special Conditions of Contract (SCC) of the Tender Documents. Contractor should prepare a detailed monthly or weekly construction program jointly with the Engineer-in-Charge/Project Manager. The Work shall be executed strictly as per the Time Schedule given in the Tender Documents. The period of construction given includes the time required for mobilization testing, rectifications, if any, retesting and completion in all respects in accordance with Contract Document to the entire satisfaction of the Engineer-in-Charge/Project Manager.

18.2.2 The Contractor shall submit a detailed PERT network within the time frame agreed consisting of adequate number of activities covering various key phases of the Work such as Design, Procurement, Manufacturing, Shipment and Field Erection activities. This network shall also indicate the interface facilities to be provided by the Employer/ Owner, if any and the dates by which such facilities are needed.

19. Force Majeure

19.1 A 'Force Majeure' means any event or circumstance or combination of events those stated below that wholly or partly prevents or unavoidably delays an Affected Party in the performance of its obligations under this Agreement, but only if and to the extent that such events or circumstances are not within the reasonable control, directly or indirectly, of the Affected Party and could not have been avoided if the Affected Party had taken reasonable care or complied with Prudent Utility Practices:

- Act of God, including, but not limited to lightning, fire not caused by contractors' negligence and explosion (to the extent originating from a source external to the site), earthquake (above 7.0

magnitude on Richter Scale), volcanic eruption, landslide, unprecedented flood, cyclone, typhoon or tornado;

- Any act of war (whether declared or undeclared), invasion, armed conflict or act of foreign enemy, blockade, embargo, revolution, riot, insurrection, terrorist or military action, quarantine;
- Radioactive contamination or ionizing radiation originating from a source in India or resulting from another Force Majeure Event mentioned above.

19.2 Force Majeure Exclusions

Force Majeure shall not include (i) any event or circumstance which is within the reasonable control of the Parties and (ii) the following conditions, except to the extent that they are consequences of an event of Force Majeure:

- Unavailability, late delivery, or changes in cost of the plant, machinery, equipment, materials, spare parts or consumables for the Power Project;
- Delay in the performance of any contractor, sub-contractor or their agents;
- Non-performance resulting from normal wear and tear typically experienced in power generation materials and equipment;
- Strikes at the facilities of the Contractor / Affected Party;
- Insufficiency of finances or funds or the agreement becoming onerous to perform; and
- Non-performance caused by, or connected with, the Affected Party's:
 - o Negligent or intentional acts, errors or omissions;
 - o Failure to comply with an Indian Law; or
 - o Breach of, or default under this Contract Agreement.
- Normal rainy seasons and monsoon

19.3 In the event of either party being rendered unable by Force Majeure to perform any obligation required to be performed by them under this Contract, relative obligation of the party affected by such Force Majeure shall be treated as suspended during the period which the Force Majeure clause last.

19.4 Upon occurrence of such causes, the party alleging that it has been rendered unable as aforesaid, thereby, shall notify the other party in writing by registered notice within 48 (forty eight) hours of the alleged beginning thereof giving full particulars and satisfactory evidence in support of its claim. Further, within 7 (seven) days, the Contractor will furnish a detailed Contingency Plan to overcome the effects of the incident and bring the project on its schedule after cessation of the effect of Force Majeure.

19.5 The Affected Party shall give notice to the other Party of (i) the cessation of the relevant event of Force Majeure; and (ii) the cessation of the effects of such event of Force Majeure on the performance of its rights or obligations under this Agreement, as soon as practicable after becoming aware of each of these cessations.

19.6 Time for Performance of the relative obligation suspended by the force majeure shall stand extended by the period for which such Force Majeure clause lasts.

19.7 If works are suspended by Force Majeure conditions lasting for more than two months, the Employer/Owner shall have the option of cancelling this Contract in whole or part thereof, at its discretion.

19.8 The Contractor will not be entitled to claim any compensation for Force Majeure conditions and shall take appropriate steps to insure its men and materials utilized by it under the Contract.

20. Liquidated Damages (LD)

20.1 Subject to Force Majeure Clause, if the Contractor fails to comply with the Time for Completion /successful commissioning of Plant in accordance with SCC Clause for the whole of the facilities, (or a part for which a separate time for completion is agreed) then the Contractor shall pay to the Employer/ Owner a sum equivalent to one percent (1%) of the Contract Price for the whole of the facilities, (or a part for which a separate time for completion is agreed) as liquidated damages for such default and not as a penalty, without prejudice to the Employer's/ Owner's other remedies under the Contract, for each week or part thereof which shall elapse between the relevant Time for Completion and the date stated in Taking Over Certificate of the whole of the Works (or a part for

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

which a separate time for completion is agreed) subject to the limit of ten percent (10%) of Contract Price for the whole of the facilities, (or a part for which a separate time for completion is agreed). The Employer/ Owner may, without prejudice to any other method of recovery, deduct the amount of such damages from any amount due or to become due to the Contractor. The payment or deduction of such damages shall not relieve the Contractor from his obligation to complete the Works, or from any other of his obligations and liabilities under the Contract. Once the maximum limit is reached, Employer/ Owner may consider the termination of contract. Any such recovery on account of the Liquidated damages can be done from the running bills of the contractor by Owner.

- 20.2 The Employer/ Owner shall as an alternative to the Liquidated Damages at its option, get work executed from elsewhere at the risk and cost of the Contractor irrespective of the fact whether the scope of Contract is identical to the original scope of Contract and in case the Employer/ Owner chooses the alternative course as mentioned, it will be entitled to recover compensation/ damages from the Contractor irrespective of maximum limit prescribed under Clause 20.1.
- 20.3 The Employer/ Owner may by giving (01) one month notice to the Contractor cancel the Contract without prejudice to the Employer's/ Owner's right under Clauses 20.1 and 20.2 any other provisions contained in the Contract to determine the Contract and claim damaged from the Contractor.
- 20.4 The Contractor shall not raise the question of proving actual loss suffered by the Employer/ Owner consequent on the said delay in Completion.

21. Rights of the employer to forfeit Contract Performance Security

- 21.1 Whenever any claim against the Contractor for the payment of a sum of money arises out or under the Contract, the Employer/ Owner shall be entitled to recover such sum by appropriating in part or whole the Contract Performance Security of the Contractor. In the event of the security being insufficient or if no security has been taken from the Contractor, then the balance or the total sum recoverable, as the case may be shall be deducted from any sum then due or which at any time thereafter may become due to the Contractor. The Contractor shall pay to the Employer/ Owner on demand any balance remaining due.

22. Failure by the Contractor to comply with the provisions of the Contract

- 22.1 If the Contractor refuses or fails to execute the Work or any separate part thereof with such diligence as will ensure its completion within the time specified in the Contract or extension thereof or fails to perform any of his obligation under the Contract or in any manner commits a breach of any of the provisions of the Contract it shall be open to the Employer/ Owner at its option by written notice to the Contractor:

a) To determine the event in which the Contract shall stand terminated and shall cease to be in force and effect on and from the date appointed by the Employer/ Owner on that behalf, whereupon the Contractor shall stop forthwith any of the Contractor's work then in progress, except such work as the Employer/ Owner may, in writing, require to be done to safeguard any property or work, or installations from damage, and the Employer/ Owner, for its part, may take over the work remaining unfinished by the Contractor and complete the same through a fresh Contractor or by other means, at the risk and cost of the Contractor, and any of his sureties if any, shall be liable to the Employer/ Owner for any excess cost occasioned by such work having to be so taken over and completed by the Employer/ Owner over and above the cost at the rates specified in the schedule of quantities and rate/prices.

b) Without determining the Contract to take over the work of the Contractor or any part thereof and complete the same through a fresh Contractor or by other means at the risk and cost of the Contractor. The Contractor and any of his sureties are liable to the Employer/ Owner for any excess

cost over and above the cost at the rates specified in the Schedule of Rates/ Price Schedule, occasioned by such works having been taken over and completed by the Employer/ Owner.

22.2 In such events of Clause 22.1(a) or (b) above.

a) The whole or part of the Contract Performance Security furnished by the Contractor is liable to be forfeited without prejudice to the right of the Employer/ Owner to recover from the Contractor the excess cost referred to in the Clause aforesaid, the Employer/ Owner shall also have the right of taking possession and utilizing in completing the works or any part thereof, such as materials, equipment and plants available at work site belonging to the Contractor as may be necessary and the Contractor shall not be entitled for any compensation for use or damage to such materials, equipment and plant.

b) The amount that may have become due to the Contractor on account of work already executed by him shall not be payable to him until after the expiry of 06 (Six) calendar months reckoned from the date of termination of Contract or from the taking over of the Work or part thereof by the Employer/ Owner as the case may be, during which period the responsibility for faulty materials or workmanship in respect of such work shall, under the Contract, rest exclusively with the Contractor. This amount shall be subject to deduction of any amounts due from the Contract to the Employer/ Owner under the terms of the Contract authorized or required to be reserved or retained by the Employer/ Owner.

22.3 Before determining the Contract as per Clause 22.1(a) or (b) provided in the judgement of the Employer/ Owner, the default or defaults committed by the Contractor is/ are curable and can be cured by the Contractor if an opportunity given to him, then the Employer/ Owner may issue Notice in writing calling the Contractor to cure the default within such time specified in the Notice.

22.4 The Employer/ Owner shall also have the right to proceed or take action as per 22.1(a) or (b) above, in the event that the Contractor becomes bankrupt, insolvent, compounds with his creditors, assigns the Contract in favor of his creditors or any other person or persons, or being a company or a corporation goes into voluntary liquidation, provided that in the said events it shall not be necessary for the Employer/ Owner to give any prior notice to the Contractor.

22.5 Termination of the Contract as provided for in sub- clause 22.1(a) above shall not prejudice or affect their rights of the Employer/ Owner which may have accrued up to the date of such termination.

23. Contractor remains liable to pay compensation if

23.1 In any case in which any of the powers conferred upon the Employer/ Owner by Clause 22.0 thereof shall have become action not taken under clause 22 exercisable and the same had not been exercised, the non-exercise thereof shall not constitute a waiver of any of the conditions hereof and such powers shall notwithstanding be exercisable in .the event of any further case of default by the Contractor for which by any clause or clauses hereof he is declared liable to pay compensation amounting to the whole of his Contract Performance Security, and the liability of the Contractor for past and future compensation shall remain unaffected. In the event of the Employer/ Owner putting in force the power under above Clause (a), (b) or (c) vested in him under the preceding clause he may, if he so desired, take possession of all or any tools, and plants, materials and stores in or upon the works or the site thereof belonging to the Contractor or procured by him and intended to be used for the execution of the Work or any part thereof paying or allowing for the same in account at the Contract rates or in case of these not being applicable at current market rates to be certified by the Engineer-in-Charge/Project Manager whose certificate thereof shall be final, otherwise the Engineer-in- Charge may give notice in writing to the Contractor or his clerk of the works, foreman or other authorized agent, requiring him to remove such tools, plant, materials or stores from the premises (within a time to be specified in such notice), and in the event of the Contractor failing to comply with any such requisition, the Engineer-in-Charge/Project Manager may remove them at the

Contractor's expense or sell them by auction or private sale on account of the Contractor and at his risk in all respects without any further notice as to the date, time or place of sale and the certificate of the Engineer-in-Charge/Project Manager as to the expenses of any such removal and the amount of the proceeds and expenses of any such sale shall be final and conclusive against the Contractor.

24. Change in Constitution

24.1 The prior approval of the Employer/ Owner shall be obtained in writing, before any change is made in the constitution of the Company. If prior approval as aforesaid is not obtained, the CONTRACT shall be deemed to have been allotted in contravention of Clause 30 hereof and the same action may be taken and the same consequence shall ensure as provided in the said clause.

25. Termination of contract

25.1 Termination of Contract in Case of Liquidation/ Bankruptcy etc.

If the Contractor shall dissolve or become bankrupt or insolvent or cause or suffer any receiver to be appointed of his business or any assets thereof compound with his Creditors, or being a corporation commence to be wound up, not being a member's voluntary winding up for the purpose of amalgamation or reconstruction, or carry on its business under a Receiver for the benefits of its Creditors any of them, Employer/ Owner shall be at liberty :- To terminate the contract forthwith upon coming to know of the happening of any such event as aforesaid by notice in writing to the Contractor or to give the Receiver or liquidator or other person, the option of carrying out the contract subject to his providing a guarantee up to an amount to be agreed upon by Employer/ Owner for due and faithful performance of the contract.

25.2 Termination of Contract for Non-Performance and Subsequently Putting the Contractor on Banning List:

In case of termination of Contract herein set forth (under clause 22.0) except under conditions of Force Majeure and termination after expiry of contract, the Contractor shall be put under Banning List [i.e. neither any enquiry will be issued to the party by Employer/ Owner against any type of tender nor their offer will be considered by Employer/ Owner against any ongoing tender(s) where contract between Employer/ Owner and that particular Contractor (as a bidder) has not been finalized] for a period as decided by the Employer/ Owner to such Contractor.

26. Members of the Employer/ Owner not individually Liable

26.1 No Director, or official or employee of the Employer/ Owner shall in any way be personally bound or liable for the acts or obligations under the Contract or answerable for any default or omission in the observance or performance of any of the acts, matters or things which are herein contained.

27. Employer/Owner not bound by Personal Representations

27.1 The Contractor shall not be entitled to any increase on the scheduled rates or any other right or claim whatsoever by reason of any representation, explanation statement or alleged representation, promise or guarantees given or alleged to have been given to him by any person.

28. Contractor's office at Site

28.1 The Contractor shall provide and maintain an office at the site for the accommodation of his agent and staff and such office shall be open at all reasonable hours to receive instructions, notice or other communications. The Contractor at all time shall maintain a site instruction book and compliance of

these shall be communicated to the Engineer-in-Charge/Project Manager from time to time and the whole document to be preserved and handed over after completion of works.

29. Contractor's Subordinate Staff and their Conduct

- 29.1 The Contractor, on or after award of the Work shall name and depute a qualified Engineer having sufficient experience in carrying out work of similar nature, to whom the equipment, materials, if any, shall be issued and instructions for works given. The Contractor shall also provide to the satisfaction of the Engineer-in-Charge/Project Manager sufficient and qualified staff to superintend the execution of the Work, competent sub-agents, foremen and leading hands including those specially qualified by previous experience to supervise the types of works comprised in the Contract in such manner as will ensure work of the best quality, expeditious working. Whenever in the opinion of the Engineer-in-Charge/Project Manager additional properly qualified supervisory staff is considered necessary, they shall be employed by the Contractor without additional charge on accounts thereof. The Contractor shall ensure to the satisfaction of the Engineer-in-Charge/Project Manager that Sub-Contractors, if any, shall provide competent and efficient supervision, over the work entrusted to them.
- 29.2 If and whenever any of the Contractor's or Sub-Contractor's agents, sub-agents, assistants, foremen, or other employees shall in the opinion of Engineer-in-Charge/Project Manager be guilty of any misconduct or be incompetent or insufficiently qualified or negligent in the performance of their duties of that in the opinion of the Employer/ Owner or the Engineer-in-Charge/Project Manager, it is undesirable for administrative or any other reason for such person or persons to be employed in the works, the Contractor, is so directed by the Engineer-in-Charge/Project Manager, shall at once remove such person or persons from employment thereon. Any person or persons so removed from the works shall not again be employed in connection with the Works without the written permission of the Engineer-in-Charge/Project Manager. Any person so removed from the Work shall be immediately re-placed at the expense of the Contractor by a qualified and competent substitute. Should the Contractor be requested to repatriate any person removed from the works he shall do so and shall bear all costs in connection herewith.
- 29.3 The Contractor shall be responsible for the proper behavior of all the staff, foremen, workmen, and others, and shall exercise a proper degree of control over them and in particular and without prejudice to the said generality, the Contractor shall be bound to prohibit and prevent any employees from trespassing or acting in any way detrimental or prejudicial to the interest of the community or of the properties or occupiers of land and properties in the neighborhood and in the event of such employee so trespassing, the Contractor shall be responsible therefore and relieve the Employer/ Owner of all consequent claims or actions for damages or injury or any other grounds whatsoever. The decision of the Engineer-in-Charge/Project Manager upon any matter arising under this clause shall be final. The Contractor shall be liable for any liability to Employer/ Owner on account of deployment of Contractor's staff etc. or incidental or arising out of the execution of Contract. The Contractor shall be liable for all acts or omissions on the part of his staff, Foremen and Workmen and others in his employment, including misfeasance or negligence of whatever kind in the course of their work or during their employment, which are connected directly or indirectly with the Contract.
- 29.4 If and when required by the Employer/ Owner and Contractor's personnel entering upon the Employer's/ Owner's premises shall be properly identified by badges of a type acceptable to the Employer/ Owner which must be worn at all times on Employer's/ Owner's premises. Contractor may be required to obtain daily entry passes for his Staff/ Employees from Employer/ Owner to work within operating areas. These being safety requirements, no relaxations on this account shall be given to Contractor.

30. Sub-letting of Works

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>GCC</u> <u>Page 27 of 77</u>	<u>Signature of Bidder</u>

- 30.1 No part of the Contract nor any share or interest therein shall in any manner or degree be transferred, assigned or sublet by the Contractor directly or indirectly to any person, firm or corporation whatsoever without the consent in writing, of the Employer/ Owner except as provided for in the succeeding Clause.

i) Sub-Contracts for Temporary Works etc.

The Employer/ Owner may give written consent to Sub-Contract for the execution of any part of the Work at the site, being entered in to by Contractor provided each individual Sub-contract is submitted to the Engineer-in-Charge/Project Manager before being entered into and is approved by him.

ii) List of Sub-Contractors to be supplied

At the commencement of every month the Contractor shall furnish to the Engineer-in-Charge/Project Manager list of all Sub-Contractors or other persons or firms engaged by the Contractor and working at the Site during the previous month with particulars of the general nature of the Subcontract or works done by them.

iii) Contractor's Liability not Limited by Sub-Contractors

Notwithstanding any sub-letting with such approval as aforesaid and notwithstanding that the Engineer-in-Charge/Project Manager shall have received copies of any Subcontracts, the contractor shall be and shall remain solely responsible for the quality, proper and expeditious execution of the Contract in all respects as if such sub-letting or Subcontracting had not taken place, and as if such work had been done directly by the Contractor. The Contractor shall bear all responsibility for any act or omission on the part of sub-contractors in regard to work to be performed under the Contract.

iv) Employer/Owner May Terminate Sub-Contracts

If any Sub-Contractor engaged upon the works at the site executes any works which in the opinion of the Engineer-in-Charge/Project Manager is not in accordance with the Contract documents, the Employer/ Owner may by written notice to the Contractor request him to terminate such subcontract and the Contractor upon the receipt of such notice shall terminate such Subcontract and dismiss the Sub-Contractor(s) and the later shall forthwith leave the works, failing which the Employer/ Owner shall have the right to remove such Sub-Contractor(s) from the site.

v) No Remedy for Action Taken under this Clause

No action taken by the Employer/ Owner under the clause shall relieve the Contractor of any of his liabilities under the Contract or give rise to any right or compensation, extension of time or otherwise failing which the Employer/ Owner shall have the right to remove such Sub-Contractor(s) from the site.

vi) Termination/ Cancellation of Contract

Employer/ Owner is nowhere liable for the communication, acts and deeds and performance of the sub-contractor as engaged by the principal contractor. Principal Contractor solely is responsible and liable for the entire execution of project and performance of contract. In case of non-performance of the sub-contractor in lieu of inadequate liquidity, technical competence, adequate manpower Employer/ Owner may take an appropriate decision to get the work done at the risk and cost of the principal contractor.

Subject to poor performance and prolonged delay of the project on account of inefficient sub-letting of the project work Employer/ Owner may take a final decision to terminate the

contract of the principal contractor which will be binding and non-revertible and henceforth no plea in this regard shall be entertained.

The Contractor has to execute the work by functioning like a contractor instead of sub-letting the entire work on back to back basis. The entire work cannot be sub-let to a sub-contractor on back to back basis.

vii) Subject to the provisions of the Contract, the Contractor shall be solely responsible for the manner in which the Contract is performed. All employees, representatives or Subcontractors engaged by the Contractor in connection with the Performance of the Contract shall be under the complete control of the Contractor and shall not be deemed to be employees of the Owner/Employer. Nothing contained in the Contract or in any subcontract awarded by the Contractor shall be construed to create any contractual relationship between any such employees, representatives or Subcontractors and the Employer.

viii) Under no circumstances the sub-contractor shall claim or shall put any binding to the Owner/Employer and at all times the sub-contractor must be managed by the Contractor. The Owner/ Employer shall not be responsible for any claims at any time by the Contractor in relation to the sub-contractor.

ix) No relaxation, forbearance, delay or indulgence by either party in enforcing any of the terms and conditions of the Contract or the granting of time by either party to the other shall prejudice, affect or restrict the rights of that party under the Contract, nor shall any waiver by either party of any breach of Contract operate as waiver of any subsequent or continuing breach of Contract.

x) Any waiver of a party's rights, powers or remedies under the Contract must be in writing, must be dated and signed by an authorized representative of the party granting such waiver, and must specify the right and the extent to which it is being waived.

31. Power of Entry

31.1 If the Contractor shall not commence the Work in the manner previously described in the Contract documents or if he shall at any time in the opinion of the Engineer-in-Charge/Project Manager:

- i) fail to carry out the Work in conformity with the Contract documents, or
- ii) fail to carry out the Work in accordance with the Time Schedule, or
- iii) substantially suspend Work or the Work for a period of 14 (Fourteen) days without authority from the Engineer-in-Charge/Project Manager, or
- iv) fail to carry out and execute the Work to the satisfaction of the Engineer-in-Charge/Project Manager, or
- v) fail to supply sufficient or suitable construction plant, temporary works, labour, materials or things, or
- vi) Commit, suffer, or permit any other breach of any of the provisions of the Contract on his part to be performed or observed or persist in any of the above-mentioned breaches of the Contract for 14 (Fourteen) days, after notice in writing shall have been given to the Contractor by the Engineer-in-Charge/Project Manager requiring such breach to be remedied, or
- vii) if the Contractor abandon the Work, or
- viii) If the Contractor during the continuance of the Contract shall become bankrupt, make any arrangement or composition with his creditors, or permit any execution to be levied or go into liquidation whether compulsory or voluntary not being merely a voluntary liquidation for the purpose of amalgamation or reconstruction

then in any such case, the Employer/ Owner shall have the power to enter upon the Work and take possession thereof and of the materials, temporary Work, construction plant, and stock thereon, and

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

to revoke the Contractor's license to use the same, and to complete the Work by his agents, other Contractors or workmen or to relate the same upon any terms and to such other person, firm or corporation as the Employer/ Owner in his absolute discretion may think proper to employ and for the purpose aforesaid to use or authorize the use of any materials, temporary work, Construction Plant, and stock as aforesaid, without making payment or allowance to the Contractor for the said materials other than such as may be certified in writing by the Engineer-in-Charge/Project Manager to be reasonable, and without making any payment or allowance to the Contractor for the use of the temporary said works, construction plant and stock or being liable for any loss or damage thereto, and if the Employer/ Owner shall by reason of his taking possession of the Work or of the Work being completed by other Contractor (due account being taken of any such extra work or works which may or be omitted) then the amount of such excess as certified by the Engineer-in-Charge/Project Manager shall be deducted from any money which may be due for work done by the Contractor under the Contract and not paid for. Any deficiency shall forthwith be made good and paid to the Employer/ Owner by the Contractor and the Employer/ Owner shall have power to sell in such manner and for such price as he may think fit all or any of the construction plant, materials etc. constructed by or belonging to and to recoup and retain the said deficiency or any part thereof out of proceeds of the sale.

32. Contractor's responsibility with the Mechanical, Electrical, Intercommunication System, Air-Conditioning Contractors and other Agencies

32.1 Contractor's responsibility

32.1.1 The Contractor shall grade/level the land identified for development of the mentioned Solar power Plant (with cells & modules manufactured in India) along with the design, procure, manufacture (including associated purchases and/or subcontracting), install, commission and complete the Facilities, carry out the Guarantee tests with due care and diligence in accordance with the Contract along with interconnecting transmission system including Right of Way for Transmission Line and the O&M of the complete facilities for the period as defined under the tender document . It is contractor's responsibility to coordinate with state/central agencies in order to get any permission whatsoever, required for successful development & operation of Plant till its desired life.

32.1.2 Contractor confirms that it has entered into this Contract on the basis of proper examination of the data relating to the Facilities provided by the c and assessed by himself at the site location, after proper due diligence relating to the Facilities prior to bid submission. The Contractor acknowledges that any failure to obtain or acquaint itself with all such data and information shall not relieve its responsibility for properly estimating the difficulty or cost of successfully performing the Scope of Work.

32.1.3 The Contractor shall acquire, on behalf of Owner/Employer, in the Owner's/employers' name, all permits, approvals and/or licenses from all local, state or national government authorities or public service undertakings in the country where the Site is located that are necessary for the setting up of the Plant & operation of Plant till its desired life as mentioned under the Contract, including, but not limited to, entry permits for all imported Owner's/Employer's Equipment (if any). In this regard, any document required from Owner/ Employer shall be intimated at least 10 days prior to submission. Contractor has to ensure safe keeping of the documents and diligent use. It is the responsibility of the contractor to safe keep and return all the approvals, permits, licenses, certificates and other relevant document generated as a result of the setting up of project and O&M process to the Owner.

32.1.4 In the matter of connectivity of Plant to DISCOM's substation, Owner/ Employer shall fill up the application & hand it over to the contractor however all other activities beyond it such as coordination with DISCOM for Bay allocation, technical/regulatory compliance for interconnection including payment of Fee or any other charges to the state agencies/DIOSCOM as the case may be shall be taken care by the Contractor. Bidders are advised to include these cost in their final offer/Price BID.

- 32.1.5 The Contractor shall acquire in its name all permits, approvals and/or licenses from all local, state or national government authorities or public service undertakings in the country where the Site is located that are necessary for the Performance of the Contract, including, but not limited to, the right of way for the access to site and for erection of transmission lines as applicable, visas for the Contractor's and Subcontractor's personnel and entry permits for all imported Contractor's Equipment. The Contractor shall acquire all other permits, approvals and/or licenses that are not the responsibility of the Owner/ Employer and that are necessary for the Performance of the Contract.
- 32.1.6 Contractor shall also seek for any exemption applicable for the project as per the orders released from GOI time to time in appropriate Formats including all the required attachments. In this regard, contractor shall be responsible to take all necessary certificates as a proof of exemptions on behalf of Owner/ Employer. However, all the documents required from Employer, as needed for the process, will be provided by Owner/ Employer. The demand of such documents shall be made to the Owner/ Employer in at least 10 days advance.
- 32.1.7 The Contractor shall comply with all laws in force at the place, where the Facilities are installed and where the Installation Services are carried out. The laws will include all national, provincial, municipal or other laws that affect the Performance of the Contract and binding upon the Contractor. The Contractor shall indemnify and hold harmless the Employer/Owner from and against any and all liabilities, damages, claims, fines, penalties and expenses of whatever nature arising or resulting from the violation of such laws by the Contractor or its personnel, including the Subcontractors and their personnel.
- 32.1.8 Any plant, material, spares & spares inventory and services that will be incorporated in or be required for the facilities and other supplies shall have their origin.
- 32.1.9 Unless otherwise specified in the Contract or agreed upon by the Owner/ Employer and the Contractor, the Contractor shall provide/ deploy sufficient, properly qualified operating and maintenance personnel; shall supply and make available all raw materials, spares, other materials and facilities; and shall perform all work and services of whatsoever nature, to properly carry out Pre-commissioning, Commissioning and Guarantee Tests, all in accordance with the provisions of "Scope of Works and Supply by the Owner/ Employer" to the Contract Agreement at or before the time specified in the program furnished by the Contractor and in the manner thereupon specified or as otherwise agreed upon by the Owner/ Employer and the Contractor.
- 32.1.10 Without repugnance of any other condition, it shall be the responsibility of the Contractor executing the work of civil construction, to work in close cooperation and coordinate the Work with the Mechanical, Electrical and Intercommunication Contractor's and other agencies or their authorized representatives, in providing the necessary grooves, recesses, cuts and opening etc., in wall, slabs beams and columns etc. and making good the same to the desired finish as per specification, for the placement of electrical, intercommunication cables, conduits and other equipment's etc. where required. For the above said requirements in the false ceiling and other partitions, the Contractor before starting-up the work shall in consultation with the Electrical, Mechanical, Intercommunication, and other agencies prepare and put-up a joint scheme, showing the necessary openings, grooves, recesses, cuts, the methods of fixing required for the Work of the aforesaid, and the finishes therein, to the Engineer-in-Charge/Project Manager and get the approval. The Contractor before finally submitting the scheme to the Engineer-in-Charge/Project Manager, shall have the written agreement of the other agencies. The Engineer- in-Charge, before communicating his approval to the scheme, with any required modification, shall get the final agreement of all the agencies, which shall be binding. No claim shall be entertained on account of the above. The Contractor shall confirm in all respects with provision of any statutory regulations, ordinances or byelaws of any local or duly constituted authorities or public bodies which may be applicable from time to time to the Work or any temporary works. The Contractor shall keep the Employer/ Owner indemnified against all penalties and liabilities of every kind, arising out of non- adherence to such stains, ordinances, laws, rules, regulations, etc.

33. Other Agencies at Site

- 33.1 The Contractor shall have to execute the Work in such place and conditions where other agencies may also be engaged for other works such as site grading, filling, and levelling, electrical and mechanical engineering works, etc. No claim shall be entertained due to Work being executed in the above circumstances.

34. Notice

34.1 To the Contractor

Any notice hereunder may be served on the Contractor or his duly authorized representative at the job site or may be served by registered mail direct to the address furnished by the Contractor. Proof of issue of any such notice could be conclusive of the Contractor having been duly informed of all contents therein.

34.2 To the Employer/ Owner

Any notice to be given to the Employer/Owner under the terms of the Contractor shall be served by sending the same by Registered mail to or delivering the same at the offices of Employer/ Owner at the mentioned address in the Tender document.

35. Right of Various Interests

- 35.1 i) The Employer/ Owner reserves the right to distribute the work between more than one agency(ies). The Contractor shall cooperate and afford other agency(ies) reasonable opportunity for access to the Work for the carriage and storage of materials and execution of their works.
- ii) Wherever the work being done by any department of the Employer/ Owner or by other agency(ies) employed by the Employer/ Owner is contingent upon Work covered by this Contract, the respective rights of the various interests involved shall be determined by the Engineer-in-Charge/Project Manager to secure the completion of the various portions of the work in general harmony.

36. Patents and Royalties

- 36.1 The copyright in all drawings, documents and other materials containing data and information furnished to the Owner/ Employer by the Contractor herein shall remain vested in the Contractor or, if they are furnished to the Owner/ Employer directly or through the Contractor by any third party, including suppliers of materials, the copyright in such materials shall remain vested in such third party. The Owner/ Employer shall however be free to reproduce all drawings, documents, specification and other material furnished to the Owner/ Employer for the purpose of the contract including, if required, for operation and maintenance of the facilities.

The Contractor shall indemnify the Owner/ Employer against third party claims of infringement of patent, trademark or industrial design rights arising from use of goods or any part thereof in India.

The Contractor, if licensed under any patent covering equipment, machinery, materials or compositions of matter to be used or supplied or methods and process to be practiced or employed in the performance of this Contract, agrees to pay all royalties and license fees which may be due with respect thereto. If any equipment, machinery, materials, composition of matters, be used or supplied or methods and processes to be practiced or employed in the performance of this Contract, is covered by a patent under which the Contractor is not licensed then the Contractor before supplying or using the equipment, machinery materials, composition method or processes shall obtain such licenses and pay such royalties and license fees as may be necessary for performance

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

of this Contract. In the event the Contractor fails to pay any such royalty or obtain any such license, any suit for infringement of such patents which is brought against the Contractor or the Employer/ Owner as a result such failure will be defended by the Contractor at his own expense and the Contractor will pay any damages and costs awarded in such suit. The Contractor shall promptly notify the Employer/ Owner if the Contractor has acquired the knowledge of any plant under which a suit for infringement could be reasonably brought because of the use by the Employer/ Owner of any equipment, machinery, materials, process, methods to be supplied hereunder. The Contractor agrees to and does hereby grant to Employer/ Owner, together with the right to extend the same to any of the subsidiaries of the Employer/ Owner as irrevocable, royalty free license to use in any country, any invention made by the Contractor or his employee in or as result of the performance of the Work under the Contract.

36.2 All charges on account of royalty, tollage, rent or any other levy on materials obtained for the work or temporary work or part thereof (excluding materials provided by the Employer/ Owner, if any) shall be borne by the Contractor.

36.3 The Contractor shall not sell or otherwise dispose of or remove except for the purpose of this Contract, the sand, stone, clay, ballast, earth, rock or other substances, or materials obtained from any excavation made for the purpose of the Work or any building or produce upon the site at the time of delivery of the possession thereof, but all such substances, materials, buildings and produce shall be the property of the Employer/ Owner provided that the Contractor may with the permission of the Engineer-in-Charge/Project Manager, use the same for the purpose of the work by payment of cost of the same at such a rate as may be determined by the Engineer-in-Charge/Project Manager.

37. Liens

37.1 If, at any time there should be evidence or any lien or claim for which the Employer/ Owner might have become liable and which is chargeable to the Contractor, the Employer/ Owner shall have the right to retain out of any payment then due or thereafter to become due an amount sufficient to completely indemnify the Employer/ Owner against such lien or claim and if such lien or claim be valid, the Employer/ Owner may pay and discharge the same and deduct the amount so paid from any money which may be or may become due and payable to the Contractor. If any lien or claim remain unsettled after all payments are made, the Contractor shall refund or pay to the Employer/ Owner all money that the latter may be compelled to pay in discharging such lien or claim including all costs and reasonable expenses. Employer/ Owner reserves the right to do the same.

37.2 The Employer/ Owner shall have lien on all materials, equipment including those brought by the Contractor for the purpose of erection, testing and commissioning of the Work.

37.3 The final payment shall not become due until the Contractor delivers to the Engineer-in-Charge/Project Manager a complete release or waiver of all liens arising or which may arise out of his agreement or receipt in full or certification by the Contractor in a form approved by Engineer-in-Charge/Project Manager that all invoices for labour, materials, services have been paid in lien thereof and if required by the Engineer-in-Charge/Project Manager in any case an affidavit that so far as the Contractor has knowledge or information the releases and receipts include all the labour and material for which a lien could be filled.

37.4 Contractor will indemnify and hold the Employer/ Owner harmless, for a period of 02 (Two) years after the issue of Final Certificate, from all liens and other encumbrances against the Employer/ Owner on account of debts or claims alleged to be due from the Contractor or his Sub-Contractor to any person including Sub-Contractor and on behalf of Employer/ Owner will defend at his own expense, any claim or litigation brought against the Employer/ Owner or the Contractor in connection therewith. Contractor shall defend or contest at his own expense any fresh claim or litigation by any

person including his Sub-Contractor, till its satisfactory settlement even after the expiry of 02 (Two) years from the date of issue of Final Certificate.

38. Delays by Employer/ Owner or his Authorized Agents

- 38.1 In case the Contractor's performance is delayed due to any act or omission on the part of the Employer/ Owner or his authorized agents, then the Contractor may be given due extension of time for the completion of the Work after proper due diligence by Employer/ Owner, to the extent such omission on the part of the Employer/ Owner has caused delay in the Contractor's performance of his Work.
- 38.2 No adjustment in Contract Price shall be allowed for reasons of such delays and extensions granted except as provided in Tender Document, where the Employer/ Owner reserves the right to seek indulgence of Contractor to maintain the agreed Time Schedule of Completion. In such an event the Contractor shall be obliged for working by Contractor's personnel for additional time beyond stipulated working hours as also Sundays and Holidays and achieve the completion date/interim targets.

39. Payment if the Contract is Terminated

- 39.1 If the Contract shall be terminated as per the provisions of the Tender/ Contract, the Contractor shall be paid by the Employer/ Owner in so far as such amounts or items shall not have already been covered by payments of amounts made to the Contractor for the Work executed and accepted by Engineer-in-Charge/Project Manager prior to the date of termination at the rates and prices provided for in the Contract and in addition to the following:

- a) The amount payable in respect of any preliminary items, so far as the Work or service comprised therein has been carried out or performed and an appropriate portion as certified by Engineer-in-Charge of any such items or service comprised in which has been partially carried out or performed.
- b) Any other expenses which the Contractor has expended for performing the Work under the Contract subject to being duly recommended by Engineer-in-Charge/Project Manager and approved by Employer/ Owner for payment, based on documentary evidence of his having incurred such expenses.

- 39.2 The Contractor will be further required to transfer the title, Guarantee/Warranty of the Material/Products/Spares of the works & Projects including but not limited to PV Modules, Power Conditioning Units (PCU)/ Inverters, Transformers, Batteries (If applicable) etc and provide the following in the manner and as directed by the Employer/ Owner.

- a) Any and all completed works.
- b) Such partially completed Work including drawings, information and Contract rights as the Contractor has specially performed, produced or acquired for the performance of the Contractor.

40. No Waiver of Rights

- 40.1 Neither the inspection by the Employer/ Owner or any of their officials, Employees or Agents nor any order by the Employer/ Owner for payment of money or any payment for or acceptance of the whole or any part of the Work by the Employer/ Owner nor any extension of time, nor any possession taken by Employer/ Owner shall operate as a waiver of any provision of the Contract, or of any power herein reserved to the Employer/ Owner, or any right to damages herein provided, nor shall any waiver of any breach in the Contract be held to be a waiver of any other subsequent breach.

41. Certificate not to Affect Right of Employer and Liability of Contractor

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 34 of 77</u>	Signature of Bidder

- 41.1 No interim payment certificate(s) issued by the Engineer-in-Charge/Project Manager of the Employer/ Owner, nor any sum paid on account by the Employer/ Owner, nor any extension of time for execution of the work granted by Employer/ Owner shall affect or prejudice the rights of the Employer/ Owner against the Contractor or relieve the Contractor of his obligations for the due performance of the Contract, or be interpreted as approval of the Work done or of the equipment supplied and no certificate shall create liability for the Employer/ Owner to pay for alterations, amendments, variations or additional works not ordered, in writing, by Employer/ Owner or discharge the liability of the Contractor for the payment of damages whether due, ascertained, or certified or not or any sum against the payment of which he is bound to indemnify the Employer/ Owner.

42. Language and Measures

- 42.1 All documents pertaining to the Contract including Specifications, Schedules, Notices, Correspondence, Operating and Maintenance Instructions, Drawings or any other writing shall be written in English language only. The SI System of measurement shall be used in the Contract unless otherwise specified.

43. Guarantee Tests & Operations Acceptance and Transfer of Title

43.1 Functional Guarantees

- 43.1.1 The Contractor guarantees that during the Guarantee Test, the Facilities and all parts thereof shall attain the Functional Guarantees specified under Technical Specifications, subject to and upon the conditions therein specified.
- 43.1.2 If, for reasons attributable to the Contractor, the guaranteed level of the Functional Guarantees specified under Technical Specifications are not met either in whole or in part, the Contractor shall, within a mutually agreed time, at its cost and expense make such changes, modifications and/ or additions to the Plant or any part thereof as may be necessary to meet such Guarantees. The Contractor shall notify the Employer/Owner upon completion of the necessary changes, modifications and/or additions, and shall seek the Employer's/Owner's consent to repeat the Guarantee Test. If the level of the specified Functional Guarantee parameters, as demonstrated even during repeat of the Guarantee Test(s), are outside the acceptable shortfall limit, the Employer//Owner may at its option, either
- Reject the Equipment and advise immediate replacement to suit the provisions of Technical Specification without any additional cost or;
 - Reject the Equipment and recover the payments already made, or;
 - Terminate the Contract and recover the payments already made, or;
 - Accept the equipment after levy of liquidated damages in accordance with the provisions specified.

43.2 Plant Performance Guarantee Test

The Plant Performance Guarantee (as mentioned in TS) Test shall be conducted by the Contractor after Commissioning of the Facilities to ascertain whether the Facilities or the relevant part(s) can attain the Functional Guarantees specified in the Contract Documents. The Contractor's and Project Manager's advisory personnel shall attend the Guarantee Test. The Employer//Owner shall promptly provide the Contractor with such information as the Contractor may reasonably require in relation to the conduct and results of the Guarantee Test (and any repeats thereof). The detailed procedure for Performance Guarantee Test shall be carried out as per procedure laid down in Technical Specifications.

43.3 Operational Acceptance

- 43.3.1 Operational Acceptance shall occur in respect of the Facilities when:

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 35 of 77</u>	<u>Signature of Bidder</u>

- The Plant Performance Guarantee Test (PR Test) in accordance with the procedure specified IN The Tender document Specifications has been successfully completed and the Functional Guarantees are met; or
 - The Contractor has paid the liquidated damages, if any, specified in GCC Clause hereof;
- 43.3.2 At any time after any of the events set out in GCC Sub- Clause have occurred, the Contractor may give a notice to the Project Manager requesting the issue of an Operational Acceptance Certificate in the form provided in the Bidding Documents or in another form acceptable to the Employer//Owner in respect of the Facilities or the part thereof specified in such notice as at the date of such notice.
- 43.3.3 The Project Manager shall, after consultation with the Owner/ Employer, and within thirty (30) days after receipt of the Contractor's notice, issue an Operational Acceptance Certificate.
- 43.3.4 If within thirty (30) days after receipt of the Contractor's notice, the Project Manager fails to issue the Operational Acceptance Certificate or fails to inform the Contractor in writing of the justifiable reasons why the Project Manager has not issued the Operational Acceptance Certificate, the Facilities shall be deemed to have been accepted as at the date of the Contractor's said notice.
- 43.3.5 Subsequent to Operational Acceptance of the Facilities by the Employer/Owner and within 10 days of the commencement of the O&M period, the Contractor shall furnish an Indemnity Bond which is to be executed by the contractor for the Plant handed over by Employer/Owner for performance of its O&M Contract (Entire Solar Photo Voltaic Plant).

43.4 Final Acceptance

- 43.4.1 Final Acceptance shall occur in respect of the Facilities when:
- The Plant have achieved the Operational acceptance and served the O&M for the period stipulated under the contract agreement; and
 - All the contractors' liabilities under the O&M contract have been satisfied; and
 - Contractor has provided the list of recommended spares with detailed specification, source and price for further procurement; and
 - The Contractor has paid the liquidated damages, if any thereto;
- 43.4.2 At any time after the events set out in GCC Sub – Clause have occurred, the Contractor may give a notice to the Project Manager requesting the issue of Final Acceptance Certificate in the form provided in the Bidding Documents or in another form acceptable to the Owner/ Employer in respect of the Facilities or the part thereof specified in such notice as at the date of such notice.
- 43.4.3 The Project Manager shall, after consultation with the Employer/Owner, and within thirty (30) days after receipt of the Contractor's notice, issue Final Acceptance Certificate.
- 43.4.4 If within thirty (30) days after receipt of the Contractor's notice, the Project Manager fails to issue the Final Acceptance Certificate or fails to inform the Contractor in writing of the justifiable reasons why the Project Manager has not issued the Final Acceptance Certificate, the Facilities shall be deemed to have been accepted as at the date of the Contractor's said notice.
- 43.4.5 The O&M contract period may further be extended for minimum period of 5 years as per mutually agreed terms and conditions. The contractor is allowed to submit his intent at the time of Final acceptance.
- 43.5 The title of Ownership of supplies furnished by the Contractor shall not pass on to the Employer/ Owner for all Supplies till the same are finally accepted by the Employer/ Owner after the successful completion of Performance Test and Guarantee Test and issuance of Final Certificate.

43.6 However, the Employer/ Owner shall have the lien on all such works performed as soon as any advance or progressive payment is made by the Employer/ Owner to the Contractor and the Contractor shall not subject these works for use other than those intended under this Contract.

44. Release of Confidential Information

44.1 The Contractor shall not communicate or use in advertising, publicity, sales releases or in any other medium, photographs, or other reproduction of the Work under this Contract or description of the site dimensions, quantity, quality or other information, concerning the Work unless prior written permission has been obtained from the Employer/ Owner.

44.2 The Owner/ Employer and the Contractor shall keep confidential and shall not, without the written consent of the other party hereto, divulge to any third party any documents, data or other information furnished directly or indirectly by the other party hereto in connection with the Contract, whether such information has been furnished prior to, during or following termination of the Contract. Notwithstanding the above, the Contractor may furnish to its Subcontractor(s) such documents, data and other information it receives from the Employer/Owner to the extent required for the Subcontractor(s) to perform its work under the Contract, in which event the Contractor shall obtain from such Subcontractor(s) an undertaking of confidentiality similar to that imposed on the Contractor.

44.3 The Owner/ Employer shall not use such documents, data and other information received from the Contractor for any purpose other than the operation and maintenance of the Facilities. Similarly, the Contractor shall not use such documents, data and other information received from the Owner/ Employer for any purpose other than the design, procurement of Plant and Equipment, construction or such other work and services as are required for the Performance of the Contract.

44.4 The obligation of a party above, however, shall not apply to that information which

- Now or hereafter enters the public domain through no fault of that party
- Can be proven to have been possessed by that party at the time of disclosure and which was not previously obtained, directly or indirectly, from the other party hereto.
- Otherwise lawfully becomes available to that party from a third party that has no obligation of confidentiality.

44.5 The above provisions of this GCC shall not in any way modify any undertaking of confidentiality given by either of the parties hereto prior to the date of the Contract in respect of the Facilities or any part thereof.

44.6 The provisions of this GCC Clause 44 shall survive termination, for whatever reason, of the Contract.

45. Operation & Maintenance

45.1 The Operation and Maintenance shall be comprehensive. The maintenance service provided shall ensure project functioning of the Solar PV system as a whole and Power Evacuation System to the extent covered in the Contract. All preventive / routine maintenance and breakdown / corrective maintenance required for ensuring maximum uptime shall have to be provided. Accordingly, the Comprehensive Operation & Maintenance shall have two distinct components as described below:

45.2 Preventive / Routine Maintenance:

This shall be done by the Contractor regularly and shall include activities such as cleaning and checking the health of the Solar PV system, cleaning of module surface, tightening of all electrical connections, and any other activity including the associated civil works, as mentioned in TS Clause , wear and tear that may be required for proper functioning of the Solar PV system as a whole.

Necessary maintenance activities, Preventive and Routine for Transformers and associated switch gears and transmission line also shall be included.

45.3 Breakdown / Corrective maintenance:

Whenever a fault occurs, the Contractor has to attend to rectify the fault & the fault must be rectified within the 24 hours from the time of occurrence of fault, failing which the Contractor will be liable for additional liquidated damages as per reference to the generation parameters accumulated in similar/ associated equipment of the Plant (for example if a block consists of 4 inverters and one inverter is down for more than 24 hours, then the generation for faulty inverter shall be calculated as the average of accumulated generation for the other 3 inverters over the 24 hours duration of fault as the deemed generation) and the LD shall be levied on the deemed generation as per the tariff of Rs. 5.50 per unit. The contractor must maintain all the records pertaining to all such faults and necessary measures taken.

The date of Comprehensive Operation & Maintenance Contract period shall begin on the date of Successful demonstration of guaranteed PR i.e., Operational acceptance. However, operation of the Power Plant means operation of system as per bid and workmanship in order to keep the project trouble free covering the guarantee period. The contractor must demonstrate the committed CUF at the end of every year in accordance with commitment made in the Techno-Commercial Enclosures of the Bid.

45.4 Serviceability Level Agreement (SLA)

- 45.4.1 Contractor shall make efforts to maintain 100 % serviceability of complete Plant including all other associated infrastructure developed by the Contractor during execution of project as its scope of work.
- 45.4.2 Contractor shall produce monthly serviceability report for individual components of the plant & associated infrastructure to the employer//Owner by 5th of next month.
- 45.4.3 Contractor shall maintain a Complaint log book, which shall include the timing of logging of complaint including unique Complaint number, time of closure of complaint & it's Root Cause Analysis.
- 45.4.4 Any complaint related to unserviceability/improper functioning of any & all component of the plant including but not limited to PV Module, PCU, Transformers, switchgears, SCADA, roads, drainage, water supply lighting system, office infrastructure, CCTV system which is not attended & rectified within 48 hours, shall attract a penalty of Rs. 1000 per 24 hours, which shall be over & above GCC Clause. If such complaint is not rectified within 480 hours from logging of complaint. Employer/Owner may choose to rectify the same through any other agency at the risk of Contractor and Employer/Owner shall recover 110% of such cost incurred from subsequent payment to the contractor.
- 45.4.5 Such rectification work carried out by employer/Owner doesn't exempts/relieves Contractor from its responsibility towards subsequent operation, maintenance, repair & replacement of such component/ infrastructure of the Plant or meeting the performance parameters of the Plant.
- 45.4.6 O&M Routine & Manpower: Contractor shall provide Preventive / Routine Maintenance schedule based on Original Equipment manufacturer and good engineering practices. The team deployed for the O&M must have a minimum manpower structure with following qualification;
Project Manager (B.E./B.Tech Electrical, with minimum 5 years of relevant experience) -1 No.
Shift Engineers (BE/B-Tech Electrical, with minimum 3 years of relevant experience) –1 No / Shift
Polytechnic/Diploma Electrical (with minimum 3 years of relevant experience) -2 / shift
Polytechnic/Diploma Mechanical or Civil (with minimum 3 years of relevant experience) -1/shift
Unskilled for cleaning & other unskilled works with respect to Plant -minimum 3/shift.
However contractor shall engage additional manpower as and when need arise.

46. Completion of Contract

46.1 Unless otherwise terminated under the provisions of any other relevant clause, this Contract shall be deemed to have been completed at the expiration of the Period of Liability/ Validity of the Contract as provided under Section - V, Special Conditions of Contract (SCC).

47. Commissioning & Spares

47.1 As soon as installation of the Facilities has, in the opinion of the Contractor, been completed as specified in the Technical Specifications, excluding minor items not materially affecting the operation or safety of the Facilities, the Contractor shall so notify the owner/ Employer (Project Manager/ EIC) in writing to witness the pre- commissioning of the facility.

47.2 As soon as all works in respect of Pre-commissioning are completed and, in the opinion of the Contractor, the Facilities is ready for Commissioning, the Contractor shall so notify the Project Manager in writing. The Contractor shall commence Commissioning of the facilities as per the GCC Sub.

47.3 Commissioning of the Facilities shall be completed by the Contractor as per procedures detailed in the Technical Specifications and in the presence of the Project Manager or the representatives of the Owner/ Employer.

47.4 If the Project Manager notifies the Contractor of any defects and/or deficiencies, the Contractor shall then correct such defects and/or deficiencies, and shall repeat the procedure described in GCC Sub- Clause.

47.5 If the Project Manager is satisfied that the Facilities have reached Completion, the Project Manager shall, within seven (7) days after receipt of the Contractor's repeat notice, issue a Completion Certificate stating that the Facilities have reached Completion as at the date of the Contractor's repeat notice.

47.6 If the Project Manager is not so satisfied, then it shall notify the Contractor in writing of any defects and/or deficiencies within seven (7) days after receipt of the Contractor's repeat notice, and the above procedure shall be repeated.

47.7 If the Project Manager fails to issue the Completion Certificate and fails to inform the Contractor of any defects and/or deficiencies within fourteen (14) days after receipt of the Contractor's notice under GCC Clause or within seven (7) days after receipt of the Contractor's repeated notice under GCC Clause, or if the Employer/Owner makes use of the Facilities, then the Facilities shall be deemed to have reached Completion as of the date of the Contractor's notice or repeated notice, or as of the Employer's/Owner's use of the Facilities, as the case may be.

47.8 As soon as possible after Completion, the Contractor shall complete all outstanding minor items so that the Facilities are fully in accordance with the requirements of the Contract, failing which the Owner/ Employer will undertake such completion and deduct the costs thereof from any monies owing to the Contractor.

47.9 Upon Completion, commissioning and successful demonstration of the PR test, the contractor shall be responsible for the care and custody of the Facilities, together with the risk of loss or damage thereto, and shall thereafter take over the Facilities or the relevant part thereof for the agreed duration of operation and maintenance as stipulated and mutually agreed terms and conditions.

The Contractor shall furnish to the Employer/ Owner all spares required for Commissioning of the plants, recommendatory and/ or mandatory spares, which are required essential by the

manufacturer/ supplier. The same shall be delivered at Site prior to Commissioning. Also, the Contractor should furnish the manufacturing drawings for fast wearing spares.

[E] PERFORMANCE OF WORK

48. Execution of Work

- 48.1 All the Works shall be executed in strict conformity with the provisions of the Contract Documents and with such explanatory detailed drawings, specification and instructions as may be furnished from time to time to the Contractor by the Engineer-in-Charge/Project Manager whether mentioned in the Contract or not. The Contractor shall be responsible for ensuring that works throughout are executed in the most substantial, proper and workmanlike manner with the quality of material and workmanship in strict accordance with the Specifications and to the entire satisfaction of the Engineer-in-Charge/Project Manager. The Contractor shall provide all necessary materials equipment labour etc. for execution and maintenance of Work till completion unless otherwise mentioned in the Contract.
- 48.2 All materials shall be of the best quality and workmanship capable of satisfactory operation under the operating and climatic conditions as may be specified. Unless otherwise specified, they shall conform in all respect to the latest edition of the relevant IS codes specification wherever Indian specifications apply or IEC codes or equivalent internationally accepted standard.
- 48.3 The Contractor shall supply & deliver all equipment and materials for installation at site. The Contractor shall arrange for transportation, loading & unloading and safe storage of materials at project site at his own cost & risk.
- 48.4 If the Contractor offers equipment manufactured in accordance with other international well recognized standards (mentioned above), he shall, in that case, supply a copy in English of the Standard Specification adopted and shall clearly mention in what respect such standard specification differs from Indian Standard Specifications. The Plant, equipment, and materials offered by the Contractor should comply with one consistent set of Standards only to make the system compatible and work in harmony as far as possible, except if mentioned otherwise.

49. Unforeseen/ Differing site Conditions

- 49.1 If, during the execution of the Contract, the Contractor shall encounter on the Site any physical conditions (other than climatic conditions) or artificial obstructions that could not have been reasonably foreseen prior to the date of the Contract Agreement by an experienced contractor on the basis of reasonable examination of the data relating to the Facilities, and on the basis of information that it could have obtained from a visual inspection of the Site (if access thereto was available) or other data readily available to it relating to the Facilities, and if the Contractor determines that it will in consequence of such conditions or obstructions incur additional cost and expense or require additional time to perform its obligations under the Contract that would not have been required if such physical conditions or artificial obstructions had not been encountered, the Contractor shall promptly, and before performing additional work or using additional Plant and Equipment or Contractor's Equipment, notify the Project Manager in writing of
- The physical conditions or artificial obstructions on the Site that could not have been reasonably foreseen
 - The additional work and/or Plant and Equipment and/ or Contractor's Equipment required, including the steps which the Contractor will or proposes to take to overcome such conditions or obstructions
 - The extent of the anticipated delay
 - The additional cost and expense that the Contractor is likely to incur and the breakup of the same.

On receiving any notice from the Contractor under this GCC Sub- Clause, the Project Manager shall consult and decide upon the actions to be taken to overcome the physical conditions or artificial obstructions encountered. Following such consultations, the Project Manager shall instruct the Contractor of the actions to be taken.

49.2 Any reasonable additional cost and expense incurred by the Contractor in following the instructions from the Project Manager to overcome such physical conditions or artificial obstructions referred to in GCC Clause shall be paid by the Employer/Owner to the Contractor as an addition to the Contract Price, after submission of relevant documents justifying same.

49.3 If the Contractor is delayed or impeded in the Performance of the Contract because of any such physical conditions or artificial obstructions referred to in GCC Clause, the Time for Completion shall be extended in accordance with GCC Clause.

50. Work in Monsoon and Dewatering

50.1 Unless otherwise specified elsewhere in the tender, the execution of the Work may entail working in the monsoon also. The Contractor must maintain a minimum labour force as may be required for the job and plan and execute the construction and erection according to the prescribed schedule. No extra rate will be considered for such work in monsoon.

50.2 During monsoon and other period, it shall be the responsibility of the Contractor to keep the construction work site free from water at his own cost.

51. Change in Laws and Regulations

51.1 If, after the date seven (7) days prior to the date of Bid submission, in the country where the Site is located, any law, regulation, ordinance, order or by-law having the force of law is enacted, promulgated, abrogated or changed (which shall be deemed to include any change in interpretation or application by the competent authorities) that subsequently affects the costs and expenses of the Contractor and/or the Time for Completion, the Contract Price shall be correspondingly increased or decreased, and/or the Time for Completion shall be reasonably adjusted to the extent that the Contractor has thereby been affected in the Performance of any of its obligations under the Contract. However, these adjustments would be restricted to direct transactions between the Employer//Owner and the Contractor/assignee of Foreign Contractor (if applicable). This adjustment shall not be applicable on procurement of raw materials, intermediary components etc. by the Contractor and shall also not be applicable on bought out items dispatched directly from sub- vendor works to site. Notwithstanding the foregoing, such additional or reduced costs shall not be separately paid or credited if the same has already been accounted for in the price adjustment provisions where applicable.

52. General Conditions for Construction and Erection Work

52.1 The working time at the site of work is 48 hours per week. Overtime work is permitted in cases of need and the Employer/ Owner will not compensate the same. Shift working at 2 or 3 shifts per day may become necessary and the Contractor should take this aspect into consideration for formulating his rates for quotation. No extra claims will be entertained by the Employer/ Owner on this account.

52.2 The Contractor must arrange for the placement of workers in such a way that the delayed completion of the Work or any part thereof for any reason whatsoever will not affect their proper employment. The Employer/ Owner will not entertain any claim for idle time payment whatsoever.

52.3 The Contractor shall submit to the Employer/ Owner/ Engineer-in-Charge/Project Manager reports at regular intervals regarding the state and progress of Work. The details and proforma of the report will mutually be agreed after the award of Contract. The Contractor shall provide display boards

showing progress and labour strengths at worksite, as directed by the Engineer-in-Charge/Project Manager.

53. Design and Engineering

53.1 The Work covered under this Contract having to be executed by the Contractor on a lump-sum firm price/ item rate quoted by him, the Employer/ Owner will not accept any proposals for changes in Value of Contract or extension in time on account of any such changes which may arise to the Contractor's scope of Work as a result of detailed Engineering and thereafter during the execution of Work. The only exception to this will be a case where the Employer/ Owner requests in writing to the Contractor to upgrade the Specifications or the size of any major pieces of equipment, plant or machinery beyond what is normally required to meet the scope of Work as defined in the Contract Document. In such cases, a change order will be initialed by the Contractor at the appropriate time for the Employer's/ Owner's prior approval giving the full back-up data for their review and for final settlement of any impact on price.

53.2 Specifications and Drawings

53.2.1 The Contractor shall execute the basic and detailed design and engineering work in compliance with the provisions of the Contract, or where not so specified, in accordance with good and sound engineering practice.

53.2.1 The Contractor shall be responsible for any discrepancies, errors or omissions in the specifications, drawings and other technical documents that it has prepared, whether such specifications, drawings and other documents have been approved by the Project Manager/ EIC or not, provided that such discrepancies, errors or omissions are not because of inaccurate information furnished in writing to the Contractor by or on behalf of the Owner/ Employer.

53.2.2 The Contractor shall be entitled to disclaim responsibility for any design, data, drawing, specification or other document, or any modification thereof provided or designated by or on behalf of the Owner/ Employer, by giving a notice of such disclaimer to the Project Manager/ EIC.

53.3 Codes and Standards

53.3.1 Wherever references are made in the Contract to codes and standards in accordance with which the Contract shall be executed, the edition or the revised version of such codes and standards current at the date of bid submission shall apply unless otherwise specified.

53.3.2 Approval / Review of Technical Documents by Project Manager

The Contractor shall prepare list of documents as per technical specifications and furnish to the Project Manager for Approval of the same and Review of work schedule.

Any part of the Facilities covered by or related to the documents to be approved by the Project Manager shall be executed only after the Project Manager's approval thereof.

53.3.3 Within ten (10) days after receipt by the Project Manager of any document requiring the Project Manager's approval, the Project Manager shall either return one copy thereof to the Contractor with its approval endorsed thereon or shall notify the Contractor in writing of its disapproval thereof and the reasons therefor and the modifications that the Project Manager proposes.

53.3.4 The Project Manager shall not disapprove any document, except on the grounds that the document does not comply with some specified provision of the Contract or that it is contrary to good engineering practice.

53.3.5 If the Project Manager disapproves the document, the Contractor shall modify the document and resubmit it for the Project Manager's approval. If the Project Manager approves the document

subject to modification(s), the Contractor shall make the required modification(s), and upon resubmission with the required modifications the document shall be deemed to have been approved.

- 53.3.6 The procedure for submission of the documents by the Contractor and their approval by the Project Manager shall be as per the Contract Co-ordination procedure.
- 53.3.7 If any dispute or difference occurs between the Employer//Owner and the Contractor in connection with or arising out of the disapproval by the Project Manager of any document and/or any modification(s) thereto that cannot be settled between the parties within a reasonable period, then such dispute or difference may be settled in accordance with GCC Clause (Settlement of Dispute) hereof. If such dispute or difference is referred as per GCC clause, the Project Manager shall give instructions as to whether and if so, how, Performance of the Contract is to proceed. The Contractor shall proceed with the Contract in accordance with the Project Manager's instructions, provided that if the Arbitration upholds the Contractor's view on the dispute, then the Contractor shall be reimbursed by the Owner/ Employer for any additional costs incurred by reason of such instructions and shall be relieved of such responsibility or liability in connection with the dispute and the execution of the instructions as the Arbitration shall decide, and the Time for Completion shall be extended accordingly.
- 53.3.8 The Project Manager's approval, with or without modification of the document furnished by the Contractor, shall not relieve the Contractor of any responsibility or liability imposed upon it by any provisions of the Contract except to the extent that any subsequent failure results from modifications required by the Project Manager.
- 53.3.9 The Contractor shall not depart from any approved document unless the Contractor has first submitted to the Project Manager an amended document and obtained the Project Manager's approval thereof, pursuant to the provisions of this GCC Clause.

If the Project Manager requests any change in any already approved document and/or in any document based thereon, generally shall be taken care by the contractor if the change is not causing any major financial impact.

54. Drawings to be Supplied by the Owner/Employer

- 54.1 The drawings attached with tender, if any, are only for the general guidance to the Contractor to enable him to visualize the type of work contemplated and scope of work involved. The Contractor will be deemed to have studied the Drawings and formed an idea about the Work involved.
- 54.2 Detailed working drawings on the basis of which actual execution of the Work is to proceed, will be furnished from time to time during the progress of the work. The Contractor shall be deemed to have gone through the Drawings supplied to him thoroughly and carefully and in conjunction with all other connected drawings and bring to the notice of the Engineer-in-Charge/Project Manager discrepancies, if any, therein before actually carrying out the Work.
- 54.3 Copies of all detailed working drawings relating to the Work shall be kept at the Contractor's office on the site and shall be made available to the Engineer-in-Charge/Project Manager at any time during the Contract. The drawings and other documents issued by the Employer/ Owner shall be returned to the Employer/ Owner on completion of the Work.

55. Drawings to be Supplied by the Contractor

- 55.1 The drawings/ data which are to be furnished by the Contractor shall be furnished within the specified time.
- 55.2 Where approval/ review of drawings before manufacture/ construction/ fabrication has been specified, it shall be Contractor's responsibility to have these drawings prepared as per the directions

of Engineer-in-Charge/Project Manager and got approved before proceeding with manufacture/ construction/ fabrication as the case may be. Any change that may have become necessary in these drawings during the execution of the work shall have to be carried out by the Contractor to the satisfaction of Employer/ Owner at no extra cost. All final drawings shall bear the certification stamp duly signed by both the Contractor and Engineer-in-Charge/Project Manager.

55.3 The Drawings submitted by the Contractor shall be reviewed by the Engineer-in-Charge/Project Manager as far as practicable within 10 (Ten) working days and shall be modified by the Contractor, if any modifications and/ or corrections are required by the Engineer-in-Charge/Project Manager. The Contractor shall incorporate such modifications and/ or corrections and submit the final drawings for approval. Any delays arising out of failure by the Contractor to rectify the drawing in good time shall not alter the Contract Completion Time.

55.4 As built drawings showing all corrections, adjustments etc. shall be furnished by the Contractor in 06 (Six) Hard Copies and 01 (One) Soft Copy for record purposed to the Employer/ Owner. GFC drawings shall be provided in soft as well as Hard form to employer/Owner for reference at site. Provision should be made for digitally signing GFC Drawings and making hard copies available at site.

56. Setting out Works

56.1 The Contractor shall provide, fix and be responsible for the maintenance of all stakes, templates, level marks, profiles and other similar things and shall take all necessary precautions to prevent their removal or disturbance and shall be responsible for the consequence of such removal or disturbance should the same take place and for their efficient and timely reinstatement. The Contractor shall also be responsible for the maintenance of all existing survey marks, boundary marks, distance marks and center line marks, either existing or supplied and fixed by the Contractor. The work shall be set out to the satisfaction of the Engineer-in-Charge/Project Manager. The approval there of joining with the Contractor by the Engineer-in-Charge/Project Manager in setting out the work, shall not relieve the Contractor of any of his responsibility.

56.2 Before beginning the Works, the Contractor shall at his own cost, provide all necessary reference and level posts, pegs, bamboos, flags, ranging rods, strings and other materials for proper layout of the works in accordance with the schemes for bearing marks acceptable to the Engineer-in-Charge/Project Manager. The center, longitudinal or face lines and cross lines shall be marked by means of small masonry pillars. Each pillar shall have distinct mark at the center to enable theodolite to be set over it. No work shall be started until all these points are checked and approved by the Engineer-in-Charge/Project Manager in writing but such approval shall not relieve the Contractor of any of his responsibilities. The Contractor shall also provide all labour, material and other facilities, as necessary, for the proper checking of layout and inspection of the points during construction.

56.3 Pillars bearing geodetic marks located at the sites of units of Works under construction should be protected and fenced by the Contractor.

56.4 On completion of Work, the Contractor must submit the geodetic documents according to which the Work was carried out.

57. Geological Discoveries

All fossils, coins, articles of value or antiquity and structures and other remains or things of geological or archaeological interest discovered on the site where the services are performed, be deem to be the absolute property of the Employer/Owner. The Contractor shall take reasonable precautions to prevent the personnel or any other persons from removing or damaging any such article or thing and shall immediately upon the discovery thereof and, before removal, acquaint the

Employer/Owner of such discovery any carry out, at the expense of the Employer/Owner, the Employer's/Owner's orders as to the disposal of the same.

58. Materials to be Supplied by Contractor

58.1 Plant and Equipment

The Contractor shall procure and transport all the Plant and Equipment in an expeditious and orderly manner to the Site to achieve completion of activities as per schedule to enable commissioning of the Project by the scheduled commissioning date.

58.2 Transportation

The contractor shall ensure that all the plant and equipment required to complete the Facility at site, are procured and dispatched on FOR site basis. The Contractor shall at its own risk and expense transport all the Plant and Equipment and the Contractor's Equipment to the Site by the mode of transport that the Contractor judges most suitable under all the circumstances.

58.3 Packing and Marking

The Contractor shall be responsible for securely protecting and packing the plant & equipment as per prescribed standards in force to withstand the journey and ensuring safety of materials and also arrival of materials at destination in original condition and good for contemplated use. Packing case size & weight shall take into consideration the remoteness of the goods final destination and absence of heavy material handling facilities at all points in transit.

Packing lists of materials shall be provided in each package to facilitate checking up of the contents at the destination.

In order to import any items, associated with the Solar PV Power Project, from abroad or from any other state in India, Contractor shall have to arrange any clearance, permission, if required at his own risk, from any Government (Government of State & Government of India) or any Government (Government of State & Government of India) controlled organization for transportation of materials from manufacturing shop to delivery at Site. Necessary certificates, if so required, shall be issued by the Owner/ Employer within reasonable time after getting written request from the Contractor along with the necessary documents substantiating necessity of such approvals. Contractor shall take necessary insurances to ensure safe transit. All packing material is the property of the Employer/Owner and shall be immediately deposited by the Contractor to the Employer's/Owner's Store at project Site.

58.4 Storage of Equipment

The plant and equipment thus procured under the scope of the contract must be kept in safe custody till put under operation. All the spares, as required for the trouble free O&M of Plant, must be kept under secure storage during O&M period.

The Contractor shall procure and provide within the Value of Contract the whole of the materials required for the construction including steels, cement and other building materials, tools, tackles, construction plant and equipment for the completion and maintenance of the Work except the materials which will be issued by the Employer/ Owner and shall make his own arrangement for procuring such materials and for the transport thereof. The Employer/ Owner may give necessary recommendation to the respective authority if so desired by the Contractor but assumes no further responsibility of any nature. The Employer/ Owner will insist on the procurement of materials which bear ISI stamp and/ or which are supplied by reputed suppliers.

- 58.5 The Contractor shall properly store all materials either issued to him or brought by him to the Site to prevent damages due to rain, wind, direct exposure to sun, etc. as also from theft, pilferage, etc. for proper and speedy execution of his works. The Contractor shall maintain sufficient stocks of all materials required by him.
- 58.6 No material shall be dispatched from the Contractor's stores before obtaining the approval in writing of the Engineer-in-Charge/Project Manager.

59. Stores Supplied by the Employer/ Owner

- 59.1 If the Specification of the Work provides for the use of any material of special description to be supplied from the Employer's/ Owner's stores or it is required that the Contractor shall use certain stores to be provided by the Employer/ Owner, such materials and stores, there for as hereinafter mentioned being so far as practicable for the convenience of the Contractor, but not so as in any way to control the meaning or effect of the Contract, the Contractor shall be bound to purchase and shall be supplied such materials and stores as are from time to time required to be used by him for the purpose of the Contract only. After the completion of the Work, however, the Contractor has to account for the full quantity of materials supplied to him as per relevant clauses in this document.
- 59.2 All materials so supplied to the Contractor shall remain the absolute property of the Employer/ Owner and shall not be removed on any account from the Site of the Work, and shall be at all times open for inspection to the Engineer-in-Charge/Project Manager. Any such materials remaining unused at the time of the completion or termination of the Contract shall be returned to the Employer's/ Owner's stores or at a place as directed by the Engineer-in-Charge/Project Manager in perfectly good condition at Contractor's cost.

60. Conditions for Issue of Materials

- 60.1 i) Materials specified as to be issued by the Employer/ Owner will be supplied to the Contractor by the Employer/ Owner from his stores. It shall be responsibility of the Contractor to take delivery of the materials and arrange for its loading, transport and unloading at the Site of Work at his own cost. The materials shall be issued between the working hours and as per the rules of the Employer/ Owner as framed from time to time.
- ii) The Contractor shall bear all incidental charges for the storage and safe custody of materials at site after these have been issued to him.
- iii) Materials specified as to be issued by the Employer/ Owner shall be issued in standard sizes as obtained from the manufacturers.
- iv) The Contractor shall construct suitable godowns at the Site of Work for storing the materials safe against damage by rain, dampness, fire, theft etc. He shall also employ necessary watch and ward establishment for the purpose.
- v) It shall be duty of the Contractor to inspect the materials supplied to him at the time of taking delivery and satisfy himself that they are in good condition. After the materials have been delivered by the Employer/ Owner, it shall be the responsibility of the Contractor to keep them in good condition and if the materials are damaged or lost, at any time, they shall be repaired and/ or replaced by him at his own cost according to the instructions of the Engineer-in-Charge/Project Manager.
- vi) The Employer/ Owner shall not be liable for delay in supply or non-supply of any materials which the Employer/ Owner has undertaken to supply where such failure or delay is due to natural

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

calamities, act of enemies, transport and procurement difficulties and any circumstances beyond the control of the Employer/ Owner. In no case, the Contractor shall be entitled to claim any compensation or loss suffered by him on this account.

vii) It shall be responsibility of the Contractor to arrange in time all materials required for the Work other than those to be supplied by the Employer/ Owner. If, however, in the opinion of the Engineer-in-Charge/Project Manager the execution of the Work is likely to be delayed due to the Contractor's inability to make arrangements for supply of materials which normally he has to arrange for, the Engineer-in-Charge/Project Manager shall have the right at his own discretion to issue such materials, if available with the Employer/ Owner or procure the materials from the market or as elsewhere and the Contractor will be bound to take such materials at the rates decided by the Engineer-in-Charge/Project Manager. This, however, does not in any way absolve the Contractor from responsibility of making arrangements for the supply of such materials in part or in full, should such a situation occur nor shall this constitute a reason for the delay in the execution of the Work.

viii) None of the materials supplied to the Contractor will be utilized by the Contractor for manufacturing item which can be obtained as supplied from standard manufacturer in finished form.

ix) The Contractor shall, if desired by the Engineer-in-Charge/Project Manager, be required to execute an Indemnity Bond in the prescribed form for safe custody and accounting of all materials issued by the Employer/ Owner.

x) The Contractor shall furnish to the Engineer-in-Charge/Project Manager sufficiently in advance a statement showing his requirement of the quantities of the materials to be supplied by the Employer/ Owner and the time when the same will be required by him for the works, so as to enable the Engineer-in-Charge/Project Manager to make necessary arrangements for procurement and supply of the material.

xi) Account of the materials issued by the Employer/ Owner shall be maintained by Contractor indicating the daily receipt, consumption and balance in hand. This account shall be maintained in a manner prescribed by the Engineer-in-Charge/Project Manager along with all connected papers viz. requisitions, issues, etc., and shall be always available for inspection in the Contractor's office at Site.

xii) The Contractor should see that only the required quantities of materials are got issued. The Contractor shall not be entitled to cartage and incidental charges for returning the surplus materials, if any, to the stores wherefrom they were issued or to the place as directed by the Engineer-in-Charge/Project Manager.

xiii) Materials/ Equipment(s) supplied by Employer/ Owner shall not be utilized for any purpose(s) than issued for.

61. Material Procured with Assistance of Employer/ Return of Surplus

61.1 Notwithstanding anything contained to the contrary in any or all the clauses of this Contract where any materials for the execution of the Contract are procured with the assistance of the Employer/ Owner either by issue from Employer's/ Owner's stock or purchases made under order or permits or licenses issued by Government, the Contractor shall hold the said materials as trustee for the Employer/ Owner and use such materials economically and solely for the purpose of the Contract and not dispose them off without the permission of the Employer/ Owner and return, if required by the Engineer-in-Charge/Project Manager, shall determine having due regard to the condition of the materials.

62. Materials obtained from Dismantling

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 47 of 77</u>	<u>Signature of Bidder</u>

62.1 If the Contractor in the course of execution of the Work is called upon to dismantle any part for reasons other than those stipulated in Clauses 67 and 70 hereunder, the materials obtained in the Work of dismantling etc., will be considered as the Employer's/ Owner's property and will be disposed off to the best advantage of the Employer/ Owner.

63. Articles of Value Found

63.1 All gold, silver and other minerals of any description and all precious stones, coins, treasure relics, antiquities and other similar things which shall be found in, under or upon the Site, shall be the property of the Employer/ Owner and the Contractor shall duly preserve the same to the satisfaction of the Engineer-in-Charge/Project Manager and shall from time to time deliver the same to such person or persons indicated by the Employer/ Owner.

64. Discrepancies between Instructions

64.1 Should any discrepancy occur between the various instructions furnished to the Contractor, his agent or staff or any doubt arises as to the meaning of any such instructions or should there be any misunderstanding between the Contractor's staff and the Engineer-in-Charge/Project Manager's staff, the Contractor shall refer the matter immediately in writing to the Engineer-in-Charge/Project Manager whose decision thereon shall be final and conclusive and no claim for losses alleged to have been caused by such discrepancies between instructions, doubts, or misunderstanding shall in any event be admissible.

65. Action where no Specification is Issued

65.1 In case of any class of Work for which there is no Specification supplied by the Employer/ Owner as mentioned in the Tender Documents such Work shall be carried out in accordance with Indian Standard Specifications and if the Indian Standard Specifications do not cover the same, the Work should be carried out as per standard Engineering Practice subject to the approval of the Engineer-in-Charge/Project Manager.

66. Inspection of Works

66.1 The Engineer-in-Charge/Project Manager will have full power and authority to inspect the Work at any time wherever in progress either on the Site or at the Contractor's premises/ workshops wherever situated, premises/ workshops of any person, firm or corporation where Work in connection with the Contract may be in hand or where materials are being or are to be supplied, and the Contractor shall afford or procure for the Engineer-in-Charge/Project Manager every facility and assistance to carry out such inspection. The Contractor shall, at all time during the usual working hours and at all other time at which reasonable notice of the intention of the Engineer-in-Charge/Project Manager or his representative to visit the Work shall have been given to the Contractor, either himself be present or receive orders and instructions, or have a responsible agent duly accredited in writing, present for the purpose. Orders given to the Contractor's agent shall be considered to have the same force as if they had been given to the Contractor himself. The Contractor shall give not less than 07 (Seven) day notice in writing to the Engineer-in-Charge/Project Manager before covering up or otherwise placing beyond reach of inspection and measurement of any work in order that the same may be inspected and measured. In the event of breach of above the same shall be uncovered at Contractor's expense for carrying out such measurement or inspection.

66.2 The Contractor is to provide at all time during the progress of the Work and the maintenance period, proper means of access with ladders, gangways etc. and the necessary attendance to move and

adopt as directed for inspection or measurements of the Work by the Engineer-in-Charge/Project Manager.

- 66.3 The Contractor shall make available to the Engineer-in-Charge/Project Manager free of cost all necessary instruments and assistance in checking or setting out of Work and in the checking of any Work made by the Contractor for the purpose of setting out and taking measurements of Work.

67. Tests for Quality of Work

- 67.1 All workmanship shall be of the respective kinds described in the Contract Documents and in accordance with the instructions of the Engineer-in-Charge/Project Manager and shall be subjected from time to time to such test as the Engineer-in-Charge/Project Manager may direct at the place of manufacture or fabrication or on the site or at all or any such places. **The cost of inspection/ pre-dispatch inspection/ in-stage inspection shall be borne by Contractor. Such pre-dispatch inspection(s) at the manufacturer's facility shall be carried out in the presence of the Employer/Owner or their authorized representatives, for such items as is specified by the Engineer-in-Charge/Project Manager. Travel expenses for such inspections shall be borne by the Employer/Owner. However, in case re-inspection is necessitated on account of non-acceptance of item(s) due to failure on Factory Acceptance Test(s), the cost of associated travel and accommodation borne by the Employer/Owner shall be on account of the Contractor.** The Contractor shall provide assistance, instruments, labour and materials as are normally required for examining, measuring and testing any workmanship as may be selected and required by the Engineer-in-Charge/Project Manager
- 67.2 All the tests that will be necessary in connection with the execution of the Work as decided by the Engineer-in-Charge/Project Manager shall be carried out at the field testing laboratory of the Employer/ Owner by paying the charges as decided by the Employer/ Owner from time to time. In case of non-availability of testing facility with the Employer/ Owner, the required test shall be carried out at the cost of Contractor at Government or any other testing laboratory as directed by Engineer-in-Charge/Project Manager.
- 67.3 If any tests are required to be carried out in conjunction with the Work or materials or workmanship not supplied by the Contractor, such tests shall be carried out by the Contractor as per instructions of Engineer-in-Charge/Project Manager and cost of such tests shall be reimbursed by the Employer/ Owner.
- 67.4 The PV modules/ inverters/ cables and other Balance of system equipment deployed in the solar PV power Plant shall have valid test certificates for their qualification as per above specified IEC/ IS Standards by one of the NABL Accredited Test Centers in India. In case of module types/ equipment for which such Test facilities may not exist in India, test certificates from reputed ILAC Member body accredited Labs abroad (with proof of accreditation) will be acceptable

68. Samples for Approval

- 68.1 The Contractor shall furnish to the Engineer-in-Charge/Project Manager for approval, when requested or if required by the specifications, adequate samples of all materials and finished to be used in the Work. Such samples shall be submitted before the Work is commenced and in ample time to permit tests and examinations thereof. All materials furnished and finishes applied in actual Work shall be fully equal to the approved samples.

69. Action and Compensation in case of Bad Work

- 69.1 If it shall appear to the Engineer-in-Charge/Project Manager that any work has been executed with unsound, imperfect or unskilled workmanship, or with materials of any inferior description, or that any materials or articles provided by the Contractor for the execution of the Work are unsound, or

of a quality inferior to that contracted for, or otherwise not in accordance with the Contract, the Contractor shall on demand in writing from the Engineer-in-Charge/Project Manager or his authorized representative specifying the Work, materials or articles complained of notwithstanding that the same may have been inadvertently passed, certified and paid for, forthwith rectify or remove and reconstruct the Work so specified and provide other proper and suitable materials or articles at his own cost and in the event of failure to do so within the period specified by the Engineer-in-Charge/Project Manager in his demand aforesaid, the Contractor shall be liable to pay compensation at the rate of 1% (One Percent) of the estimated cost of the whole Work, for every week limited to a maximum of 10% (Ten Percent) of the value of the whole Work, while his failure to do so shall continue and in the case of any such failure the Engineer-in-Charge/Project Manager may on expiry of notice period rectify or remove and re-execute the Work or remove and replaced with others, the materials or articles complained of to as the case may be at the risk and expense in all respects of the Contractor. The decision of the Engineer-in-Charge/Project Manager as to any question arising under this clause shall be final and conclusive.

70. Suspension of Works

70.1 i) Subject to the provisions of sub-para (ii) of this clause, the Contractor shall, if ordered in writing by the Engineer-in-Charge/Project Manager, or his representative, temporarily suspend the Works or any part thereof for such written order, proceed with the Work therein ordered to be suspended until, he shall have received a written order to proceed therewith. The Contractor shall not be entitled to claim compensation for any loss or damage sustained by him by reason of temporary suspension of the Works aforesaid. An extension of time for completion, corresponding with the delay caused by any such suspension of the Works as aforesaid will be granted to the Contractor should he apply for the same provided that the suspension was not consequent to any default or failure on the part of the Contractor.

ii) In case of suspensions of entire Work, ordered in writing by Engineer-in-Charge/Project Manager, for a period of more than 03 (Three) months, the Contractor shall have the option to terminate the Contract.

71. Employer/ Owner may do Part of Work

71.1 Upon failure of the Contractor to comply with any instructions given in accordance with the provisions of this Contract the Employer/ Owner has the alternative right, instead of assuming charge of entire Work, to place additional labour force, tools, equipment and materials on such parts of the Work, as the Employer/ Owner may designate or also engage another Contractor to carry out the Work. In such cases, the Employer/ Owner shall deduct from the amount which otherwise might become due to the Contractor, the cost of such work and material with 10% (Ten Percent) added to cover all departmental charges and should the total amount thereof exceed the amount due to the Contractor, the Contractor shall pay the difference to the Employer/ Owner.

72. Possession prior to Completion

72.1 The Engineer-in-Charge/Project Manager shall have the right to take possession of or use any completed or partially completed Work or part of the Work. Such possession or use shall not be deemed to be an acceptance of any work completed in accordance with the Contract Agreement. If such prior possession or use by the Engineer-in-Charge/Project Manager delays the progress of Work, equitable adjustment in the time of completion will be made and the Contract Agreement shall be deemed to be modified accordingly.

73. Defects Liability Period [12 (Twelve) Months Period of Liability from the date of Operational Acceptance]

- 73.1 The Contractor must warrant that the Facilities shall be free from defects in the design, engineering, materials and workmanship of the Plant and Equipment supplied and of the work executed.
- 73.2 If it shall appear to the Project Manager that any supplies have been executed with unsound, imperfect or unskilled workmanship, or with materials of any inferior description, or that any materials or articles provided by the Contractor for the execution of Contractor are unsound or otherwise not in accordance with the Contract, the Contractor shall on demand in writing inform the Project Manager or its authorized representative specifying the item, materials or articles complained of, notwithstanding that the same may have been inadvertently passed, certified and paid for. The Contractor shall forthwith rectify or remove and replace that item so specified and provide other proper and suitable materials or articles at its own charge and cost, and in the event of failure to do so within a period to be specified by the Project Manager in its demand aforesaid, the Project Manager may on expiry of notice period rectify or remove and re-execute the time or remove and replace with others, the materials or articles complained of as the case may be at the risk and expense in all respects of the Contractor. The decisions of the Project Manager in this regard shall be final and binding.
- 73.3 The Contractor shall also be undertaking the operation and maintenance of the Facility and consequently shall be required to rectify any defects that emerge during the operation of the Facilities for the entire term of this Contract.
- 73.4 The Defect Liability Period shall be of twelve (12) months from the date of completion of the Facilities, during which the Contractor must repair any defect identified by the Project Manager / EIC after commissioning of the Plant. All the expenses to repair the defects shall be borne by the contractor and no additional cost charged to the Employer/Owner ("Defects Liability Period").
- 73.5 If during the Defect Liability Period any defect should be found in the design, engineering, materials and workmanship of the Plant and Equipment supplied or of the work executed by the Contractor, the Contractor shall promptly, in consultation and agreement with the Owner/ Employer regarding appropriate remedying of the defects, and at its cost, repair, replace or otherwise make good (as the Contractor shall, at its discretion, determine) such defect as well as any damage to the Facilities caused by such defect.
- 73.6 Furthermore, without prejudice to the generality of the foregoing, it is clarified that the Contractor shall also be responsible for the repair, replacement or making good of any defect, or of any damage to the Facilities arising out of or resulting from any of the following causes:
- Improper operation or maintenance of the Facilities by the Contractor during operation and maintenance of the Facility; and
 - Operation of the Facilities outside specifications of the Facilities.
- 73.7 The Owner/ Employer shall give the Contractor a notice stating the nature of any such defect together with all available evidence thereof, promptly following the discovery thereof. The Owner/ Employer shall afford all reasonable opportunity for the Contractor to inspect any such defect.
- 73.8 The Owner/ Employer shall provide the Contractor all necessary access to the Facilities and the Site to enable the Contractor to perform its obligations under this Clause (Defect Liability). The Contractor may, with the consent of the Employer/Owner, remove any Plant and Equipment or any part of the Facilities that are defective from the Site, if the nature of the defect and/or any damage to the Facilities caused by the defect is such that repairs cannot be expeditiously carried out at the Site.

- 73.9 If the repair, replacement or making good is of such a nature that it may affect the efficiency of the Facilities or any part thereof, the Employer/Owner may give to the Contractor a notice requiring that tests of the defective part of the Facilities shall be made by the Contractor immediately upon completion of such remedial work, whereupon the Contractor shall carry out such tests.
- 73.10 If such part fails the tests, the Contractor shall carry out further repair, replacement or making good (as the case may be) until that part of the Facilities passes such tests. The tests, in character, shall in any case be not inferior to what has already been agreed upon by the Employer//Owner and the Contractor for the original equipment/part of the Facilities.
- 73.11 If the Contractor fails to commence the work necessary to remedy such defect or any damage to the Facilities caused by such defect within a reasonable time (which shall in no event be considered to be less than seven (7) days), the Employer/Owner may, following a notice to the Contractor, proceed to do such work, and the costs incurred by the Employer/Owner in connection therewith shall be paid to the Employer/Owner by the Contractor or may be deducted by the Employer/Owner from any monies due to the Contractor or claimed under the Performance Guarantee, without prejudice to other rights, which the Owner/ Employer may have against the Contractor in respect of such defects.
- 73.12 If the Facilities or any part thereof cannot be used by reason of such defect and/or making good of such defect, the Defect Liability Period of the Facilities or such part, as the case may be, shall be extended by a period equal to the period during which the Facilities or such part cannot be used by the Employer/Owner because of any of the aforesaid reasons. Upon correction of the defects in the Facilities or any part thereof by repair/replacement, such repair/replacement shall have the defect liability period of twelve (12) months from such replacement.
- 73.13 In addition, the Contractor shall also provide an extended warranty for any such component of the Facilities and for the period of time. Such obligation shall be in addition to the defect liability specified.
- 73.14 The Bidder's liability under this contract for any reason, what so ever, shall be limited to the total Contract Price (Including T & D)

73.15 Limitation of Liability

Notwithstanding anything contrary contained herein, the aggregate total liability of Contractor under the Agreement or otherwise shall be limited to 100% of Agreement/ Contract Value. However, neither party shall be liable to the other party for any indirect and consequential damages, loss of profits or loss of production.

73.16 Guarantee/ Warranty

As enumerated in Clause no. 73 (Defect Liability Period) of GCC, the overall DLP should stand valid for a period of 12 (Twelve) Months from the date of Operational Acceptance. However, Contractor needs to ensure following Guarantees/ Warranties to the best possible extent for the successful execution of the Contract. Subsequently, necessary Guarantee/ Warranty Certificate shall be produced by the Contractor prior to Operational Acceptance of the Facility. **Guarantee/ Warranty as defined under Section VII, Scope of work and Technical specifications will prevail in this clause**

For the major Material/Products/Spares of the works & Projects including but not limited to PV Modules, Power Conditioning Units (PCU)/ Inverters, Transformers, Batteries (If applicable) etc the Contractor shall invariably engage OEMs/Sub-Contractors who are specialists in the field and OEM's/OPM's/firms of repute and such a OEM/OPM/Sub-

Contractor shall furnish guarantees/warranties for their workmanship to the Employer/ Owner directly in the name of Employer/ Owner only without any deviation . The Contractor shall give the guarantee/warranty to the Employer/ Owner directly For other minor Material/Products/Spares.

73.16.1 PV modules to be used in grid connected Solar Power Plant must be warranted for peak output wattage, which should not be less than 90% at the end of 10 years and 80% at the end of 25 years.

73.16.2 The modules shall be warranted for at least 10 years for failures due to material defects and workmanship.

73.16.3 The mechanical structures, electrical works and overall workmanship of the grid connected Solar Power Plant must be warranted for a minimum of 10 years.

73.16.4 The Contractor must ensure that the goods supplied under the Contract are new, unused and of most recent or current models and incorporate all recent improvements in design and materials unless provided otherwise in the Contract.

73.17 The warranty / guarantee period shall be as follows:

73.17.1 Solar PV Modules: Modules shall be warranted for a minimum period of 25 years in the Bidder's detailed Warranty / Guarantee certificate.

73.5.2 Power Conditioning Units (PCU)/ Inverters: PCUs shall be warranted for the minimum period of 5 years or guarantee period provided by the OEM, whichever is higher.

73.5.3 Transformers, associated switch gear and others: Bidder must furnish in detail its warranties / guarantees for these items.

73.18 During the period of Warranty / Guarantee the Contractor shall remain liable to replace any defective parts, that becomes defective in the Plant, of its own manufacture or that of its sub-Contractors, under the conditions provided for by the Contract under and arising solely from faulty design, materials, workmanship or any reason attributable to works carried out by the contractor, provided such defective parts are not repairable at Site. After replacement, the defective parts shall be returned to the Contractors works at the expense of the Contractor unless otherwise arranged.

73.19 At the end of guarantee period, the Contractor's liability shall cease. In respect of goods not covered by the GCC Sub Clause, the Employer/Owner shall be entitled to the benefit of such guarantee given to the Contractor by the original Contractor or manufacturer of such goods.

73.20 During the Operation & Maintenance and guarantee period, the Contractor shall be responsible for any defects in the work due to faulty workmanship or due to use of sub-standard materials in the work. Any defects in the work during the guarantee period shall therefore, be rectified by the Contractor without any extra cost to the Owner/ Employer within a reasonable time as may be considered from the date of receipt of such intimation from the Employer/Owner failing which the Employer/Owner reserves the right to take up rectification work at the risk and cost of the Contractor.

74. Care of Works

74.0 From the commencement to completion of the Work, the Contractor shall take full responsibility for the care for all works including all temporary works and in case any damages, loss or injury shall happen to the Work or to any part thereof or to any temporary works from any cause whatsoever, shall at his own cost repair and make good the same so that at completion the Work shall be in good order and in conformity in every respects with the requirement of the Contract and the Engineer-in-Charge's instructions.

74.1 Defects Prior to Taking Over

If at any time, before the Work is taken over, the Engineer-in-Charge/Project Manager shall:

a) Decide that any works done or materials used by the Contractor or by any Sub-Contractor is defective or not in accordance with the Contract, or that the works or any portion thereof are defective, or do not fulfill the requirements of Contract (all such matters being hereinafter, called 'Defects' in this clause), and

b) As soon as reasonably practicable, gives to the Contractor notice in writing of the said decision, specifying particulars of the defects alleged to exist or to have occurred, then the Contractor shall at his own expenses and with all speed make good the defects so specified. In case, Contractor shall fail to do so, the Employer/ Owner may take, at the cost of the Contractor, such steps as may take in all circumstances, be reasonable to make good such defects. The expenditure so incurred by the Employer/ Owner will be recovered from the amount due to the Contractor. The decision of the Engineer-in-Charge/Project Manager with regard to the amount to be recovered from the Contractor will be final and binding on the Contractor. As soon as the Work has been completed in accordance with the Contract (except in minor respects that do not affect their use for the purpose for which they are intended and except for maintenance there provided in clause 73.1 of General Conditions of Contract) and have passed the tests on completion, the Engineer-in-Charge/Project Manager shall issue a Certificate (hereinafter called Completion Certificate) in which he shall certify the date on which the Work have been so completed and have passed the said tests and the Employer/ Owner shall be deemed to have taken over the Work on the date so certified. If the Work has been divided into various groups in the Contract, the Employer/ Owner shall be entitled to take over any group or groups before the other or others and there upon the Engineer-in-Charge/Project Manager shall issue a Completion Certificate which will, however, be for such group or groups so taken over only. In such an event if the group/ section/ part so taken over is related, to the integrated system of the work, notwithstanding date of grant of Completion Certificate for group/ section/ part. The period of liability in respect of such group/ section/ part shall extend 12 (Twelve) months from the date of completion of Work.

74.2 Defects after Taking Over

In order that the Contractor could obtain a Completion Certificate he shall make good, with all possible speed, any defect arising from the defective materials supplied by the Contractor or workmanship or any act or omission of the Contract or that may have been noticed or developed, after the works or groups of the works has been taken over, the period allowed for carrying out such Work will be normally 01 (One) Month. If any defect be not remedied within a reasonable time, the Employer/ Owner may proceed to do the Work at Contractor's risk and expense and deduct from the final bill such amount as may be decided by the Employer/ Owner. If by reason of any default on the part of the Contractor a Completion Certificate has not been issued in respect of any portion of the Work within 01 (One) Month after the date fixed by the Contract for the completion of the Work, the Employer/ Owner shall be at liberty to use the Work or any portion thereof in respect of which a completion certificate has not been issued, provided that the Work or the portion thereof so used as aforesaid shall be afforded reasonable opportunity for completing these works for the issue of Completion Certificate.

75. Guarantee/ Transfer of Guarantee

75.1 For the major Material/Products/Spares of the works & Projects including but not limited to PV Modules, Power Conditioning Units (PCU)/ Inverters, Transformers, Batteries (If applicable) etc the Contractor shall invariably engage OEMs/Sub-Contractors who are specialists in the field and OEM's/OPM's/firms of repute and such a OEM/OPM/Sub-Contractor shall furnish guarantees/warranties for their workmanship to the Employer/ Owner directly in the name of Employer/ Owner only without any deviation . The Contractor shall give the guarantee/warranty to the Employer/ Owner directly For other minor Material/Products/Spares.

In case of the contract termination/cancellation and wherein the title of Guarantee/Warranty for the major Material/Products/Spares of the works & Projects including but not limited to PV Modules, Power Conditioning Units (PCU)/ Inverters, Transformers, Batteries (If applicable) is in the name of the contractor, then all such Guarantee/Warranties for all such major products/material/spares will have to be mandatorily transferred in the name of Owner as soon as the contract is terminated/cancelled & no plea/deviation from the contractor side will be entertained in this regard.

For works like water-proofing, acid and alkali resisting materials, pre-construction soil treatment against termite or any other specialized works etc. the Contractor shall invariably engage Sub-Contractors who are specialists in the field and firms of repute and such a Sub-Contractor shall furnish guarantees for their workmanship to the Employer/ Owner, through the Contractor. In case such a Sub-Contractor is not prepared to furnish a guarantee to the Employer/ Owner, the Contractor shall give that guarantee to the Employer/ Owner directly.

76. Installation and Training of Employer's/ Owner's Personnel

76.1 Tools & Tackles

The Contractor shall provide technically suitable tools and tackles for installation & erection of Plant & Machineries conforming to relevant BIS safety and technical standards for proper execution of work. The Owner/ Employer, in no way, shall be responsible for supply of any tools and tackles for implementation of the work and also to carry out operation & maintenance activities.

76.2 Setting up/Supervision/Labor

76.2.1 Bench Mark:

The Contractor shall be responsible for the true and proper setting-up of the Facilities in relation to bench marks, reference marks which are mutually agreed upon by the contractor and Owner/ Employer.

If, at any time during the progress of installation of the Facilities, any error shall appear in the position, level or alignment of the Facilities, the Contractor shall forthwith notify the Project Manager of such error and, at its own expense, immediately rectify such error to the satisfaction of the Project Manager.

76.2.2 Contractor's Supervision:

The Contractor shall give or provide all necessary superintendence during the installation of the Facilities, and the Construction Manager or its deputy shall be constantly on the Site to provide full-time superintendence of the installation. The Contractor shall provide and employ only technical personnel who are skilled and experienced in their respective callings and supervisory staff who are competent to adequately supervise the work at hand.

76.2.3 Labuor:

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 55 of 77</u>	Signature of Bidder

The Contractor shall provide and employ on Site in the installation of the Facilities such skilled, semi-skilled and unskilled labor as is necessary for proper and timely execution of the Contract. The Contractor is encouraged to use local labor that has the necessary skills.

Unless otherwise provided in the Contract, the Contractor shall be responsible for the recruitment, transportation, accommodation, first aid facility and catering of all labor, local or expatriate, required for the execution of the Contract and for all payments in connection therewith.

The Contractor shall be responsible for obtaining all necessary permit(s) and/or visa(s) from the appropriate authorities for the entry of all labour and personnel to be employed by contractor on the Site.

The Contractor shall at all times during the progress of the Contract use its best endeavors to prevent any unlawful, riotous or disorderly conduct or behavior by or amongst its employees and the labour of its Subcontractors.

The Contractor shall, in all dealings with its labour and the labour of its Subcontractors currently employed on or connected with the Contract, pay due regard to all recognized festivals, official holidays, religious or other customs and all local laws and regulations pertaining to the employment of labor.

76.3 Contractor's Equipment

76.3.1 All equipment brought by the Contractor onto the Site shall be deemed to be intended to be used exclusively for the execution of the Contract. The Contractor shall not remove the same from the Site without the Project Manager's consent that such Contractor's Equipment is no longer required for the execution of the Contract.

76.3.2 Unless otherwise specified in the Contract, upon completion of the Facilities, the Contractor shall remove from the Site all Equipment brought by the Contractor onto the Site.

76.4 Site Regulations and Safety

The Contractor shall have to provide necessary and adequate safety measures including personal protective equipment and precautions to avoid any accident, which may cause damage to any equipment / material or injury to workmen. The contractor, if required, will provide necessary safety training to workmen. The Owner/ Employer shall not be responsible for any such accidents. Also, contractor shall engage sufficient security guards to protect Facility from any theft and unauthorized access to Site.

76.5 Site Clearance

76.5.1 Site Clearance in Course of Performance

In the course of carrying out the Contract, the Contractor shall keep the Site reasonably free from all unnecessary obstruction, store or remove any surplus materials, clear away any wreckage, packaging material, rubbish & debris and temporary installations from the Site, and remove any Contractor's Equipment no longer required for execution of the Contract.

76.5.2 Site Clearance after Completion

After Completion of all parts of the Facilities, the Contractor shall clear away and remove all wreckage, packaging material, rubbish & debris and temporary works & installations of any kind from the Site, and shall leave the Site and Facilities clean and safe.

76.5.3 Disposal of Scrap

The Contractor shall with the agreement of the Owner/ Employer promptly remove from the site any 'Scrap' generated during Performance of any activities at site in pursuance of the Contract. The term 'Scrap' shall refer to scrap/ waste/ remnants arising out of the unpacking of equipment, construction debris, breakage of modules, fabrication of structural steel work and piping work at the project site in the course of execution of the contract and shall also include any wastage of cables during the termination process while installing the cables.

The disposal of such Scrap shall vest with the Contractor for the items supplied by the Contractor and issued by Owner/ Employer under this contract for installation and construction without any additional cost to the Employer. The removal of scrap shall be subject to the Contractor producing the necessary clearance from the relevant authorities (Custom, Excise etc.), if required by the law, in respect of disposal of the scrap. The liability for the payment of the applicable GST shall be that of the Contractor.

The Contractor shall also indemnify to keep the Owner/ Employer harmless from any act of omission or negligence on the part of the Contractor in following the statutory requirements with regard to removal/disposal of scrap. The Indemnity Bond shall be furnished by contractor as per Format enclosed. Further, in case the laws require the Employer to take prior permission of the relevant Authorities before handing over the scrap to the Contractor, the same shall be obtained by the Contractor on behalf of the Employer.

76.5.4 Watch & Ward and Lighting

The Contractor shall provide and maintain at its own expense all lighting, fencing, watch and ward wherever necessary for the proper execution and the protection of the Facilities, or for the safety of the owners and occupiers of adjacent property and for the safety of the public.

The Contractor undertakes to provide training to Personnel selected and sent by the Employer/ Owner at the works of the Contractor without any cost to the Employer/ Owner. The period and the nature of training for the individual personnel shall be agreed upon mutually between the Contractor and the Employer/ Owner. These personnel shall be given special training at the shops, where the equipment will be manufactured and/ or in their collaborator's works and where possible, in any other plant where equipment manufactured by the Contractor or his collaborators is under installation or test to enable those personnel to become familiar with the equipment being furnished by the Contractor. Employer/ Owner shall bear only the to and fro fare of the said personnel.

77. Replacement of Defective Parts and Materials

- 77.1 If during the progress of the Work, Employer/ Owner shall decide and inform in writing to the Contractor, that the Contractor has manufactured any plant or part of the plant unsound or imperfect or has furnished plant inferior to the quality specified, the Contractor on receiving details of such defects or deficiencies shall at his own expenses within 07 (Seven) days of his receiving the notice, or otherwise within such time as may be reasonably necessary for making it good, proceed to alter, re-construct or remove such work and furnish fresh equipment's up to the standards of the specifications. In case the Contractor fails to do so, Employer/ Owner may on giving the Contractor 07 (Seven) day notice in writing of his intentions to do so, proceed to remove the portion of the Work so complained of and at the cost of Contractor's, perform all such works or furnish all such equipment's provided that nothing in the clause shall be deemed to deprive the Employer/ Owner of or affect any rights under the Contract, the Employer/ Owner may otherwise have in respect of such defects and deficiencies.

78. Indemnity

- 78.1 If any action is brought before a Court, Tribunal or any other Authority against the Employer/ Owner or an officer or agent of the Employer/ Owner, for the failure, omission or neglect on the part of the Contractor to perform any acts, matters, covenants or things under the Contract, or damage or injury or death caused by the alleged omission or negligence on the part of the Contractor, his agents, representatives or his Sub-Contractor's, or in connection with any claim based on lawful demands of Sub-Contractor's workmen suppliers or employees, the Contractor, shall in such cases indemnify and keep the Employer/ Owner and/ or their representatives harmless from all losses, damages, expenses or decrees arising out of such action.

79. Construction Aids, Equipment, Tools & Tackles

- 79.1 Contractor shall be solely responsible for making available for executing the Work, all requisite Construction Equipments, Special Aids, Barges, Cranes and the like, all Tools, Tackles and Testing Equipment and Appliances, including imports of such equipment etc. as required. In case of import of the same the rates applicable for levying of Custom Duty on such Equipment, Tools & Tackles and the duty drawback applicable thereon shall be ascertained by the Contractor from the concerned authorities of Government of India. It shall be clearly understood that Employer/ Owner shall not in any way be responsible for arranging to obtain Custom Clearance and/ or payment of any duties and/ or duty draw backs etc. for such equipment's so imported by the Contractor and the Contractor shall be fully responsible for Goods and Service Tax (GST) and documentation with regard to the same. Tenderer in his own interest may contact, for any clarifications in the matter, concerned agencies/ Dept./ Ministries of Govt. of India. All clarifications so obtained and interpretations thereof shall be solely the responsibility of the Contractor.

[F] CERTIFICATES AND PAYMENTS

80. Schedule of Rates and Payments

80.1 Contractor's Remuneration

The price to be paid by the Employer/ Owner to Contractor for the whole of the Work to be done and for the performance of all the obligations undertaken by the Contractor under the Contract Documents shall be ascertained by the application of the respective Schedule of Rates (the inclusive nature of which is more particularly defined by way of application but not of limitation, with the succeeding Clause of this clause) and payment to be made accordingly for the Work actually executed and approved by the Engineer-in-Charge/Project Manager. The sum so ascertained shall (excepting only as and to the extent expressly provided herein) constitute the sole and inclusive remuneration of the Contractor under the Contract and no further or other payment whatsoever shall be or become due or payable to the Contractor under the Contract.

80.2 Schedule of Rates to be Inclusive

The prices/ rates quoted by the Contractor shall remain firm till the issuance of Final Certificate and shall not be subject to escalation. Schedule of Rates shall be deemed to include and cover all costs, expenses and liabilities of every description and all risks of every kind to be taken in executing, completing and handing over the Work to the Employer/ Owner by the Contractor. The Contractor shall be deemed to have known the nature, scope, magnitude and the extent of the Work and materials required though the Contract Document may not fully and precisely furnish them. Tenderers shall make such provision in the Schedule of Rates as he may consider necessary to cover the cost of such items of Work and materials as may be reasonable and necessary to complete the Work. The opinion of the Engineer-in-Charge/Project Manager as to the items of Work which are necessary and reasonable for Completion of Work shall be final and binding on the Contractor,

although the same may not be shown on or described specifically in Contract Documents. Generality of this present provision shall not be deemed to cut down or limit in any way because in certain cases it may and in other cases it may not be expressly stated that the Contractor shall do or perform a work or supply articles or perform services at his own cost or without addition of payment or without extra charge or words to the same effect or that it may be stated or not stated that the same are included in and covered by the Schedule of Rates.

80.3 Schedule of Rates to Cover Construction Equipments, Materials, Labour etc.

Without in any way limiting the provisions of the preceding Clause the Schedule of Rates shall be deemed to include and cover the cost of all construction equipment, temporary Work (except as provided for herein), pumps, materials, labour, insurance, fuel, consumables, stores and appliances to be supplied by the Contractor and all other matters in connection with each item in the Schedule of Rates and the execution of the Work or any portion thereof finished, complete in every respect and maintained as shown or described in the Contract Documents or as may be ordered in writing during the continuance of the Contract.

80.4 Schedule of Rates to Cover Royalties, Rents and Claims

The Schedule of Rates (i.e., Value of Contract) shall be deemed to include and cover the cost of all Royalties and Fees for the articles and processes, protected by letters, patent or otherwise incorporated in or used in connection with the Work, also all Royalties, Rents and other payments in connection with obtaining materials of whatsoever kind for the Work and shall include an Indemnity to the Employer/ Owner which the Contractor hereby gives against all actions, proceedings, claims, damages, costs and expenses arising from the incorporation in or use on the Work of any such articles, processes or materials, octroi or other municipal or local Board Charges, if levied on materials, equipment or machineries to be brought to site for use on Work shall be borne by the Contractor.

80.5 Schedule of Rates to Cover Taxes and Duties

No exemption or reduction of Customs Duties, Goods & Service Tax (GST) on Works Contract quay or any port dues, transport charges, stamp duties or Central or State Government or Local Body or Municipal Taxes or from or of any other body, whatsoever, will be granted or obtained, all of which expenses shall be deemed to be included in and covered by the Schedule of Rates. The Contractor shall also obtain and pay for all permits or other privileges necessary to complete the Work.

80.6 Schedule of Rates to Cover Risks of Delay

The Schedule of Rates shall be deemed to include and cover the risk of all possibilities of delay and interference with the Contractor's conduct of Work which occur from any causes including orders of the Employer/ Owner in the exercise of his power and on account of extension of time granted due to various reasons and for all other possible or probable causes of delay.

80.7 Schedule of Rates Cannot be Altered

(a) For Engineering, Procurement and Commissioning (EPC) Contracts or Lumpsum Turnkey (LSTK) Contracts, the total Project/ Contract Value stands to be fixed inclusive of entire items, Materials, Spares, Consumables, Services, Erection and all quoted and unquoted items/ Services in the Bill of Quantity (BOQ) of the Tender/ Contract. Contract Value of such EPC Contracts comprises of all the related costs required for successful execution of the work. The final payment outlay or total cost of the project will be limited to the total value of the EPC Contract and O & M Contract. Any kind of variations related to Total Contract Value shall be to

Contractor's account. The payment will be made according to the Work actually carried out, for which purpose an item wise, or work wise Schedule of Rates shall be furnished, suitable for evaluating the value of Work done and preparing running account bill.

- (b) For Item Rate Contracts, no alteration will be allowed in the Schedule of Rates by reason of works or any part of them being modified, altered, extended, diminished or committed. The Schedule of Rates are fully inclusive of rates which have been fixed by the Contractor and agreed to by the Employer/ Owner and cannot be altered.

Based on the mechanism of Tender as described in the Special Conditions of Contract (SCC), the methodologies described above shall prevail. However, payment for any additional work which is not covered in the Schedule of Rates, shall only be released on issuance of change order.

81. Procedure for Measurement and Billing

81.1 Billing Procedure

Following procedures shall be adopted for billing of works executed by the Contractor.

- 81.1.1 For EPC/ Lumpsum Turnkey Contracts, the billing procedure will follow as per the prescribed payment terms as defined in Special Conditions of Contract (SCC).
- 81.1.2 For Item Rate Contracts, all measurements shall be recorded in sextuplicate on standard measurement sheets in duly approved formats for scrutiny and passing by Employer/ Owner. Employer/ Owner shall scrutinize and check the measurements recorded on the sheets and shall certify correctness of the same on the measurement sheets.
- 81.1.3 Engineer-in-Charge/Project Manager shall pass the bills after carrying out the comprehensive checks in accordance with the terms and conditions of the Contracts, within 10 (Ten) days of submission of the bills, complete in all respects and send the same to the Employer/ Owner to effect payment to the Contractor as per the defined payment terms.
- 81.1.4 Employer/ Owner shall make all endeavor to make payments of undisputed amount of the bills submitted based on the joint measurements within 30 (Thirty) days from the date of certification by the Engineer-in-Charge/Project Manager.
- 81.1.5 Measurements shall be recorded as per the methods of measurement spelt out in Employer/ Consultant Specifications/ Contract Document. Employer/ Owner shall be fully responsible for checking the measurements quantitatively and qualitatively as recorded in the Measurement Books/ Bills.
- 81.1.6 While preparing the final bills overall measurements will not be taken again. Only volume of work executed since the last measured bill along with summary of final measurements will be considered for the final bill. However, a detailed check shall be made as to missing measurements and in case there are any missing items or measurements the same shall be recorded.

81.2 Secured Advance on Material

Unless otherwise provided elsewhere in the tender, no 'Secured Advance' on security of materials brought to site for execution of contracted items(s) shall be paid to the Contractor whatsoever.

81.3 Dispute in Mode of Measurement

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 60 of 77</u>	<u>Signature of Bidder</u>

In case of any dispute as to the mode of measurement not covered by the Contract to be adopted for any item of Work, mode of measurement as per latest Indian Standard Specifications shall be followed.

81.4 Rounding-Off of Amounts

In calculating the amount of each item due to the Contractor in every certificate prepared for payment, sum of less than 50 paise shall be omitted and the total amount on each certificate shall be rounded off to the nearest rupees, i.e., sum of less than 50 paise shall be omitted and sums of 50 paise and more up to one rupee shall be reckoned as one rupee.

82. Lumpsum in Tender

82.1 The payment against any Lumpsum item shall be made only on completion of that item as per the provision of the Contract after certification by Engineer-in-Charge/Project Manager.

83. Running Account Payments to be regarded as Advance

83.1 All running account payments shall be regarded as payment by way of advance against the final payment only and not as payments for Work actually done and completed and shall not preclude the requiring of bad, unsound and imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the Contract, or any part thereof, in this respect, or of the occurring of any claim by the Contractor, nor shall it conclude, determine or affect in any way the powers of the Employer/ Owner under these conditions or any of them as to the final settlement and adjustment of the accounts or otherwise, or in any other way vary or affect the Contract. The final bill shall be submitted by the Contractor within 01 (One) Month of the date of physical completion of the Work; otherwise, the Engineer-in-Charge/Project Manager's certificate of the measurement and of total amount payable for the Work accordingly shall be final and binding on all parties

84. Notice of Claims for Additional Payments

84.1 Should the Contractor consider that he is entitled to any extra payment for any extra/ additional Works or Material change in original Specifications carried out by him in respect of Work he shall forthwith give notice in writing to the Engineer-in-Charge/Project Manager that he claims extra payment. Such notice shall be given to the Engineer-in-Charge/Project Manager upon which Contractor bases such claims and such notice shall contain full particulars of the nature of such claim with full details of amount claimed. Irrespective of any provision in the Contract to the contrary, the Contractor must intimate his intention to lodge claim on the Employer/ Owner within 10 (Ten) days of the commencement of happening of the event and quantify the claim within 30 (Thirty) days, failing which the Contractor will lose his right to claim any compensation /reimbursement/ damages etc. or refer the matter to arbitration. Failure on the part of Contractor to put forward any claim without the necessary particulars as above within the time above specified shall be an absolute waiver thereof. No omission by Employer/ Owner to reject any such claim and no delay in dealing therewith shall be waiver by Employer/ Owner of any of this rights in respect thereof.

84.2 Engineer-in-Charge/Project Manager shall review such claims within a reasonably period of time and cause to discharge these in a manner considered appropriate after due deliberations thereon. However, Contractor shall be obliged to carry on with the Work during the period in which his claims are under consideration by the Employer/ Owner, irrespective of the outcome of such claims, where additional payments for Works considered extra are justifiable in accordance with the Contract provisions, Employer/ Owner shall arrange to release the same in the same manner as for normal Work payments. Such of the extra works so admitted by Employer/ Owner shall be governed by all the terms, conditions, stipulations and specifications as are applicable for the Contract.

85 Payment of Contractor's Bill

- 85.1 Payment due to the Contractor shall be made by the Employer/ Owner either by e-Banking or by Account Payee Cheque forwarding the same to registered office or the notified office of the Contractor. In no case, will Employer/ Owner be responsible if the cheque is mislaid or misappropriated by unauthorized person/ persons. In all cases, the Contractor shall present his bill duly pre-receipted on proper revenue stamp payment shall be made in Indian Currency.
- 85.2 In general payment of final bill shall be made to Contractor within 60 days of the submission of bill on joint measurements, after completion of all the obligations under the Contract.

86 Receipt for Payment

- 86.1 Receipt for payment made on account of work when executed by a company, must be signed by a person holding due power of attorney in this respect on behalf of the Contractor, except when the Contractor's are described in their tender as a limited company in which case the receipts must be signed in the name of the company by one of its principal officers or by some other person having authority to give effectual receipt for the company.

87. Completion Certificate

87.1 Application for Completion Certificate

When the Contractor fulfils his obligation under Clause 74.1 he shall be eligible to apply for Completion Certificate. The Engineer-in-Charge/Project Manager shall normally issue to the Contractor the Completion Certificate within 01 (One) Month after receiving any application therefore from the Contractor after verifying from the completion documents and satisfying himself that the Work has been completed in accordance with and as set out in the construction and erection drawings, and the Contract Documents. The Contractor, after obtaining the Completion Certificate, is eligible to present the final bill for the Work executed by him under the terms of Contract.

87.2 Completion Certificate

Within 01 (One) Month of the completion of the Work in all respects, the Contractor shall be furnished with a certificate by the Engineer-in-Charge/Project Manager of such completion, but no certificate shall be given nor shall the Work be deemed to have been executed until all scaffolding, surplus materials and rubbish is cleared off the Site completely nor until the Work shall have been measured by the Engineer-in-Charge/Project Manager whose measurement shall be binding and conclusive. The Works will not be considered as complete and taken over by the Employer/ Owner, until all the temporary works, labour and staff colonies are cleared to the satisfaction of the Engineer-in-Charge/Project Manager. If the Contractor fails to comply with the requirements of this clause on or before the date fixed for the completion of the Work, the Engineer-in-Charge/Project Manager may at the expense of the Contractor remove such scaffolding, surplus materials and rubbish and dispose off the same as he thinks fit and clean off such dirt as aforesaid, and the Contractor shall forthwith pay the amount of all expenses so incurred and shall have no claim in respect of any such scaffolding or surplus materials as aforesaid except for any sum actually realized by the sale thereof.

87.3 Completion Certificate Documents

For the purpose of Clause 87.0 the following documents will be deemed to form the completion documents:

- i) The technical documents according to which the Work was carried out.
- ii) 06 (Six) sets of construction drawings showing therein the modification and correction made during the course of execution and signed by the Engineer-in-Charge/Project Manager.

- iii) Completion Certificate for 'Embedded' and 'Covered up' work.
- iv) Certificates of final levels as set out for various works.
- v) Certificates of tests performed for various Works.
- vi) Material appropriation, Statement for the materials issued by the Employer/ Owner for the Work and list of surplus materials returned to the Employer's/ Owner's store duly supported by necessary documents.

88. Final Decision and Final Certificate

- 88.1 Upon expiry of the period of liability and subject to the Engineer-in-Charge/Project Manager being satisfied that the Works have been duly maintained by the Contractor during monsoon or such period as hereinbefore provided in Clause 73 & 74 and that the Contractor has in all respect duly made-up any subsidence and performed all his obligations under the Contract, the Engineer-in-Charge/Project Manager shall (without prejudice to the rights of the Employer/ Owner to retain the provisions of relevant Clause hereof) otherwise give a certificate herein referred to as the Final Certificate to that effect and the Contractor shall not be considered to have fulfilled the whole of his obligations under Contract until Final Certificate shall have been given by the Engineer-in-Charge/Project Manager notwithstanding any previous entry upon the Work and taking possession, working or using of the same or any part thereof by the Employer/ Owner.

89. Certificate and Payments on Evidence of Completion

- 89.1 Except the Final Certificate, no other certificates or payments against a certificate or on general account shall be taken to be an admission by the Employer/ Owner of the due performance of the Contract or any part thereof or of occupancy or validity of any claim by the Contractor.

90. Deductions from the Contract Price

- 90.1 All costs, damages or expenses which Employer/ Owner may have paid or incurred, which under the provisions of the Contract, the Contractor is liable/ will be liable, will be claimed by the Employer/ Owner. All such claims shall be billed by the Employer/ Owner to the Contractor regularly as and when they fall due. Such claims shall be paid by the Contractor within 15 (Fifteen) days of the receipt of the corresponding bills and if not paid by the Contractor within the said period, the Employer/ Owner may, then, deduct the amount from any moneys due i.e., Contract Performance Security or becoming due to the Contractor under the Contract or may be recovered by actions of law or otherwise, if the Contractor fails to satisfy the Employer/ Owner of such claims.

[G] TAXES AND INSURANCE

91. Goods & Service Tax (GST)/Taxes

- 91.1 The Contractor agrees to and does hereby accept full and exclusive liability for the payment of any and GST/all Taxes. now in force or hereafter imposed, increased, modified, from time to time in respect of Works and materials and all contributions and taxes for unemployment compensation, insurance and old age pensions or annuities now in force or hereafter imposed by any Central or State Government authorities which are imposed with respect to or covered by the wages, salaries or other compensations paid to the persons employed by the Contractor and the Contractor shall be responsible for the compliance of all Sub-Contractors, with all applicable Central, State, Municipal and local law and regulation and requirement of any Central, State or local Government agency or authority. Contractor further agrees to defend, indemnify and hold Employer/ Owner harmless from any liability or penalty which may be imposed by the Central, State or Local authorities by reason or

any violation by Contractor or Sub-Contractor of such laws, suits or proceedings that may be brought against the Employer/ Owner arising under, growing out of, or by reason of the work provided for by this Contract, by third parties, or by Central or State Government authority or any administrative sub-division thereof. Tax deductions will be made as per the rules and regulations in force in accordance with acts prevailing from time to time.

92. GST

- 92.1 Bidder should quote all-inclusive prices including the liability of GST (in line with the given SOR Format) whether on the works contract as a whole or in respect of bought out components used by the Contractor in execution of the Contract. Employer/ Owner shall not be responsible for any such liability of the Contractor in respect of this Contract.

93. Statutory Variations

- 93.1 Goods & Service Tax (GST) [applicable for both Centre and state] and other levies [if any] payable by the Contractor under the Contract, or for any other cause, shall be included in the rates/ prices and the total bid-price submitted by the Bidder. Applicable rate of taxes shall be indicated in Agreed SOR formats.
- 93.2 In case of any variation (positive/ negative) in existing rates of GST/taxes or a new tax/ duty/ levy is introduced or any existing tax/ duty/ levy is abolished or application of any Tax in the course of the performance of this Contract, which will/ may impact the overall pricing in connection with performance of the Contract, an equitable adjustment of the Contract Price shall be made to factor any such change by addition to the Contract Price or deduction therefrom, as the case may be.

All these adjustments would be carried out by considering the base price of taxes equivalent to the amount mentioned under taxes and duties column of the SOR/ PS.

- 93.3 However, any increase in the rate of these taxes, duties and levies beyond the contractual completion period shall be to Contractor's account and any decrease shall be passed on to Employer/ Owner.

94. Insurance

- 94.1 During the entire Contract period including O&M period, i.e., during Construction & O&M period, all insurance related expenses shall be borne by the Contractor. The goods supplied under the Contract shall be fully insured against the loss or damage incidental to manufacture or acquisition, transportation, storage and delivery in such a manner that Employer/Owner shall not incur any financial loss, as long as the plant continues to remain under the custody of the Contractor. During O&M period also (after the Contract period is over), the insurances shall be in the scope of the contractor.
- 94.2 In case of any loss or damage or pilferage or theft or fire accident or combination of the said incidents etc. under the coverage of insurance, the Contractor shall lodge the claim as per rules of insurance. Any FIR required to be lodged to local Police Station shall be the responsibility of the Contractor.
- 94.3 The Contractor shall arrange to supply/ rectify/ recover the materials even if the claim is unsettled for timely completion of the project. The final financial settlement with the insurance company shall rest upon the Contractor.
- 94.4 In case of any delay of the project attributable to the Contractor, the Contractor himself in consultation with Owner/Employer should take the extension of insurance. Any financial implications shall, however, be borne by the Contractor.

- 94.5 The Contractor should arrange for providing insurance coverage to its workmen under Workmen's Compensation Act or similar Rules and Acts as applicable during execution of work for covering risk against any mishap to its workmen. The Contractor shall also undertake a Third Party Insurance. The Owner/ Employer will not be responsible for any such loss or mishap.
- 94.6 All other insurance like In – transit insurance (Marine/ Cargo/ others as applicable), Contractor All Risk, Erection All Risk, workmen compensation , third party liability, insurance against theft and acts of GOD and others as required for the Construction and O&M of the Plant and to indemnify the Employer/ equipment/ material and resources shall be borne by the Contractor. Fire insurance is to be arranged by the Contractor up to the years of O&M of the Contract.
- 94.7 Owner/ Employer shall be named as co – insured under all insurance policies taken out by the contractor pursuant to GCC Clause, except for the workmen compensation, third party liability and Owner's/Employer's liability insurances. Also, Contractors' sub – contractor shall be named as co – insured under all insurances taken out by the contractor pursuant to GCC Clause except for Cargo insurance, workmen compensation insurance and Employer's/Owner's liability insurance. All insurers' rights of subrogation against such co – insured for losses or claims arising out of the performance of the contract shall be waived under such policies.
- 94.8 All the insurance cover taken for the construction and O&M period shall be seamless in nature.
- 94.9 The insurance are to be suitably taken for the activity/ act which is required to cover all the risks associated to the activity / act. The contractor shall be responsible to take suitable insurance till the completion of the O&M contract and indemnify the Employer/Owner from all associated risks whatsoever.

94.10 Employees State Insurance (ESI) Act

The Contractor agrees to and does hereby accept full and exclusive liability for the compliance with all obligations imposed by the Employee State Insurance Act 1948 and the Contractor further agrees to defend, indemnify and hold Employer/ Owner harmless for any liability or penalty which may be imposed by the Central, State or Local authority by reason of any asserted violation by Contractor or Sub-Contractor of the Employees' State Insurance Act, 1948, and also from all claims, suits or proceeding that may be brought against the Employer/ Owner arising under, growing out of or by reasons of the work provided for by this Contractor, by third parties or by Central or State Government authority or any political sub- division thereof. The Contractor agrees to fill in with the Employee's State Insurance Corporation, the Declaration Forms, and all forms which may be required in respect of the Contractor's or Sub-Contractor's employees, who are employed in the Work provided for or those covered by ESI from time to time under the Agreement. The Contractor shall deduct and secure the agreement of the Sub-Contractor to deduct the Employee's contribution as per the first schedule of the Employee's State Insurance Act from wages and affix the Employees Contribution Card at wages payment intervals. The Contractor shall remit and secure the agreement of Sub-Contractor to remit to the Employee's State Insurance Corporation Account, the Employee's contribution as required by the Act. The Contractor agrees to maintain all cards and Records as required under the Act in respect of employees and payments and the Contractor shall secure the agreement of the Sub-Contractor to maintain such records. Any expenses incurred for the contributions, making contributions or maintaining records shall be to the Contractor's or Sub-Contractor's account. The Employer/ Owner shall retain such sum as may be necessary from the total Value of Contract until the Contractor shall furnish satisfactory proof that all contributions as required by the Employees State Insurance Act, 1948, have been paid. This will be pending on the Contractor when the ESI Act is extended to the place of work.

“The Contractors shall have the registration with EPFO & ESIC. The EPF & ESI contribution on the part of Employer/ Owner in respect of this Contract shall be paid by the Contractor.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 65 of 77</u>	<u>Signature of Bidder</u>

These contributions on the part of Employer/ Owner paid by the Contractor shall be reimbursed by the Engineer-in-Charge/Project Manager to the Contractor on actual basis”.

94.11 Workmen Compensation and Employer's/Owner's Liability Insurance

Insurance shall be effected for all the Contractor's employees engaged in the performance of this Contract. If any of the work is sublet, the Contractor shall require the Sub-Contractor to provide workman's Compensation and Employer's/ Owner's liability insurance for the later employees if such Employees are not covered under the Contractor's Insurance.

94.12 Accident or Injury to Workmen

The Employer/ Owner shall not be liable for or in respect of any damages or compensation payable at law in respect or in consequence of any accident or injury to any workman or other person in the Employment of the Contractor or any Sub-Contractor save and except an accident or injury resulting from any act or default of the Employer/ Owner, his agents or servants and the Contractor shall indemnify and keep indemnified the Employer/ Owner against all such damages and compensation (save and except and aforesaid) and against all claims, demands, proceeding, costs, charges and expenses, whatsoever in respect or in relation thereto.

94.13 Transit Insurance

In respect of all items to be transported by the Contractor to the Site of Work, the cost of transit insurance should be borne by the Contractor and the quoted price shall be inclusive of this cost.

94.14 Comprehensive Automobile Insurance

This insurance shall be in such a form as to protect the Contractor against all claims for injuries, disability, disease and death to members of public including Employer's/ Owner's men and damage to the property of others arising from the use of motor vehicles during on or off the site operations, irrespective of the Employership of such vehicles.

94.15 Comprehensive General Liability Insurance

a) This insurance shall protect the Contractor against all claims arising from injuries, disabilities, disease or death of member of public or damage to property of others due to any act or omission on the part of the Contractor, his agents, his employees, his representatives and Sub-Contractor's or from riots, strikes and civil commotion.

b) Contractor shall take suitable Group Personal Accident Insurance Cover for taking care of injury, damage or any other risks in respect of his Engineers and other Supervisory staff who are not covered under Employees State Insurance Act.

c) The policy shall cover third party liability. The third party (liability shall cover the loss/ disablement of human life (person not belonging to the Contractor) and also cover the risk of damage to others materials/ equipment/ properties during construction, erection and commissioning at site.

The value of third party liability for compensation for loss of human life or partial/ full disablement shall be of required statutory value but not less than INR 2 (Two) Lakhs per death, INR 1.5 (One and Half) Lakhs per full disablement and INR 1 (One) Lakh per partial disablement and shall nevertheless cover such compensation as may be awarded by Court by Law in India and cover for damage to others equipment/ property as approved by the Purchaser. However, third party risk shall be maximum to INR 10 (Ten) Lakhs to death.

d) The Contractor shall also arrange suitable insurance to cover damage, loss, accidents, risks etc., in respect of all his plant, equipment and machinery, erection tools & tackles and all other temporary attachments brought by him at site to execute the work.

e) The Contractor shall take out insurance policy in the joint name of Employer/ Owner and Contractor from one or more nationalized insurance company from any branch office at Project site.

f) Any such insurance requirements as are hereby established as the minimum policies and coverages which Contractor must secure and keep in force must be complied with, Contractor shall at all times be free to obtain additional or increased coverages at Contractor's sole expenses.

viii) ANY OTHER INSURANCE REQUIRED UNDER LAW OR REGULATIONS OR BY EMPLOYER/OWNER:

Contractor shall also carry and maintain any and all other insurance(s) which he may be required under any law or regulation from time to time without any extra cost to Employer/ Owner. He shall also carry and maintain any other insurance which may be required by the Employer/ Owner.

95 Damage to Property or to any Person or any Third Party

95.1 Contractor shall be responsible for making good to the satisfaction of the Employer/ Owner any loss or any damage to structures and properties belonging to the Employer/ Owner or being executed or procured or being procured by the Employer/ Owner or of other agencies within in the premises of all the work of the Employer/ Owner, if such loss or damage is due to fault and/ or the negligence or willful acts or omission of the Contractor, his employees, agents, representatives or Sub-Contractors.

95.2 The Contractor shall take sufficient care in moving his plants, equipment and materials from one place to another so that they do not cause any damage to any person or to the property of the Employer/ Owner or any third party including overhead and underground cables and in the event of any damage resulting to the property of the Employer/ Owner or of a third party during the movement of the aforesaid plant, equipment or materials the cost of such damages including eventual loss of production, operation or services in any plant or establishment as estimated by the Employer/ Owner or ascertained or demanded by the third party shall be borne by the Contractor. Third party liability risk shall be INR 1 (One) Lakh for single accident and limited to INR 10 (Ten) Lakhs.

95.3 The Contractor shall indemnify and keep the Employer/ Owner harmless of all claims for damages to property other than Employer's/ Owner's property arising under or by reason of this agreement, if such claims result from the fault and/ or negligence or willful acts or omission of the Contractor, his employees, agents, representative of Sub-Contractor.

[H] LABOUR LAWS

96. Labour Laws & Indemnity Bond

i) No labour below the age of 18 (Eighteen) Years shall be employed on the Work.

ii) The Contractor shall not pay less than what is provided under law to labourers engaged by him on the Work.

iii) The Contractor shall at his expense comply with all labour laws and keep the Employer/ Owner indemnified in respect thereof.

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

iv) The Contractor shall pay equal wages for men and women in accordance with applicable labour laws.

v) If the Contractor is covered under the Contract Labour (Regulation and Abolition) Act, he shall obtain a license from licensing authority (i.e. office of the labour commissioner) by payment of necessary prescribed fee and the deposit, if any, before starting the Work under the Contract. Such fee/ deposit shall be borne by the Contractor.

vi) The Contractor shall employ labour in sufficient numbers either directly or through Sub-Contractor's to maintain the required rate of progress and of quality to ensure workmanship of the degree specified in the Contract and to the satisfaction of the Engineer-in-Charge/Project Manager.

vii) The Contractor shall furnish to the Engineer-in- Charge the distribution return of the number and description, by trades of the work people employed on the works. The Contractor shall also submit on the 4th and 19th of every month to the Engineer-in-Charge/Project Manager a true statement showing in respect of the second half of the preceding month and the first half of the current month (1) the accidents that occurred during the said fortnight showing the circumstances under which they happened and the extent of damage and injury caused by them and (2) the number of female workers who have been allowed Maternity Benefit as provided in the Maternity Benefit Act 1961 on Rules made thereunder and the amount paid to them.

viii) The Contractor shall comply with the provisions of the Payment of Wage Act 1936, Employee Provident Fund Act 1952, Minimum Wages Act 1948. Employers Liability Act 1938. Workmen's Compensation Act 1923, Industrial Disputes Act 1947, the Maternity Benefit Act 1961 and Contract Labour Regulation and Abolition Act 1970, Employment of Children Act 1938 or any modifications thereof or any other law relating thereto and rules made thereunder from time to time.

ix) The Engineer-in-Charge/Project Manager shall on a report having been made by an Inspecting Officer as defined in Contract Labour (Regulation and Abolition) Act 1970 have the power to deduct from the money due to the Contractor any sum required or estimated to be required for making good the loss suffered by a worker or workers by reason of non- fulfillment of the Conditions of the Contract for the benefit of workers, non-payment of wages or of deductions made from his or their wages which are not justified by the terms of the Contract or non-observance of the said regulations.

x) The Contractor shall indemnify the Employer/ Owner against any payments to be made under and for the observance of the provisions of the aforesaid Acts without prejudice to his right to obtain indemnity from his Sub-Contractor's. In the event of the Contractor committing a default or breach of any of the provisions of the aforesaid Acts as amended from time to time, of furnishing any information or submitting or filling and Form/ Register/ Slip under the provisions of these Acts which is materially incorrect then on the report of the inspecting Officers, the Contractor shall without prejudice to any other liability pay to the Employer/ Owner a sum not exceeding INR 5000 as Liquidated Damages for every default, breach or furnishing, making, submitting, filling materially incorrect statement as may be fixed by the Engineer-in-Charge/Project Manager and in the event of the Contractor's default continuing in this respect, the Liquidated Damages may be enhanced to INR 5000 per day for each day of default subject to a maximum of 01 (One) Percent of the estimated cost of the Work put to tender. The Engineer-in-Charge/Project Manager shall deduct such amount from bills or Contract Performance Security of the Contractor and credit the same to the Welfare Fund constitute under these acts. The decision of the Engineer-in-Charge/Project Manager in this respect shall be final and binding.

xi) The Contractor shall also indemnify to keep the Owner/ Employer harmless from any act of omission or negligence on the part of the Labour Laws compliance in following the statutory requirements with regard to Labour laws. Against the signing of the contract, The Indemnity Bond shall be furnished by contractor as per Format enclosed under Forms and Formats for the labour law compliance . Further, in case the laws require the Employer/Owner to take prior permission of

the relevant Authorities before handing over the scrap to the Contractor, the same shall be obtained by the Contractor on behalf of the Employer/Owner.

97. Implementation of Apprentices Act, 1961

97.1 The Contractor shall comply with the provisions of the Apprentices Act, 1961 and the Rules and Orders issued thereunder from time to time. If he fails to do so, his failure will be a breach of the Contract and the Engineer-in-Charge/Project Manager may, at his discretion, cancel the Contract. The Contractor shall also be liable for any pecuniary liability arising on account of any violation by him of the provisions, of the Act.

98. Contractor to Indemnify the Employer/ Owner

98.1 The Contractor shall indemnify the Employer/ Owner and every member, office and employee of the Employer/ Owner, also the Engineer-in-Charge/Project Manager and his staff against all actions, proceedings, claims, demands, costs and expenses whatsoever arising out of or in connection with the matters referred to in Clause 95 and elsewhere and all actions, proceedings, claims, demands, costs and expenses which may be made against the Employer/ Owner for or in respect of or arising out of any failure by the Contractor in the performance of his obligations under the Contract Document. The Employer/ Owner shall not be liable for or in respect of or arising out of any failure by the Contractor in the performance of his obligations under the Contract Document. The Employer/ Owner shall not be liable for or in respect of any demand or compensation payable by law in respect or in consequence of any accident or injury to any workmen or other person. In the employment of the Contractor or his Sub-Contractor the Contractor shall indemnify and keep indemnified the Employer/ Owner against all such damages and compensations and against all claims, damages, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto.

98.2 Payment of Claims and Damages

Should the Employer/ Owner have to pay any money in respect of such claims or demands as aforesaid the amount so paid and the costs incurred by the Employer/ Owner shall be charged to and paid by the Contractor and the Contractor shall not be at liberty to dispute or question the right of the Employer/ Owner to make such payments notwithstanding the same, may have been made without the consent or authority or in law or otherwise to the contrary.

98.3 In every case in which by virtue of the provisions of Section 12, Sub-section (i) of workmen's compensation Act, 1923 or other applicable provision of Workmen Compensation Act or any other Act, the Employer/ Owner is obliged to pay compensation to a workman employed by the Contractor in execution of the Work, the Employer/ Owner will recover from the Contractor the amount of the compensation so paid, and without prejudice to the rights of Employer/ Owner under Section 12, Sub- section (2) of the said Act, Employer/ Owner shall be at liberty to recover such amount or any part thereof by deducting it from the Contract Performance Security or from any sum due to the Contractor whether under this Contract or otherwise. The Employer/ Owner shall not be bound to contest any claim made under Section 12, Sub-section (i) of the said act, except on the written request of the Contractor and upon his giving to the Employer/ Owner full security for all costs for which the Employer/ Owner might become liable in consequence of contesting such claim.

99. Health and Sanitary Arrangements for Workers

99.1 In respect of all labour directly or indirectly employed in the Works for the performance of the Contractor's part of this agreement, the Contractor shall comply with or cause to be complied with all the rules and regulations of the local sanitary and other authorities or as framed by the Employer/ Owner from time to time for the protection of health and sanitary arrangements for all workers.

- 99.2 The Contractor shall provide in the labour colony all amenities such as electricity, water and other sanitary and health arrangements. The Contractor shall also provide necessary surface transportation to the place of work and back to the colony for their personnel accommodated in the labour colony.

[I] APPLICABLE LAWS & SETTLEMENT OF DISPUTES

100 A. Adjudicator

100 A.1 If any dispute of any kind whatsoever shall arise between the Owner/Employer and the Contractor in connection with or arising out of the Contract, including without prejudice to the generality of the foregoing, any question regarding its existence, validity or termination, or the execution of the facilities-whether during the progress of the facilities or after their completion and whether before or after the termination, abandonment or breach of the contract-parties shall seek to resolve such a dispute or difference by mutual consultation. If the parties fail to resolve such a dispute or difference by mutual consultation, then the dispute shall be referred in writing by either party to the Adjudicator, with a copy to the other party.

100 A.2 The dispute adjudication board (DAB) shall consists of either one or three suitably qualified member ("the Members").

100 A.3 If the DAB consists of three members, each party shall nominate one member for the approval of the other party. The parties shall consult both the members and shall agree upon third member, who shall be appointed as Chairman of DAB.

100 A.4 The Adjudicator shall give its decision in writing to both parties within twenty-eight (28) days of a dispute being referred to it. If the Adjudicator has done so, and no notice of intention to commence arbitration has been given by either the Owner/Employer or the Contractor within fifty – six (56) days of such reference, the decision shall become final and binding upon the Owner/Employer and the Contractor. Any decision that has become final and binding shall be implemented by the parties forthwith.

100 A.5 Should the Adjudicator resign or prolonged absence from work assigned due to unforeseen circumstances, or should the Owner/Employer and the Contractor agree that the Adjudicator is not fulfilling its functions in accordance with the provisions of the contract, a new Adjudicator shall be jointly appointed by the Owner/Employer and the Contractor. Failing agreement between the two within twenty eight (28) days, the new Adjudicator shall be appointed at the request of either party or by the Appointing Authority The adjudicator shall be paid fee plus reasonable expenditures incurred in the execution of its duties as adjudicator under the contract. This cost shall be divided equally between the Owner/Employer and the Contractor.

100 B. Arbitration

100 B.1 Unless otherwise specified, the matters where decision of the Engineer-in-Charge/Project Manager is deemed to be final and binding as provided in the Agreement and the issues/ disputes which cannot be mutually resolved within a reasonable time, all disputes shall be referred to arbitration by Sole Arbitrator. The Employer/ Owner shall suggest a panel of three independent and

distinguished persons to the Bidder/ Contractor/ Supplier (as the case may be) to select any one among them to act as the Sole Arbitrator. In the event of failure of the other parties to select the Sole Arbitrator within 30 (Thirty) Days from the receipt of the communication suggesting the panel of arbitrators, the right of selection of the sole arbitrator by the other party shall stand forfeited and the Employer/ Owner shall have discretion to proceed with the appointment of the Sole Arbitrator. The decision of Employer/ Owner on the appointment of the sole arbitrator shall be final and binding on the parties. The award of sole arbitrator shall be final and binding on the parties and unless directed/ awarded otherwise by the sole arbitrator, the cost of arbitration proceedings shall be shared equally by the parties. The Arbitration proceedings shall be in English language and venue shall be New Delhi, India. Subject to the above, the provisions of (Indian) Arbitration & Conciliation Act 1996 and the Rules framed there under shall be applicable. All matter relating to this contract are subject to the exclusive jurisdiction of the court situated in the state of New Delhi. Bidders/ Suppliers/ Contractors may please note that the Arbitration & Conciliation Act 1996 was enacted by the Indian Parliament and is based on United Nations Commission on International Trade Law (Uncitral Model Law), which were prepared after extensive consultation with Arbitral Institutions and centers of International Commercial Arbitration. The United Nations General Assembly vide resolution 31/98 adopted the Uncitral Arbitration Rules on 15th December 1976.

100 B.2 FOR THE SETTLEMENT OF DISPUTES BETWEEN GOVERNMENT DEPARTMENT AND ANOTHER AND ONE GOVERNMENT DEPARTMENT AND PUBLIC ENTERPRISE AND ONE PUBLIC ENTERPRISE AND ANOTHER THE ARBITRATION SHALL BE AS FOLLOWS:

"In the event of any dispute or difference between the parties hereto, such dispute or difference shall be resolved amicably by mutual consultation or through the good offices of empowered agencies of the Government. If such resolution is not possible, then, the unresolved dispute or difference shall be referred to arbitration of an arbitrator to be nominated by Secretary, Department of Legal Affairs ("Law Secretary") in terms of the Office Memorandum No.55/3/1/75-CF, dated the 19th December 1975 issued by the Cabinet Secretariat (Department of Cabinet Affairs), as modified from time to time. The Arbitration Act 1940 (10 of 1940) shall not be applicable to the arbitration under this clause. The award of the Arbitrator shall be binding upon parties to the dispute. Provided, however, any party aggrieved by such award may make a further reference for setting aside or revision of the award to Law Secretary whose decision shall bind the parties finally and conclusively.

101. Jurisdiction

- 101.1 The Contract shall be governed by and constructed according to the laws in force in INDIA. The Contractor hereby submits to the jurisdiction of the Courts situated at "**State of the Owner of the Project as defined in the BDS/SCC**" for the purposes of disputes, actions and proceedings arising out of the Contract, the courts at "**State of the Owner of the Project**" only will have the jurisdiction to hear and decide such disputed, actions and proceedings.

[J] SAFETY CODES

102. General

- 102.1 Contractor shall adhere to safe construction practice and guard against hazardous, and unsafe working conditions and shall comply with Safety rules as set forth herein.

Any hazardous material used during construction or used as part of the plant has to be taken back by the supplier for recycling or dumping purpose after its operating / working life, so that it may not affect the environment or any living being. Bidder(s) have to comply with Telangana State Pollution Board regulation.

103. Safety Regulations

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	GCC <u>Page 71 of 77</u>	<u>Signature of Bidder</u>

103.1 i) In respect of all labour, directly employed in the Work for the performance of Contractor's part of this agreement, the Contractor shall at his own expense arrange for all the safety provisions as per safety codes of C.P.W.D., Indian Standards Institution. The Electricity Act, The Mines Act and such other acts as applicable.

ii) The Contractor shall observe and abide by all fire and safety regulations of the Employer/ Owner. Before starting construction work Contractor shall consult with Employer's/ Owner's safety Engineers or Engineer-in-Charge/Project Manager and must make good to the satisfaction of the Employer/ Owner any loss or damage due to fire to any portion of the work done or to be done under this agreement or to any of the Employer's/ Owner's existing property.

104. First Aid and Industrial Injuries

104.1 i) Contractor shall maintain first aid facilities for its employees and those of its Sub-Contractor.

ii) Contractor shall make outside arrangements for Ambulance Service and for the treatment of industrial injuries. Names of those providing these services shall be furnished to Employer/ Owner prior to start of construction and their telephone numbers shall be prominently posted in Contractor's Site Office.

ii) All critical industrial injuries shall be reported promptly to Employer/ Owner, and a copy of Contractor's report covering each personal injury requiring the attention of a physician shall be furnished to the Employer/ Owner.

105. General Rules

105.1 Smoking within the battery area, tank farm or dock limits is strictly prohibited. Violators of the no smoking rules shall be discharged immediately.

106. Contractor's Barricades

106.1 i) Contractor shall erect and maintain barricades required in connection with his operation to guard or protect: -

- a) Excavations
- b) Hoisting Areas.
- c) Areas adjudged hazardous by Contractor's or Employer's/ Owner's inspectors.
- d) Employer's/ Owner's existing property subject to damage by Contractor's Operations.
- e) Rail Road unloading spots

ii) Contractor's employees and those of his Sub-Contractor's shall become acquainted with Employer's/ Owner's barricading practice and shall respect the provisions thereof.

iii) Barricades and hazardous areas adjacent to, but not located in normal routes of travel shall be marked by red flasher lanterns at nights.

107. Scaffolding

107.1 i) Suitable scaffolding should be provided for workmen for all works that cannot safely be done from the ground or from solid construction except such short period work as can be done safely from ladders. When a ladder is used an extra Mazdoor shall be engaged for holding the ladder and if the ladder is used for carrying material as well, suitable footholds and handholds shall be provided on the ladder and the ladder shall be given an inclination not steeper than 1 in 4 (1 Horizontal and 4 Vertical).

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

ii) Scaffolding or staging more than 4 meters above the ground or floor, swing suspended from an overhead support or erected with stationary support shall have a guard rail properly attached, bolted, braced and otherwise retarded at least one meter high above the floor or platform of such scaffolding or staging and extending along the entire length of the outside and ends thereof with only such openings as may be necessary for the delivery of materials. Such scaffolding or staging shall be so fastened as to prevent it from swaying from the building or structure.

iii) Working platform, gangway and stairway should be so constructed that they should not sag unduly or unequally and if the height of platform of the gangway or the stairway is more than 4 meters above the ground level or floor level, they should be closely boarded, should have adequate width and should be suitably fastened as in ii) above.

iv) Every opening in the floor of a building or in a working platform shall be provided with suitable means to prevent the fall of persons or materials by providing suitable fencing or railing whose minimum heights shall be 1 meter.

v) Safe-means of access shall be provided to all working platforms and other working places, every ladder shall be securely fixed. No portable single ladder shall be over 9 meters in length while the width between side rails in rung ladder shall in no case be less than 30cms for ladder up to and including 3 meters in length. For longer ladder this width should be increased 5mm for each additional foot of length. Uniform steps spacing shall not exceed 30cms. Adequate precautions shall be taken to prevent danger from electrical equipment. No materials on any of the sites or work shall be so stacked or placed to cause danger or inconvenience to any person or public. The Contractor shall also provide all necessary fencing and lights to protect the workers and staff from accidents, and shall be bound to bear the expenses of defense of every suit, action or other proceeding of law that may be brought by any person for injury sustained owing to neglect of the above precautions and pay any damages and costs which may be awarded in any such suit or action or proceeding to any such person or which may with the consent of the Contractor be paid to compromise any claim by any such person.

108. Excavation and Trenching

108.1 All trenches 1.2 Meters or more in depth, shall at all times be supplied with at least one ladder for each 50 Meters length or fraction thereof. Ladder shall be extended from bottom of the trenches to at least 1 meter above the surface of the ground. The sides of the trenches which are 1.5 Meters in depth shall be stepped back to give suitable slope or securely held by timber bracing, so as to avoid the danger of sides to collapse. The excavated materials shall not be placed within 1.5 Meters of the edge of the trench or half of the trench width whichever is more. Cutting shall be done from top to bottom. Under no circumstances undermining or under-cutting shall be done.

109. Demolition/ General Safety

- 109.1 i) Before any demolition work is commenced and also during the progress of the demolition work
- a) All roads and open areas adjacent to the work site shall either be closed or suitably protected.
 - b) No electric cable or apparatus which is liable to be a source of danger shall remain electrically charged.
 - c) All practical steps shall be taken to prevent danger to persons employed from risk of fire or explosion or flooding. No floor, roof or other part of the building shall be so overloaded with debris or materials as to render it unsafe.

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

ii) All necessary personal safety equipment as considered adequate by the Engineer-in-Charge/Project Manager, should be kept available for the use of the persons employed on the Site and maintained in condition suitable for immediate use, and the Contractor shall take adequate steps to ensure proper use of equipment by those concerned.

a) Workers employed on mixing asphaltic materials, cement and lime mortars shall be provided with protective footwear and protective gloves.

b) Those engaged in white washing and mixing or stacking or cement bags or any material which are injurious to the eyes be provided with protective goggles.

c) Those engaged in welding and cutting works shall be provided with protective face & eye shield, hand gloves, etc.

d) Stone breakers shall be provided with protective goggles and protective clothing and seated at sufficiently safe intervals.

e) When workers are employed in sewers and manholes, which are in use, the CONTRACTOR shall ensure that the manhole covers are opened and are ventilated at least for an hour before the workers are allowed to get into the manholes, and the manholes so opened shall be cordoned off with suitable railing and provided with warning signals or board to prevent accident to the public.

f) The CONTRACTOR shall not employ men below the age of 18 years and women on the work of painting with products containing lead in any form. Wherever men above the age of 18 years are employed on the work of lead painting, the following precautions should be taken.

1) No paint containing lead or lead product shall be used except in the form of paste or readymade paint.

2) Suitable face masks should be supplied for use by the workers when paint is applied in the form of spray or a surface having lead paint dry rubbed and scrapped.

3) Overalls shall be supplied by the Contractor to the workmen and adequate facilities shall be provided to enable the working painters to wash them during and on cessation of work.

iii) When the work is done near any place where there is risk of drowning, all necessary safety equipment should be provided and kept ready for use and all necessary steps taken for prompt rescue of any person in danger and adequate provision should be made for prompt first aid treatment of all injuries likely to be sustained during the course of the work.

iv) Use of hoisting machines and tackles including their attachments, anchorage and supports shall conform to the following standards or conditions:

a) These shall be of good mechanical construction, sound materials and adequate strength and free from patent defect and shall be kept in good working order.

b) Every rope used in hoisting or lowering materials or as means of suspension shall be of durable quality and adequate strength and free from patent defects.

c) Every crane driver or hoisting appliance operator shall be properly qualified and no person under the age of 21 years should be in charge of any hoisting machine including any scaffolding, winch or give signals to the operator.

d) In case of every hoisting machine and of every chain ring hook, shackle, swivel, and pulley block used in hoisting or lowering or as means of suspension, the safe working load shall be ascertained by adequate means. Every hoisting machine and all gears referred to above shall be plainly marked with the safe working load of the conditions under which it is applicable and the same shall be clearly

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

indicated. No part of any machine or any gear referred to above in this paragraph shall be loaded beyond safe working load except for the purpose of testing.

e) In case of departmental machine, the safe working load shall be notified by the Engineer-in-Charge/Project Manager. As regards Contractor's machines, the Contractor shall notify the safe working load of the machine to the Engineer-in-Charge/Project Manager whenever he brings any machinery to Site of Work and get it verified by the Engineer concerned.

v) Motors, gears, transmission lines, electric wiring and other dangerous parts of hoisting appliances should be provided with efficient safeguards. Hoisting appliances should be provided with such means as to reduce to minimum the accidental descent of the load, adequate precautions should be taken to reduce the minimum risk of any part or parts of a suspended load becoming accidentally displaced. When workers are employed on electrical installations which are already energized, insulating mats, wearing apparel, such as gloves, sleeves, and boots as may be necessary should be provided. The workers shall not wear any rings, watches and carry keys or other materials which are good conductors of electricity.

vi) All scaffolds, ladders and other safety devices mentioned or described herein shall be maintained in safe conditions and no scaffolds, ladder or equipment shall be altered or removed while it is in use. Adequate washing facilities should be provided at or near places of work.

vii) These safety provisions should be brought to the notice of all concerned by displaying on a notice board at a prominent place at the work-spot. The person responsible for compliance of the safety code shall be named therein by the Contractor.

viii) To ensure effective enforcement of the rules and regulations relating to safety precautions, the arrangements made by the Contractor shall be open to inspection by the Welfare Officer, Engineer-in-Charge/Project Manager or safety Engineer of the Administration or their representatives.

ix) Notwithstanding the above clauses there is nothing in these to exempt the Contractor for the operations of any other Act or rules in force in the Republic of India. The work throughout including any temporary works shall be carried out in such a manner as not to interfere in any way whatsoever with the traffic on any roads or footpath at the site or in the vicinity thereto or any existing works whether the property of the Administration or of a third party. In addition to the above, the Contractor shall abide by the safety code provision as per C.P.W.D. Safety code and Indian Standard Safety Code from time to time.

110. Care in Handling Inflammable Gas

110.1 The Contractor has to ensure all precautionary measures and exercise utmost care in handling the inflammable gas cylinder/ inflammable liquids/ paints etc. as required under the law and/ or as advised by the fire Authorities of the Employer/ Owner.

111. Temporary Combustible Structures

111.1 Temporary combustible structures will not be built near or around work site.

112. Precautions against Fire

112.1 The Contractor will have to provide Fire Extinguishers, Fire Buckets and drums at worksite as recommended by Engineer-in-Charge/Project Manager. They will have to ensure all precautionary measures and exercise utmost care in handling the inflammable gas cylinders/ inflammable liquid/ paints etc. as advised by Engineer-in-Charge/Project Manager. Temporary combustible structure will not be built near or around the work-site.

113. Explosives

- 113.1 Explosives shall not be stored or used on the Work or on the Site by the Contractor without the permission of the Engineer-in-Charge/Project Manager in writing and then only in the manner and to the extent to which such permission is given. When explosives are required for the Work they will be stored in a special magazine to be provided at the cost of the Contractor in accordance with the Explosives Rules. The Contractor shall obtain the necessary license for the storage and the use of explosives and all operations in which or for which explosives are employed shall be at sole risk and responsibility of the Contractor and the Contractor shall indemnify the Employer/Owner against any loss or damage resulting directly or indirectly therefrom.

114 Mines Act

- 114.1 SAFETY CODE: The Contractor shall at his own expense arrange for the safety provisions as required by the Engineer-in-Charge/Project Manager in respect of all labour directly employed for performance of the Works and shall provide all facilities in connection therewith. In case the Contractor fails to make arrangements and provides necessary facilities as aforesaid, the Engineer-in-Charge/Project Manager shall be entitled to do so and recover the costs thereof from the Contractor.
- 114.2 Failure to comply with Safety Code or the provisions relating to report on accidents and to grant of maternity benefits to female workers shall make the Contractor liable to pay Company Liquidated Damages an amount not exceeding INR 50/- for each default or materially incorrect statement. The decision of the Engineer-in-Charge/Project Manager in such matters based on reports from the Inspecting Officer or from representatives of Engineer-in-Charge/Project Manager shall be final and binding and deductions for recovery of such Liquidated Damages may be made from any amount payable to the Contractor from all the provisions of the Mines Act, 1952 or any statutory modifications or re-enactment thereof the time being in force and any Rules and Regulations made thereunder in respect of all the persons employed by him under this Contract and shall indemnify the Employer/ Owner from and against any claim under the Mines Act or the rules and regulations framed thereunder by or on behalf of any persons employed by him or otherwise.

115. Preservation of Place

- 115.1 The Contractor shall take requisite precautions and use his best endeavors to prevent any riotous or unlawful behavior by or amongst his worker and others employed or the works and for the preservation of peace and protection of the inhabitants and security of property in the neighborhood of the Work. In the event of the Employer/ Owner requiring the maintenance of a Special Police Force at or in the vicinity of the site during the tenure of works, the expenses thereof shall be borne by the Contractor and if paid by the Employer/ Owner shall be recoverable from the Contractor.

116. Outbreak of Infectious Diseases

- 116.1 The Contractor shall remove from his camp such labour and their facilities who refuse protective inoculation and vaccination when called upon to do so by the Engineer-in-Charge/Project Manager's representative. Should Cholera, Plague or other infectious diseases break out the Contractor shall burn the huts, beddings, clothes and other belongings or used by the infected parties and promptly erect new huts on healthy sites as required by the Engineer-in-Charge/Project Manager failing which within the time specified in the Engineer's requisition, the work may be done by the Employer/ Owner and the cost thereof recovered from the Contractor.

117. Use of Intoxicants

- 117.1 The unauthorized sale of spirits or other intoxicants, beverages upon the work in any of the buildings, encampments or tenements owned, occupied by or within the control of the Contractor or any of his

Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of
5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant
O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding

employee is forbidden and the Contractor shall exercise his influence and authority to the utmost extent to secure strict compliance with this condition. In addition to the above, the Contractor shall abide by the safety code provision as per C.P.W.D. safety code and Indian Standard Code framed from time to time.



SECTION - V

SPECIAL CONDITIONS OF CONTRACT (SCC)

SPECIAL CONDITIONS OF CONTRACT (SCC)

The following Special Conditions of Contract (SCC) shall supplement the General Conditions of Contract (GCC). Wherever there is a conflict, the provisions herein shall prevail over those in the GCC. The corresponding Clause number(s) of the GCC is/ are indicated in parentheses.

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
1.	Definitions (Clause No. 1)	The Employer is: Solar Energy Corporation of India Limited, D - 3, 1st Floor, Wing - A, Prius Platinum Building, District Centre Saket, New Delhi - 110 017 Kind Attn.: General Manager (C & P) / Manager (C & P) Telephone Nos.: - 0091-(0)11-71989256/ 71989290 Fax No.: - 0091-(0)11-71989243 E-mail: - contracts@seci.co.in The Owner is: Bharat Dynamics Limited, Kanchanbagh Hyderabad (Dist.), Telangana(State) - 500058 Kind Attn.: Shri CH Ramesh Babu (AGM) Telephone Nos.: - 0091-(0) 040-24587104/24587124 Fax No.: - 0091-(0) 040-24340464 E mail: tsdkbc.bdl@bdl-india.com
2.		The Engineer-in-Charge is: "To be nominated"
3.		Time for Completion is: 6 (Six) Months from the date of issuance of NOA/ LOI/ LOA as detailed below in Table No. 3.1. Further Contractor is also to provide Operation & Maintenance Contract of Solar Photo Voltaic Plant for a period of 5 (Five) years from the date of Operational Acceptance of the Plant.

Table No. 4.1

S. No.	Stage	Reference from D
3.1.1	Issue of NOA/ LOI/ LOA	Zero Date (D)
3.1.2	Detailed Engineering Design and Drawing Approvals & Procurement Planning and Approval	D + 2 Month
3.1.3	Completion of supply of major equipment like SPV Modules (including structure for the above), Power Conditioning Units, transformers etc.	D + 3 Months
3.1.4	Installation of all Major Equipment	D + 4 Months
3.1.5	Interconnection of all Major Equipments and Completion of Installation	D + 5 Months
3.1.6	Completion, Testing and Pre-Commissioning of Solar PV Power Plant	
3.1.7	Commissioning of Plant along with Completion of Facilities in line with Technical/ Functional/ Performance Requirement stated under this Tender Document along with demonstration of PG Tests as mentioned in the SCC	<u>D + 6 Months</u>

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
4.	Location of Site (Clause No. 2.1.a)	The Location of Site is: The Grid Connected Solar PV Power Plant shall be installed at the designated land location of Bharat Dynamics Limited, Ibrahimpatnam, In the State of Telangana. Bidders should take a note that the attached available land area & is tentative which may slightly vary at the time of actual execution. The contractor has to suitably plan the layout of the Plant including shadow analysis for optimum utilization of Space and the structural analysis. For actual distance/ routing of cables & evacuation, Bidders are advised to visit the site. The allocated land will be handed over to the Contractor by the owner. The project sites are within the Solar Park hence the contractor shall strictly follow proper care, work permit & safety system. (Refer Section-VII for the Project site layout)
5.	New Clause (Notice of Operation)	The Contractor shall not carry out important operation without the consent in writing of the Employer/Owner or his representative. For carrying out such important activity, the Contractor shall intimate to the Employer/Owner at least 72 hours before starting of the job.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SCC <u>Page 3 of 10</u>	<u>Signature of Bidder</u>

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
6.	New Clause (Contract Performance Security)	Against EPC/ LSTK Contract & O&M Contract of the project, within 30 (Thirty) days from the issuance of the Notification of Award/ Letter of Intent/ Letter of Allocation from Employer/ Owner, the successful bidder shall furnish an unconditional and irrevocable Contract Performance Security as below. The Contract Performance Security shall be in the form of either Banker's Cheque or Demand Draft or Bank Guarantee and shall be in the currency of the Contract and will be issued in the name of the Owner as "Bharat Dynamics Limited, Telangana". The Contract Performance Security against this Contract need to be furnished in 02 (Two) different stages as mentioned below: - 1. First Stage: The value of the Contract Performance Security shall be 10% of the Contract Value (i.e., total sum of the Supply Contract & Service Contract) and will remain valid 90 (Ninety) days beyond half of the prescribed O & M Period, i.e. 2.5 (Two and Half) Years. Henceforth, 10% Contract Performance Security needs to be furnished for the first 2.5 (Two and Half) Years of the O & M period. 2. Second Stage: The value of the Contract Performance Security shall be 5% of the Contract Value (i.e., total sum of the Supply Contract & Service Contract) and will remain valid 90 (Ninety) days beyond the balance O & M Period, i.e. 2.5 (Two and Half). Henceforth, 5% Contract Performance Security needs to be furnished for the last 2.5 (Two and Half) of the O & M period. 3. Contractor needs to furnish the revised Contract Performance Security amounting 5% of the total Contract Value as mentioned above within the validity period of the Contract Performance Security submitted at First Stage. 4. In case the Contractor fails to furnish the Contract Performance Security mentioned under the Second Stage within the indicated time period as mentioned above under point no. 3, Employer/ Owner at their sole discretion will forfeit the Contract Performance Security furnished at First Stage. 5. The Contract Performance Security shall be towards faithful performance of the contractual obligations and performance of equipment. 6. In case of any default or failure of the Contractor to comply with the requirements of any of the Obligations covered under this Tender Document and/ or Contract Agreement shall constitute sufficient grounds for forfeiture of the entire Contract Performance Security. 7. Further, any delay beyond 30 (Thirty) days shall attract interest @ 1.25% per month on the total Contract Performance Security amount, calculated on pro-rata basis accordingly. Employer/

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		Owner at its sole discretion may cancel the Contract Agreement/ NOA/ LOI/ LOA & forfeit 100% of EMD, in case Contract Performance Security is not submitted within 40 (Forty) days from issuance of NOA/ LOI/ LOA. However, total project completion period shall remain same. Part Security shall not be accepted. 8. Rest of the standard Performance Security clauses will prevail as per ITB clause 38 Contract Performance Security submitted shall be released to the Contractor without any interest not later than 75 (Seventy-Five) days after the successful completion of the complete O&M period (5 Years) subject to the approval and acceptance of the O&M period deliverables by the Engineer in charge/Technical Team.
7.	New Clause (Performance Measurement Procedure)	The Plant performance will be evaluated as defined under Section VII, Scope of Work and Technical Specifications, "PERFORMANCE GUARANTEE TEST PROCEDURE"
8.	New Clause (Compensation for PR and CUF deviations)	1. During the Operational Acceptance any shortfall in the Performance Ratio (PR) as determined through the PR Test Procedure specified Section VII, Scope of Work and Technical Specifications, Annexure – B "PERFORMANCE GUARANTEE TEST PROCEDURE", will attract imposition of penalty. For every 0.01 shortfall in PR below 0.78 by the bidder, a penalty of 0.1% of the total Contract Value (i.e., total sum of all the Supply Contract, Service Contract and absolute value of O & M Contract) shall be levied. In case the Plant PR result is 0.05 below 0.78, i.e., 0.73 or lower, the total Contract Performance Security submitted by the bidder will be forfeited. In case the Contract Performance Security has already been encashed on account of delays, the due amount will be recovered from the Final Instalment of the EPC payable at the end of the first year (as per the Terms of Payment specified in SCC) 2. Difference in units derived from committed and achieved CUF x Rs. 6.5; for period after commissioning till the O&M contract closure. The CUF shall be evaluated as per the formula mentioned Section VII, Scope of Work and Technical Specifications. 3. In case the Project fails to generate any power continuously for 1 month any time during the O&M period, apart from the force majeure and grid outages as certified by competent authority from STU/ CTU, it shall be considered as "an event of default". In the case of default the entire Contract Performance Security will be forfeited.

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		4. Penalty during O&M period against breakdown of other Infrastructure of Solar Power Plant which doesn't affect the generation of power, directly such as but not limited to civil infrastructure, water supply system/network, other Infrastructure developed by the Contractor as a Scope of Work for the Project (Section-VII: Scope of Works & Technical Specifications) shall be penalised @ Rs.1000/day, per incident of breakdown reported beyond 48 Hours of such reporting. Cumulative value of such penalty shall be limited to 50% of yearly O&M cost. 5. The Penalty specified on account of delays, as specified in Liquidated Damages and Penalty specified on account of deviations in Functional Guarantees as above shall be assessed independent of each other. Above mentioned Penalties specified under this clause of SCC are independent of each other.
9.	New Clause (Award of Contract)	Owner shall issue separate Orders (NOA/ LOI/ LOA) for different components of the contract i.e., a. First Contract: FOR destination basis Supply including Transportation for delivery at site and Insurance of all Equipments and materials including mandatory spares and any other supplies specified in the Contract Documents. b. Second Contract: For providing all services i.e. including ,unloading, Storage, handling at site, Civil Works, Erection, Installation, Testing and Commissioning including performance testing in respect of all the equipments supplied under the "First Contract" and any other services specified in the Contract Documents Both contracts will contain a cross fall breach clause specifying that breach of one will constitute breach of the other. c. Third Contract: For O & M job covering the entire scope of work for Operation and Maintenance activities
10.	New Clause (Payment Terms)	A. The payment for the First Contract (related to Supply Portion) shall be made as per the following terms and conditions: i) Interest bearing adjustable initial advance (OPTIONAL) of 10% of the Contract Value (i.e., total sum of all the Supply Contract & Service Contract) shall be released to successful bidder upon receipt of unconditional acceptance of NOA/ LOI/ LOA, detailed Performa invoice of contractor and against submission of unconditional & irrevocable Advance Bank Guarantee (ABG) with a validity period up to date of final commissioning total amounting to 110% of total advance amount. The ABG needs to be submitted in addition to the Contract Performance Security. The annual interest rate shall be calculated based on SBI one year MCLR as applicable.

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		ii) Seventy percent (70%) payments shall be paid on Pro rata basis against supply, receipt and acceptance of Materials at site on submission of documents (except Advance Bank Guarantee) indicated under clause i) above, Contractor's detailed invoice & packing list identifying contents of each shipment, evidence of dispatch (GR/ LR copy), Copies of Certificates to the effect of payments of State/ Central Goods and Service Tax etc, Certified copy of Insurance policy/Insurance Certificate, Manufacturer's/ Contractor's Guarantee certificate of Quality, submission of the certificate by the Employer's authorized representative that the item(s) have been received and MDCC (Material Dispatch Clearance Certificate) issued by Employer's authorized representative in original. (a) If Successful Bidder has opted for advance then, Ten percent (10%) (full amount of advance) shall be adjusted while making payments of this installment. Also, up-to-date accrued interest shall also be recovered. (iii) Twenty Five percent (25%) payments shall be paid against successful erection, testing and commissioning of materials at site and Operational Acceptance of the Facility pursuant to successful Guarantee Tests and demonstration of Performance Ratio (PR) including submission of all as-built drawings and documents. (iv) Final Five percent (05%) payment of Supplies shall be paid after CUF demonstration on completion of first year of O&M of the Facility pursuant to submission of all requisite documentation. However, this Payment may also be released after demonstration of PR and submission of all requisite documentation on the submission of Bank Guarantee of equivalent amount. The BG shall be valid up to demonstration of CUF for the successful first year of Operation. However, in case of delay, the BG shall be extended suitably. B. Now, For the Second Contract (related to Services Part), the payment shall be made as detailed below. No Initial Advance Payment shall be made against Second Contract related to Service Part. In accordance with the provisions of clause 94.10 of GCC, it shall be the responsibility of the Contractor to comply with all the statutory requirements of EPFO and ESIC within due time period. It shall be the responsibility of the Contractor to duly deposit all the PF and ESIC contribution to the Authorities, of the manpower deployed by them on the project. These payments shall be released/reimbursed to the Contractor on production of challan stating proof of deposition of amount with the authorities. However, it may be noted that the amount towards EPF and ESIC is not over and above the Contract Value. Contract Value is assumed to be inclusive of all such amounts (PF and ESI contribution of the Employer). Thus, in order to ensure the compliance with these

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		requirements, Owner will release the payment to the Contractor in accordance with the following mechanism:- Amount towards PF and ESI Contribution will be presumed to be included in Service Part of the Contract. Accordingly, respective progressive/stage payments under Service Contract will be released to the Contractor after ensuring/obtaining copies of following documents from the contractor:- 1. Copies of EPF/ESIC Challan 2. Wage Sheet duly certified by the Engineer in Charge/Project Manager/Authorized Signatory of the Employer/Owner 3. Attendance Sheet of the manpower deployed by the Contractor on the Project which will be duly counter certified by Engineer in Charge/Project Manager/Authorized Representative of Employer/Owner. In case the Contractor could not produce the required documents at the time of its claim for any progressive/stage payment under Service Contract, Employer/Owner shall be at liberty to deduct the amount equivalent to the PF/ESIC (for the period for which manpower has been deployed on the project) from that stage payment which will be released to the Contractor later on only on production of required documents. <u>Further, such kind of adjustments may be made by Owner/Employer from either First Portion or the Second Portion of the Service Contract.</u> i) For the First Portion of the Second Contract (i.e. Erection, Testing and Commissioning Portion), the payment shall be made as detailed below: - (a) Eighty Percent (80%) of the total price of Design, Engineering, Erection, Testing and Commissioning shall be paid on pro-rata basis on completion of installation of equipment on certification by the Engineer-In-Charge/ Project Manager for the quantum of work completed after successful clearance of quality check points involved in the quantum of work billed. (b) Fifteen Percent (15%) of the total price of Design, Engineering, Erection, Testing and Commissioning shall be paid on Operational Acceptance of the Facility pursuant to successful integration with existing internal grid system, Guarantee Tests and demonstration of PR. (c) Final Five percent (05%) payments shall be paid after CUF demonstration after first year of O&M of the Facility pursuant to submission of all requisite documentation. However, this Payment may also be released after successful Guarantee Tests and demonstration of PR and submission of all requisite documentation on the submission of Bank Guarantee of equivalent amount. The BG shall be valid up to demonstration of CUF for the successful first year

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		of Operation. However, in case of delay, the BG shall be extended suitably. ii) For the Second Portion of the Second Contract (i.e. Civil & Allied Works), the payment shall be made as detailed below: - (a) Eighty Percent (80%) of the total price of Civil Works shall be paid progressively on certification by the Project Manager/ Engineer In - Charge for the quantum of work completed/ Milestones achieved after successful clearance of quality check points involved in the quantum of work. (b) Fifteen Percent (15%) of the total price of Civil Works shall be paid on completion of all the civil works including finishing and debris removal. (c) Final Five (05%) of the total price of Civil Works shall be paid after CUF demonstration after first year of O&M of the Facility pursuant to completion of all the civil works including finishing and debris removal. However, this Payment may also be released after completion of all the civil works including finishing and debris removal on submission of Bank Guarantee of equivalent amount. The BG shall be valid up to demonstration of CUF for the successful first year of Operation. However, in case of delay, the BG shall be extended suitably. C. For the Third Contract (related to Operation & Maintenance Part), the payment shall be made as detailed below: - (a) Against successful Operation and Maintenance of the Facility on quarterly basis at the end of every quarter for each year till 5 (Five) years. The O&M of the plant will commence from the date of Operational Acceptance/Commercial Operations Date of the facility. (i) Year 1 : OM -1 (ii) Year 2 : OM -2 (iii) Year 3 : OM -3 (iv) Year 4 : OM -4 (v) Year 5 : OM -5 D. All the payment shall be released from Owner's Head Office, Telangana upon submission of Original Documents as mentioned against each Payment Milestones, Joint Commissioning and Handing Over Certificate duly certified by the authorized representative of Employer.
11.	New Clause (Starting of Works)	The date of issue of Notification of Award (NOA) shall be treated as the Zero day for the start of work & there by Contract Timeline. The Contractor shall be required to start the work within 15 (fifteen) days from the date of issue of Notification of Award (NOA) and shall thereof, report to the Project Manager/ Engineer-in-charge

SCC No.	GCC Clause Ref. No. (If Applicable)	Details/ Description/ Special Conditions
		accordingly. During these 15 days following things are to be accomplished; (a) PM/ EIC at its own discretion may call a kick-off meeting, where broader guidelines of EPC shall be discussed. (b) Contractor's representative from Procurement, design, Project Execution team shall participate in this meeting & submit their Plan with respect to EPC works. (c) Contractor shall submit the baseline schedule of Project activities within 15 days from the date of NOA (d) Communication Protocol for Project coordination to be frozen by the PM/EIC, within this timeline Contractor must identify & communicate the details of their nodal persons for Procurement, Design & Execution.
12.	New Clause (Handing Over – Taking Over)	The work shall be taken over by the Owner upon successful completion of all tasks to be performed at Site(s) on equipment supplied, installed, erected and commissioned by the Contractor in accordance with provision of Tender Document. During handing over complete project work, the Contractor shall submit the following for considering final payment: (a) All as- Built Drawings and documents as per the contract coordination procedure set out for the successful completion of the project. (b) Detailed Engineering Document with detailed specification, schematic drawing, circuit drawing, cable routing plans and test results, manuals for all deliverable items, Operation, Maintenance & Safety Instruction Manual and other information about the project. (c) Bill of material. (d) Inventory of recommended and mandatory spares at project Site. (e) Immediately after taking over of complete facilities (s), the same will be handed over to the Contractor for Operation & Maintenance for a period of as mentioned in the bidding document.



SECTION - VI

SAMPLE FORMS & FORMATS

Preamble

This Section (Section - VI) of the Bidding Documents [named as Sample Forms and Procedures (FP)] provides proforma to be used by the bidders at the time of their bid preparation and by the Contractor subsequent to the award of Contract.

The Bidder shall complete, sign and submit with its bid the relevant FORMS to be used unamended, in accordance with the requirements included in the Bidding Documents.

The Bidder shall provide the EMD, in the form included hereafter acceptable to the Employer, pursuant to the provisions in the instructions to Bidders.

The Performance Security (ies) and Bank Guarantee for Advance Payment forms should not be completed by the bidders at the time of their bid preparation. Only the successful Bidder will be required to provide the Performance Security(ies) and Bank Guarantee for Advance Payment, according to one of the forms indicated herein acceptable to the Employer and pursuant to the provisions of the General and Special Conditions of Contract, respectively.

Depending on specific facts and circumstances related to the Bid/ Tender and the contract, the text of the Forms herein may need to be modified to some extent. The Employer reserves the right to make such modifications in conformity with such specific facts and circumstances and rectify and consequent discrepancies, if any. However, modifications, if any, to the text of the Forms that may be required in the opinion of the Bidder/ Contractor shall be effected only if the same is approved by the Employer. The Employer's decision in this regard shall be final and binding.

<u>LIST OF FORMS & FORMAT</u>	
Form No.	Description
F-0	COVERING LETTER
F-1	BIDDER'S GENERAL INFORMATION
F-4	PROFORMA OF "BANK GUARANTEE" FOR "EARNEST MONEY DEPOSIT (EMD)"
F-6	NO DEVIATION CONFIRMATION
F-7	DECLARATION REGARDING BANNING AND LIQUIDATION, COURT RECEIVERSHIP ETC.
F-9	PROFORMA OF "BANK GUARANTEE" FOR "CONTRACT PERFORMANCE SECURITY"
F-13	BIDDER'S EXPERIENCE
F-16	FORMAT OF CHARTERED ACCOUNTANT CERTIFICATE FOR FINANCIAL CAPABILITY OF THE BIDDER
F-17	FORMAT FOR JOINT VENTURE AGREEMENT
F-17A	FORMAT FOR POWER OF ATTORNEY FOR JOINT VENTURE AGREEMENT
F-18	FORMAT FOR CONSORTIUM AGREEMENT
F-18A	FORMAT FOR POWER OF ATTORNEY FOR CONSORTIUM AGREEMENT
F-19	E-BANKING FORMAT
F-20	PROFORMA OF "BANK GUARANTEE" FOR "ADVANCE PAYMENT"
F-22	LIST OF BANKS
F-23	SHAREHOLDING CERTIFICATE
F-24	POWER OF ATTORNEY FOR BIDDING COMPANY

Form F-0

COVERING LETTER

(The Covering Letter should be submitted on the Letter Head of the Bidding Company)

Ref.No. _____

Date: _____

From: _____ (Insert name and address of Bidding Company)

Tel.#: _____

Fax#: _____

E-mail address# _____

To

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Sub: Bid for "Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding"

Dear Sir / Madam,

1. We, the undersigned.... [insert name of the 'Bidder'] having read, examined and understood in detail the tender Document for "Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding" hereby submit our Bid comprising of Techno Commercial Bid and Price Bid. We confirm that neither we nor any of our Parent Company/ Affiliat / Ultimate Parent Company has submitted Bid other than this Bid directly or indirectly in response to the aforesaid tender.
2. We give our unconditional acceptance to the tender, dated..... and tender documents attached thereto, issued by Solar Energy Corporation of India Limited, as amended. As a token of our acceptance to the tender documents, the same have been initialled by us and enclosed to the Bid. We shall ensure that we execute such tender documents as per the provisions of the tender and provisions of such tender documents shall be binding on us.

3. Bid Capacity

We have bid for the capacity of 5 MW (AC).

4. Bid Processing Fees

We have enclosed a Bid Processing Fees of INR..... (Insert Amount), in the form of Demand Draft/ Banker's Cheque no..... (Insert reference of the DD/ Banker's Cheque) dated..... (Insert date of DD/ banker's cheque) from (Insert name of Bank providing DD/ banker's cheque) and valid up to and including in terms of Clause of this tender.

5. Earnest Money Deposit

We have enclosed an Earnest Money Deposit of INR..... (Insert Amount), in the form of bank guarantee no..... (Insert reference of the bank guarantee) dated..... (Insert date of bank guarantee) as per Format F-4 from (Insert name of Bank providing BG) and valid up to and including in terms of Clause of this tender. The offered quantum of power by us is ____ MWp. (Insert total capacity offered).

6. We have submitted our Price Bid strictly as per this tender, without any deviations, conditions and without mentioning any assumptions or notes for the Price Bid in the said format(s).

7. In case we are a Successful Bidder, we shall furnish a declaration at the time of commissioning of the Project to the effect that neither we have availed nor we shall avail in future any Incentive other than received from SECI for implementation of the project.

8. Acceptance

We hereby unconditionally and irrevocably agree and accept that the decision made by Solar Energy Corporation of India Limited in respect of any matter regarding or arising out of the tender shall be binding on us. We hereby expressly waive any and all claims in respect of Bid process.

We confirm that there are no litigations or disputes against us, which materially affect our ability to fulfil our obligations with regard to execution of projects of capacity offered by us.

9. Familiarity with Relevant Indian Laws & Regulations

We confirm that we have studied the provisions of the relevant Indian laws and regulations as required to enable us to submit this Bid and execute the tender documents, in the event of our selection as Successful Bidder. We further undertake and agree that all such factors as mentioned in tender have been fully examined and considered while submitting the Bid.

10. Contact Person

Details of the contact person are furnished as under:

Name :

Designation :

Company :

Address :

Phone Nos. :

Fax Nos. :

E-mail address :

11. We are enclosing herewith the Envelope-I (Covering Letter, Processing Fees, EMD etc through Offline and Online, Techno-Commercial documents through online as per clause no. 11.1 of Section - II, ITB) and Envelope II (Price Bids) (through online) containing duly signed formats, each one duly sealed separately, in one original as desired by you in the tender for your consideration as per clause no. 11.0 of Section - II, ITB.

It is confirmed that our Bid is consistent with all the requirements of submission as stated in the tender and subsequent communications from Solar Energy Corporation of India Limited. The information submitted in our Bid is complete, strictly as per the requirements stipulated in the tender and is correct to the best of our knowledge and understanding. We would be solely responsible for any errors or omissions in our Bid. We confirm that all the terms and conditions of our Bid are valid for acceptance for a period as specified in BDS from the date of opening of "Techno-Commercial/ Un-priced Bid". We confirm that we have not taken any deviation so as to be deemed non-responsive.

Dated the _____ day of _____, 20....

Thanking you,

We remain,

Yours faithfully,

Name, Designation and Signature of Authorized Person in whose name Power of Attorney/ Board Resolution/ Declaration. Copy of Power of Attorney/ Board Resolution/ Declaration should be enclosed along with Covering Letter.

Form F-1

BIDDER'S GENERAL INFORMATION

(To be submitted on the Letter Head of the Bidding Company)

Sr. No.	Description	Remarks
1	Name of the Bidder (Incase of JV/ Consortium, name of all the members to be indicated and lead member to be identified)	
2	Status of the Firm	
3	Mailing Address of Registered Office	
4	Mailing Address of Operation Office	
5	E-mail	
6	Web site	
7	Authorized Contact Person(s) with Name, Designation, Address and Mobile Phone No., E-mail address / Fax No. to whom all references shall be made	
8	Year of Incorporation	
9	Number of Years in Operation	
10	ISO Certification Yes/No	
11	Name of the Banker	
12	Branch Details of Bank	
13	Type of Account with Account Number	
14	IFSC Code	
15	Permanent Account Number (PAN) of the Bidder	(Copy of PAN Card to be enclosed)
16	Whether the Vendor is registered/ Likely to be registered under GST	Yes or No : If Yes, then customer will be treated as registered customer & he will have to provide further

		details as stated on the below left hand side
17	GST ID (Proof to be submitted – GST No acknowledgement OR Email from GoI)	
18	GSTN Address	

Sr. No.	Description	Remarks
19	PF Registration Number with Details	(Copy of Registration to be enclosed)
20	ESI Registration Number with Details	(Copy of Registration to be enclosed)
21	Have the Bidder/ Company ever been debarred by any Govt. Dept./ Undertaking for undertaking any work	Yes/No (If answer is YES, please provide details)
22	Reference of any document information attached by the Bidder other than specified in the tender.	
23	Whether the Bidder wishes to form a Project Company for execution of work	Yes/No
24	Bidding company is listed in India	Yes/No
25	Whether company is MSME as on the bidding date	Yes/No

(Signature of Authorized Signatory)

With Stamp

Form F-4

**PROFORMA OF BANK GUARANTEE FOR EARNEST
MONEY DEPOSIT (EMD)**

(To be on non-judicial stamp paper of appropriate value as per Stamp Act relevant to place of execution.)

Ref. _____

Bank Guarantee No. _____

Date: _____

In consideration of the -----[Insert name of the Bidder] (hereinafter referred to as 'Bidder') submitting the response to NIT inter alia for selection of the Project in response to the NIT No. _____ dated _____ issued by Solar Energy Corporation of India Limited (hereinafter referred to as SECI) and SECI considering such response to the NIT of[insert the name of the Bidder] as per the terms of the NIT, the _____ [insert name & address of bank] hereby agrees unequivocally, irrevocably and unconditionally to pay to SECI at [Insert Name of the Place from the address of SECI] forthwith on demand in writing from SECI or any Officer authorized by it in this behalf, any amount upto and not exceeding Rupees -----[Insert amount] only, on behalf of M/s. _____ [Insert name of the Bidder] .

This guarantee shall be valid and binding on this Bank up to and including _____ [insert date of validity in accordance with NIT] and shall not be terminable by notice or any change in the constitution of the Bank or the term of contract or by any other reasons whatsoever and our liability hereunder shall not be impaired or discharged by any extension of time or variations or alternations made, given, or agreed with or without our knowledge or consent, by or between parties to the respective agreement.

Our liability under this Guarantee is restricted to Rs. _____ (Rs. _____ only). Our Guarantee shall remain in force until _____ [insert date of validity in accordance with NIT]. SECI shall be entitled to invoke this Guarantee till _____ [Insert date which is 30 days after the date in the preceding sentence].

The Guarantor Bank hereby agrees and acknowledges that the SECI shall have a right to invoke this BANK GUARANTEE in part or in full, as it may deem fit.

The Guarantor Bank hereby expressly agrees that it shall not require any proof in addition to the written demand by SECI, made in any format, raised at the above-mentioned address of the Guarantor Bank, in order to make the said payment to SECI.

The Guarantor Bank shall make payment hereunder on first demand without restriction or conditions and notwithstanding any objection by ----- [Insert name of the Bidder] and/or any other person.

The Guarantor Bank shall not require SECI to justify the invocation of this BANK GUARANTEE, nor shall the Guarantor Bank have any recourse against SECI in respect of any payment made hereunder.

This BANK GUARANTEE shall be interpreted in accordance with the laws of India and the courts at Delhi shall have exclusive jurisdiction.

The Guarantor Bank represents that this BANK GUARANTEE has been established in such form and with such content that it is fully enforceable in accordance with its terms as against the Guarantor Bank in the manner provided herein.

This BANK GUARANTEE shall not be affected in any manner by reason of merger, amalgamation, restructuring or any other change in the constitution of the Guarantor Bank.

This BANK GUARANTEE shall be a primary obligation of the Guarantor Bank and accordingly SECI shall not be obliged before enforcing this BANK GUARANTEE to take any action in any court or arbitral proceedings against the Bidder, to make any claim against or any demand on the Bidder or to give any notice to the Bidder or to enforce any security held by SECI or to exercise, levy or enforce any distress, diligence or other process against the Bidder.

Notwithstanding anything contained hereinabove, our liability under this Guarantee is restricted to Rs. _____ (Rs. _____ only) and it shall remain in force until _____ [Date to be inserted on the basis of this NIT] with an additional claim period of thirty (30) days thereafter. We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only if SECI serves upon us a written claim or demand.

Signature _____

Name _____

Power of Attorney No. _____

For

_____ [Insert Name of the Bank] _____

Banker's Stamp and Full Address.

Dated this ____ day of ____, 20__

Bank Contact Details & E Mail ID is to be provided

Form F-6

NO DEVIATION CONFIRMATION
(To be submitted on the Letter Head of the Bidding Company)

Ref.No. _____

Date: _____

From: _____ (Insert name and address of Bidding Company)

Tel.#: _____

Fax#: _____

E-mail address# _____

To

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Sub: Bid for “Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding.

Dear Sir / Madam,

We understand that any 'deviation/ exception' in any form may result in rejection of bid. We, therefore, certify that we have not taken any 'exception/ deviation' anywhere in the bid and we agree that if any 'deviation/ exception' is mentioned or noticed, our bid may be rejected.

Place:

Date:

[Signature of Authorized Signatory of Bidder]

Name:

Designation:

Seal:

Form F-7

**DECLARATION REGARDING BANNING, LIQUIDATION,
COURT RECEIVERSHIP ETC.**

(To be submitted on the Letter Head of the Bidding Company)

Ref.No. _____

Date: _____

From: _____ (Insert name and address of Bidding Company)

Tel. #:

Fax #:

E-mail address#

To

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Sub: Bid for “Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding”.

Dear Sir / Madam,

We hereby confirm that we are not on Banning List by Employer/ Owner or Public Sector Project Management Consultant due to “poor performance” or “corrupt and fraudulent practices” or any other reason or banned by Government department/ Public Sector on due date of submission of bid.

Further, we confirm that neither we nor our allied agency/(ies) (as defined in the Procedure for Action in case of Corrupt/ Fraudulent/ Collusive/ Coercive Practices) are on banning list of Employer/ Owner or the Ministry of New & Renewable Energy.

We also confirm that we are not under any liquidation, court receivership or similar proceedings or ‘bankruptcy’.

In case it comes to the notice of Employer/ Owner that we have given wrong declaration in this regard, the same shall be dealt as ‘fraudulent practices’ and action shall be initiated as per the Procedure for action in case of Corrupt/Fraudulent/Collusive/Coercive Practices.

Further, we also confirm that in case there is any change in status of the declaration prior to award of contract, the same will be promptly informed to Employer/ Owner by us.

Place:

[Signature of Authorized Signatory of Bidder]

Date:

Name:

**5 MW (AC) Solar PV Power
Plant Project**

**Tender No
SECI/C&P/NIT/2017/BDL5MW-2**

**SAMPLE
FORMS
Page 12 of 40**

Signature of Bidder

Designation:
Seal:

Form F-9

PROFORMA OF BANK GUARANTEE FOR CONTRACT PERFORMANCE SECURITY

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the issuing Bank)*

Bank Guarantee No.:
Date:

NOA/ Contract No.....

..... *[Name of Contract]*

To:

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Dear Sir / Madam,

We refer to the Contract ("the Contract")

signed on*(insert date of the Contract)* between you and M/s *(Name of Contractor)*
.....,

(or)

vide notification of award issued on *(insert date of the notification of award)* by you to M/s
..... *(Name of Contractor)* having its Principal place of business at *(Address of Contractor)* and Registered Office at *(Registered address of Contractor)*
..... ("the Contractor") concerning
(Indicate brief scope of work) for the complete execution of the *(insert name of Package alongwith name of the Project)*

By this Bank Guarantee, we, the undersigned, ... *(insert name & address of the issuing bank)*,
a Bank (which expression shall include its successors, administrators, executors and assigns) organized
under the laws of and having its Registered/Head Office at *(insert address of registered office of the bank)* do hereby irrevocably guarantee payment to you up to
..... i.e., ten percent (10%) of the Contract Price until ninety (90) days beyond the Defect
Liability Period i.e., upto and inclusive of *(dd/mm/yy)*.

We undertake to make payment under this Bank Guarantee upon receipt by us of your first written demand
signed by your duly authorized officer or authorized officer of the Owner declaring the Contractor to be in

default under the Contract and without cavil or argument any sum or sums within the above-named limits, without your need to prove or show grounds or reasons for your demand and without the right of the Contractor to dispute or question such demand.

Our liability under this Bank Guarantee shall be to pay to you whichever is the lesser of the sum so requested or the amount then guaranteed hereunder in respect of any demand duly made hereunder prior to expiry of the Bank Guarantee, without being entitled to inquire whether or not this payment is lawfully demanded.

This Bank Guarantee shall remain in full force and shall be valid from the date of issuance until ninety (90) days beyond the Defect Liability Period of the Facilities i.e. upto and inclusive of (dd/mm/yy) and shall be extended from time to time for such period (not exceeding one year), as may be desired by M/s Solar Energy Corporation of India Limited on whose behalf this Bank Guarantee has been given.

Except for the documents herein specified, no other documents or other action shall be required, notwithstanding any applicable law or regulation.

Our liability under this Bank Guarantee shall become null and void immediately upon its expiry, whether it is returned or not, and no claim may be made hereunder after such expiry or after the aggregate of the sums paid by us to you shall equal the sums guaranteed hereunder, whichever is the earlier.

All notices to be given under shall be given by registered (airmail) posts to the addressee at the address herein set out or as otherwise advised by and between the parties hereto.

We hereby agree that any part of the Contract may be amended, renewed, extended, modified, compromised, released or discharged by mutual agreement between you and the Contractor, and this security may be exchanged or surrendered without in any way impairing or affecting our liabilities hereunder without notices to us and without the necessity for any additional endorsement, consent or guarantee by us, provided, however, that the sum guaranteed shall not be increased or decreased.

No action, event or condition which by any applicable law should operate to discharge us from liability hereunder shall have any effect and we hereby waive any right we may have to apply such law so that in all respects our liability hereunder shall be irrevocable and, except as stated herein, unconditional in all respects.

Notwithstanding anything contained herein:

1. Our liability under this Bank Guarantee shall not exceed _____ (value in figures) _____
[_____ (value in words) _____].
2. This Bank Guarantee shall be valid upto _____ (validity date) _____.
3. We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only & only if we receive a written claim or demand on or before _____ (validity date) _____."

For and on behalf of the Bank

[Signature of the authorised signatory(ies)]

Signature _____

Name _____

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE</u> <u>FORMS</u> <u>Page 14 of 40</u>	<u>Signature of Bidder</u>

Designation_____

POA Number_____

Contact Number(s): Tel._____ Mobile_____

Fax Number_____

email _____

Common Seal of the Bank_____

Witness:

Signature_____

Name_____

Address_____

Contact Number(s): Tel._____ Mobile_____

email _____

Note :

1. For the purpose of executing the Bank Guarantee, the non-judicial stamp papers of appropriate value shall be purchased in the name of Bank who issues the 'Bank Guarantee'.
2. The Bank Guarantee shall be signed on all the pages by the Bank Authorities indicating their POA nos. and should invariably be witnessed.
3. The Bank Guarantee should be in accordance with the proforma as provided. However, in case the issuing bank insists for additional paragraph regarding applicability of ICC publication No: 758, the following may be added at the end of the proforma of the Bank Guarantee [*i.e., end paragraph of the Bank Guarantee preceding the signature(s) of the issuing authority(ies) of the Bank Guarantee*]:

"This Guarantee is subject to Uniform Rules for Demand Guarantee, ICC publication No. 758 except that article 15(a) is hereby excluded."



Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of
5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years
Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding



5 MW (AC) Solar PV Power
Plant Project

Tender No
SECI/C&P/NIT/2017/BDL5MW-2

SAMPLE
FORMS
Page 16 of 40

Signature of Bidder

Form F-13

BIDDER'S EXPERIENCE

(To be submitted on the Letter Head of the Bidding Company)

Ref.No. _____

Date: _____

From: _____ (Insert name and address of Bidding Company)

Tel.#: _____

Fax#: _____

E-mail address# _____

To

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Sub: Bid for "Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding".

Dear Sir / Madam,

Sl. No	Description of the Services	LOA /WO No. and date	Full Address & phone nos. of Client. Name, designation and address of Engineer/ Officer-in-Charge (for cases other than purchase)	Postal & phone nos. of Client.	Value of Contract/ Order (Specify Currency Amount)	Date of Commencement of Services	Scheduled Completion Time (Months)	Date of Actual Completion	Reasons for delay in execution, if any
(1)	(2)	(3)	(5)	(6)	(7)	(8)	(9)	(10)	

Place:

Date:

[Signature of Authorized Signatory of Bidder]

Name:

Designation:

Seal

Form F-16

FORMAT OF CHARTERED ACCOUNTANT CERTIFICATE
FOR FINANCIAL CAPABILITY OF THE BIDDER
(To be submitted on the Letter Head of the Chartered Accountant)

Ref.No. _____

Date: _____

To

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Sub: Bid for “Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding”.

Dear Sir / Madam,

We have verified the Annual Accounts and other relevant records of M/s..... (Name of the bidder) and certify the following

Further, we certify that the Financially Evaluated Entity (ies) had an Annual Turnover

A. ANNUAL TURNOVER OF LAST 3 YEARS:

Year	Amount (Currency)
Year 1:	
Year 2:	
Year 3:	

And

Net worth (strike out whichever is not applicable) of INR.....Crore computed as per instructions provided in this tender based on unconsolidated audited annual accounts as per last FY.

B. FINANCIAL DATA FOR LAST AUDITED FINANCIAL YEAR:

Description	Year _____
	Amount (Currency)
1. Current Assets	
2. Current Liabilities	
3. Working Capital (Current Assets- Current liabilities)	
4. Net Worth (As mentioned under Annexure to BDS)	

Yours faithfully

(Signature and stamp (on each page) of Authorized Signatory of Bidding Company.

Name:

Date:

Place:

Signature and stamp (on each page) of Chartered Accountant/Statutory Auditors of Bidding Company.

Name:

Date:

Place:

Notes:

Audited consolidated annual accounts of the Bidder may also be used for the purpose of financial criteria provided the Bidder has at least 26% equity in each company whose accounts are merged in the audited consolidated accounts and provided further that the financial capability of such companies (of which accounts are being merged in the consolidated accounts) shall not be considered again for the purpose of evaluation of the Bid.

Form F-17

FORMAT FOR JOINT VENTURE AGREEMENT

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the Joint Venture)*

THIS JOINT DEED OF UNDERTAKING executed on this..... day of..... Two Thousand and..... by a company incorporated under the laws of and having its Registered Office at(hereinafter called the "Party No.1" which expression shall include its successors, executors and permitted assigns) and M/s.....a company incorporated under the laws of and having its Registered Office at (hereinafter called the "Party No.2" which expression shall include its successors, executors and permitted assigns) and M/s..... a Company incorporated under the laws of and having its Registered Office at (hereinafter called the "Party No.3" which expression shall include its successors, executors and permitted assigns) for the purpose of making a bid and entering into a contract [hereinafter called the "Contract" {in case of award}] against the Tender No..... for *(insert name of the package alongwith project name)* of Solar Energy Corporation of India Limited, a Company incorporated under the Companies Act of 2013 having its registered office at D-3, 1st Floor, Wing-A, Prius Platinum Building, District Centre, Saket, New Delhi-110017 (hereinafter called the "Employer").

WHEREAS the Party No.1, Party No.2 and Party No.3 have entered into an Agreement dated.....

AND WHEREAS the Employer invited bids as per the above-mentioned Specification for the design, manufacture, supply, erection, testing and commissioning including O & M of Equipment/ Materials stipulated in the Tender Documents under *(insert name of the package alongwith project name)*

AND WHEREAS Clause 2, Section-ITB and BDS (documents establishing the Qualification of Bidder) & Qualification Criteria in Annexure to BDS forming part of the Tender Documents, inter-alia stipulates that an Undertaking of two or more qualified manufacturers as partners, meeting the requirements of Qualification Criteria in Annexure to BDS, as applicable may bid, provided, the Joint Venture fulfills all other requirements under Qualification Criteria in Annexure to BDS and in such a case, the Bid Forms shall be signed by all the partners so as to legally bind all the Partners of the Joint Venture, who will be jointly and severally liable to perform the Contract and all obligations hereunder.

The above clause further states that this Undertaking shall be attached to the bid and the Contract Performance Security will be as per the format F-9 enclosed with the Tender Documents without any restrictions or liability for either party.

AND WHEREAS the bid is being submitted to the Employer vide proposal No..... dated by Party No.1 based on this Undertaking between all the parties; under these presents and the bid in accordance with the requirements of Clause 2, Section-ITB and BDS (documents establishing the Qualification of Bidder) & Qualification Criteria in Annexure to BDS, has been signed by all the parties.

NOW THIS UNDERTAKING WITNESSETH AS UNDER:

In consideration of the above premises and agreements all the parties of this Deed of Undertaking do hereby declare and undertake:

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE FORMS</u> Page 20 of 40	<u>Signature of Bidder</u>

1. In requirement of the award of the Contract by the Employer to the Joint Venture Partners, we, the Parties do hereby undertake that M/s..... the Party No.1, shall act as Lead Partner and further declare and confirm that we the parties to the Joint Venture shall jointly and severally be bound unto the Employer for the successful performance of the Contract and shall be fully responsible for the design, manufacture, supply and successful performance of the equipment in accordance with the Contract:
2. In case of any breach or default of the said Contract by any of the parties to the Joint Venture, the party(ies) do hereby undertake to be fully responsible for the successful performance of the Contract and to carry out all the obligations and responsibilities under the Contract in accordance with the requirements of the Contract.
3. Further, if the Employer suffers any loss or damage on account of any breach in the Contract or any shortfall in the performance of the equipment in meeting the performances guaranteed as per the specification in terms of the Contract, the Party(ies) of these presents undertake to promptly make good such loss or damages caused to the Employer, on its demand without any demur. It shall not be necessary or obligatory for the Employer to proceed against Lead Partner to these presents before proceeding against or dealing with the other Party(ies), the Employer can proceed against any of the parties who shall be jointly and severally liable for the performance and all other liabilities/ obligations under the Contract to the Employer.
4. The financial liability of the Parties of this Deed of Undertaking to the Employer, with respect to any of the claims rising out of the performance or non-performance of the obligations set forth in this Deed of Undertaking, read in conjunction with the relevant conditions of the Contract shall, however not be limited in any way so as to restrict or limit the liabilities or obligations of any of the Parties of this Deed of Undertaking.
5. It is expressly understood and agreed between the Parties to this Undertaking that the responsibilities and obligations of each of the Parties shall be as delineated in Appendix - I (*to be suitably appended by the Parties alongwith this Undertaking in its bid*) to this Deed of Undertaking. It is further undertaken by the parties that the above sharing of responsibilities and obligations shall not in any way be a limitation of joint and several responsibilities of the Parties under the Contract.
6. It is also understood that this Undertaking is provided for the purposes of undertaking joint and several liabilities of the partners to the Joint Venture for submission of the bid and performance of the Contract and that this Undertaking shall not be deemed to give rise to any additional liabilities or obligations, in any manner or any law, on any of the Parties to this Undertaking or on the Joint Venture, other than the express provisions of the Contract.
7. This Undertaking shall be construed and interpreted in accordance with the provisions of the Contract.
8. In case of an award of a Contract, we the parties to this Deed of Undertaking do hereby agree that we shall be jointly and severally responsible for furnishing a Contract Performance Security from a bank in favour of the Employer in the currency/ currencies of the Contract.
9. It is further agreed that this Deed of Undertaking shall be irrevocable and shall form an integral part of the bid and shall continue to be enforceable till the Employer discharges the same or upon the completion of the Contract in accordance with its provisions, whichever is earlier. It shall be effective from the date first mentioned above for all purposes and intents.

IN WITNESS, WHEREOF, the Parties to this Deed of Undertaking have through their authorised representatives executed these presents and affixed Common Seals of their companies, on the day, month and year first mentioned above.

Common Seal of
has been affixed in my/ our
presence pursuant to Board of
Director's Resolution dated

For Lead Partner (Party No.-1)
For and on behalf of M/s
.....

Name

Designation

Signature

(Signature of the authorized
representative)

WITNESS :

I.

II.

Common Seal of
has been affixed in my/our
presence pursuant to Board of
Director's Resolution dated

For Party No.-2
For and on behalf of
M/s.....

Name

Designation

Signature

(Signature of the authorized
representative)

WITNESS :

I.

II.

Common Seal of
has been affixed in my/ our
presence pursuant to Board of
Director's Resolution dated

For Party No.-3
For and on behalf of M/s.
.....

Name

Designation

Signature

(Signature of the authorized
representative)

WITNESS :

I.

II.

Note:

1. For the purpose of executing the Joint Deed of Undertaking, the non-judicial stamp papers of appropriate value shall be purchased in the name of Joint Venture.
2. The Undertaking shall be signed on all the pages by the authorised representatives of each of the partners and should invariably be witnessed.

Form F-17A

**FORMAT FOR POWER OF ATTORNEY FOR JOINT
VENTURE AGREEMENT**

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the Joint Venture)*

KNOW ALL MEN BY THESE PRESENTS THAT WE, the Partners whose details are given hereunder have formed a Joint Venture under the laws of and having our Registered Office(s)/ Head Office(s) at (hereinafter called the 'Joint Venture' which expression shall unless repugnant to the context or meaning thereof, include its successors, administrators and assigns) acting through M/s being the Partner in-charge do hereby constitute, nominate and appoint M/s..... a Company incorporated under the laws of and having its Registered/ Head Office at as our duly constituted lawful Attorney (hereinafter called "Attorney" or "Authorised Representative" or "Partner In-charge") to exercise all or any of the powers for and on behalf of the Joint Venture in regard to Tender No..... Package the bids for which have been invited by Solar Energy Corporation of India Limited, D-3, 1st Floor, Wing-A, Prius Platinum Building, District Centre, Saket, New Delhi-110017 (hereinafter called the 'Employer') to undertake the following acts:

- i) To submit proposal and participate in the aforesaid Bid Specification of the Employer on behalf of the "Joint Venture".
- ii) To negotiate with the Employer the terms and conditions for award of the Contract pursuant to the aforesaid Bid and to sign the Contract with the Employer for and on behalf of the "Joint Venture".
- iii) To do any other act or submit any document related to the above.
- iv) To receive, accept and execute the Contract for and on behalf of the "Joint Venture".

It is clearly understood that the Partner In-charge (Lead Partner) shall ensure performance of the Contract(s) and if one or more Partner fail to perform their respective portions of the Contract(s), the same shall be deemed to be a default by all the Partners.

It is expressly understood that this Power of Attorney shall remain valid binding and irrevocable till completion of the Defect Liability Period in terms of the Contract.

The Joint Venture hereby agrees and undertakes to ratify and confirm all the whatsoever the said Attorney/ Authorised Representatives/ Partner in-charge quotes in the bid, negotiates and signs the Contract with the Employer and/or proposes to act on behalf of the Joint Venture by virtue of this Power of Attorney and the same shall bind the Joint Venture as if done by itself.

IN WITNESS, THEREOF the Partners Constituting the Joint Venture as aforesaid have executed these presents on this day of under the Common Seal(s) of their Companies.

for and on behalf of the
Partners of Joint Venture

**5 MW (AC) Solar PV Power
Plant Project**

**Tender No
SECI/C&P/NIT/2017/BDL5MW-2**

**SAMPLE
FORMS
Page 24 of 40**

Signature of Bidder

.....
.....
.....

The Common Seal of the above Partners of the Joint Venture:

The Common Seal has been affixed there unto in the presence of:

WITNESS

1. Signature.....
Name
Designation
Occupation
2. Signature.....
Name
Designation
Occupation

Note:

1. For the purpose of executing the Agreement, the non-judicial stamp papers of appropriate value shall be purchased in the name of Joint Venture.
2. The Agreement shall be signed on all the pages by the authorised representatives of each of the partners and should invariably be witnessed.

Form F-18

FORMAT FOR CONSORTIUM AGREEMENT

(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the Consortium)

THIS JOINT DEED OF UNDERTAKING executed on this..... day of..... Two Thousand and..... by a company incorporated under the laws of and having its Registered Office at(hereinafter called the "Party No.1" which expression shall include its successors, executors and permitted assigns) and M/s.....a company incorporated under the laws of and having its Registered Office at (hereinafter called the "Party No.2" which expression shall include its successors, executors and permitted assigns) and M/s.....a Company incorporated under the laws of and having its Registered Office at (hereinafter called the "Party No.3" which expression shall include its successors, executors and permitted assigns) for the purpose of making a bid and entering into a contract [hereinafter called the "Contract" {in case of award}] against the Tender No..... for (insert name of the package alongwith project name) of Solar Energy Corporation of India Limited, a Company incorporated under the Companies Act of 2013 having its registered office at D-3, 1st Floor, Wing-A, Prius Platinum Building, District Centre, Saket, New Delhi-110017 (hereinafter called the "Employer").

WHEREAS the Party No.1, Party No.2 and Party No.3 have entered into an Agreement dated.....

AND WHEREAS the Employer invited bids as per the above-mentioned Specification for the design, manufacture, supply, erection, testing and commissioning including O & M of Equipment/ Materials stipulated in the Tender Documents under (insert name of the package alongwith project name)

AND WHEREAS Clause 2, Section-ITB and BDS (documents establishing the Qualification of Bidder) & Qualification Criteria in Annexure to BDS forming part of the Tender Documents, inter-alia stipulates that an Undertaking of two or more qualified manufacturers as partners, meeting the requirements of Qualification Criteria in Annexure to BDS, as applicable may bid, provided, the Consortium fulfills all other requirements under Qualification Criteria in Annexure to BDS and in such a case, the Bid Forms shall be signed by all the partners so as to legally bind all the Partners of the Consortium, who will be jointly and severally liable to perform the Contract and all obligations hereunder.

The above clause further states that this Undertaking shall be attached to the bid and the Contract Performance Security will be as per the format F-9 enclosed with the Tender Documents without any restrictions or liability for either party.

AND WHEREAS the bid is being submitted to the Employer vide proposal No..... dated by Party No.1 based on this Undertaking between all the parties; under these presents and the bid in accordance with the requirements of Clause 2, Section-ITB and BDS (documents establishing the Qualification of Bidder) & Qualification Criteria in Annexure to BDS, has been signed by all the parties.

NOW THIS UNDERTAKING WITNESSETH AS UNDER:

In consideration of the above premises and agreements all the parties of this Deed of Undertaking do hereby declare and undertake:

1. In requirement of the award of the Contract by the Employer to the Consortium Partners, we, the Parties do hereby undertake that M/s..... the Party No.1, shall act as Lead Partner and further

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE FORMS</u> Page 26 of 40	<u>Signature of Bidder</u>

declare and confirm that we the parties to the Consortium shall jointly and severally be bound unto the Employer for the successful performance of the Contract and shall be fully responsible for the design, manufacture, supply and successful performance of the equipment in accordance with the Contract:

2. In case of any breach or default of the said Contract by any of the parties to the Consortium, the party(ies) do hereby undertake to be fully responsible for the successful performance of the Contract and to carry out all the obligations and responsibilities under the Contract in accordance with the requirements of the Contract.
3. Further, if the Employer suffers any loss or damage on account of any breach in the Contract or any shortfall in the performance of the equipment in meeting the performances guaranteed as per the specification in terms of the Contract, the Party(ies) of these presents undertake to promptly make good such loss or damages caused to the Employer, on its demand without any demur. It shall not be necessary or obligatory for the Employer to proceed against Lead Partner to these presents before proceeding against or dealing with the other Party(ies), the Employer can proceed against any of the parties who shall be jointly and severally liable for the performance and all other liabilities/ obligations under the Contract to the Employer.
4. The financial liability of the Parties of this Deed of Undertaking to the Employer, with respect to any of the claims rising out of the performance or non-performance of the obligations set forth in this Deed of Undertaking, read in conjunction with the relevant conditions of the Contract shall, however not be limited in any way so as to restrict or limit the liabilities or obligations of any of the Parties of this Deed of Undertaking.
5. It is expressly understood and agreed between the Parties to this Undertaking that the responsibilities and obligations of each of the Parties shall be as delineated in Appendix - I (*to be suitably appended by the Parties alongwith this Undertaking in its bid*) to this Deed of Undertaking. It is further undertaken by the parties that the above sharing of responsibilities and obligations shall not in any way be a limitation of joint and several responsibilities of the Parties under the Contract.
6. It is also understood that this Undertaking is provided for the purposes of undertaking joint and several liabilities of the partners to the Consortium for submission of the bid and performance of the Contract and that this Undertaking shall not be deemed to give rise to any additional liabilities or obligations, in any manner or any law, on any of the Parties to this Undertaking or on the Consortium, other than the express provisions of the Contract.
7. This Undertaking shall be construed and interpreted in accordance with the provisions of the Contract.
8. In case of an award of a Contract, we the parties to this Deed of Undertaking do hereby agree that we shall be jointly and severally responsible for furnishing a Contract Performance Security from a bank in favour of the Employer in the currency/ currencies of the Contract.
9. It is further agreed that this Deed of Undertaking shall be irrevocable and shall form an integral part of the bid and shall continue to be enforceable till the Employer discharges the same or upon the completion of the Contract in accordance with its provisions, whichever is earlier. It shall be effective from the date first mentioned above for all purposes and intents.

IN WITNESS, WHEREOF, the Parties to this Deed of Undertaking have through their authorized representatives executed these presents and affixed Common Seals of their companies, on the day, month and year first mentioned above.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE FORMS</u> Page 27 of 40	<u>Signature of Bidder</u>

Common Seal of
has been affixed in my/ our
presence pursuant to Board of
Director's Resolution dated

For Lead Partner (Party No.-1)
For and on behalf of M/s
.....

Name

Designation

Signature

(Signature of the authorized
representative)

WITNESS :

I.

II.

Common Seal of
has been affixed in my/our
presence pursuant to Board of
Director's Resolution dated

For Party No.-2
For and on behalf of
M/s.....

Name

(Signature of the authorized
representative)

Designation

Signature

WITNESS :

I.

II.

Common Seal of
has been affixed in my/ our
presence pursuant to Board of
Director's Resolution dated

For Party No.-3
For and on behalf of M/s.
.....

Name

Designation

Signature

(Signature of the authorized
representative)

WITNESS :

I.

II.

Note:

1. For the purpose of executing the Joint Deed of Undertaking, the non-judicial stamp papers of appropriate value shall be purchased in the name of Consortium.
2. The Undertaking shall be signed on all the pages by the authorized representatives of each of the partners and should invariably be witnessed.

Form F-18A

FORMAT FOR POWER OF ATTORNEY OF CONSORTIUM AGREEMENT

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the Consortium)*

KNOW ALL MEN BY THESE PRESENTS THAT WE, the Partners whose details are given hereunder
..... have formed a Consortium under the laws of
..... and having our Registered Office(s)/ Head Office(s) at
..... (hereinafter called the 'Consortium' which expression shall unless repugnant
to the context or meaning thereof, include its successors, administrators and assigns) acting through M/s
..... being the Partner in-charge do hereby constitute,
nominate and appoint M/s..... a Company incorporated under the laws of
..... and having its Registered/ Head Office at
..... as our duly constituted lawful Attorney (hereinafter called "Attorney" or
"Authorised Representative" or "Partner In-charge") to exercise all or any of the powers for and on behalf of
the Consortium in regard to Tender No..... Package the bids for which have
been invited by Solar Energy Corporation of India Limited, D-3, 1st Floor, Wing-A, Prius Platinum Building,
District Centre, Saket, New Delhi-110017 (hereinafter called the 'Employer') to undertake the following acts:

- i) To submit proposal and participate in the aforesaid Bid Specification of the Employer on behalf of the "Consortium".
- ii) To negotiate with the Employer the terms and conditions for award of the Contract pursuant to the aforesaid Bid and to sign the Contract with the Employer for and on behalf of the "Consortium".
- iii) To do any other act or submit any document related to the above.
- iv) To receive, accept and execute the Contract for and on behalf of the "Consortium".

It is clearly understood that the Partner In-charge (Lead Partner) shall ensure performance of the Contract(s) and if one or more Partner fail to perform their respective portions of the Contract(s), the same shall be deemed to be a default by all the Partners.

It is expressly understood that this Power of Attorney shall remain valid binding and irrevocable till completion of the Defect Liability Period in terms of the Contract.

The Consortium hereby agrees and undertakes to ratify and confirm all the whatsoever the said Attorney/ Authorized Representatives/ Partner in-charge quotes in the bid, negotiates and signs the Contract with the Employer and/or proposes to act on behalf of the Consortium by virtue of this Power of Attorney and the same shall bind the Consortium as if done by itself.

IN WITNESS, THEREOF the Partners Constituting the Consortium as aforesaid have executed these presents on this day of under the Common Seal(s) of their Companies.

for and on behalf of the
Partners of Consortium

.....

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE FORMS</u> Page 30 of 40	<u>Signature of Bidder</u>

.....
.....

The Common Seal of the above Partners of the Consortium:

The Common Seal has been affixed there unto in the presence of:

WITNESS

1. Signature.....
Name
Designation
Occupation
2. Signature.....
Name
Designation
Occupation

Note:

1. For the purpose of executing the Agreement, the non-judicial stamp papers of appropriate value shall be purchased in the name of Consortium.
2. The Agreement shall be signed on all the pages by the authorized representatives of each of the partners and should invariably be witnessed.

Form F-19

e-BANKING FORMAT

(To be submitted on the Letter Head of the Bidder)

1. Bidder/ Customer Name :
2. Bidder/ Customer Code :
3. Bidder/ Customer Address :
4. Bidder/ Customer E-mail ID :
5. Particulars of Bank Account
 - a) Name of Bank :
 - b) Name of Branch :
 - c) Branch Code :
 - d) Address :
 - e) Telephone Number :
 - f) Type of Account :
 - g) Account Number :
 - h) RTGS IFSC Code :
 - i) NEFT IFSC Code :
 - j) 9 digit MICR code :

I/ We hereby authorize Solar Energy Corporation of India Limited to release any amount due to me/ us in the bank account as mentioned above. I/ We hereby declare that the particulars given above are correct and complete. If the transaction is delayed or lost because of incomplete or incorrect information, we would not hold the Solar Energy Corporation of India Limited responsible.

(Signature of Vendor/ Customer)

BANK CERTIFICATE

We certify that ----- has an Account no. ----- with us and we confirm that the details given above are correct as per our records.

Bank stamp

Date

(Signature of authorized officer of bank)

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SAMPLE FORMS</u> Page 32 of 40	<u>Signature of Bidder</u>

Form F-20

**PROFORMA OF BANK GUARANTEE FOR ADVANCE
PAYMENT**

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the issuing Bank)*

Bank Guarantee No.:
Date:

NOA/ Contract No.....

..... *[Name of Contract]*

To:

Solar Energy Corporation of India Limited
(A Government of India Enterprise)
D - 3, 1st Floor, Wing - A, Prius Platinum Building
District Centre, Saket, New Delhi - 110 017

Dear Sir / Madam,

We refer to the Contract ("the Contract") signed on*(insert date of the Contract)* between you
and M/s *(Name of Contractor)*,

(or)

vide notification of award issued on *(insert date of the notification of award)* by you to M/s
..... *(Name of Contractor)* having its Principal place of business at *(Address of
Contractor)* and Registered Office at *(Registered address of Contractor)*
..... ("the Contractor") concerning
(Indicate brief scope of work) for the complete execution of the *(insert name of
Package alongwith name of the Project)*

Whereas, in accordance with the terms of the said Contract, the Employer has agreed to pay or cause to
be paid to the Contractor an interest bearing Advance Payment against furnishing of an irrevocable bank
guarantee for an amount of *(Amount in figures and words)* which is equal
to 110% of the amount of Advance Payment.

By this letter, we, the undersigned, ... *(insert name & address of the issuing bank)*, a Bank
(which expression shall include its successors, administrators, executors and assigns) organized under the
laws of and having its Registered/ Head Office at *(insert address of
registered office of the bank)* do hereby irrevocably guarantee repayment of *(Amount of
the bank guarantee in figures and words)* upon the first demand of the Employer without cavil

or argument in the event that the Contractor fails to commence or fulfill its obligations under the terms of the said Contract for reasons whatsoever.

Provided always that the Bank's obligation shall be limited to the amount of this Bank guarantee or an amount equal to the outstanding balance of the Advance Payment and the accrued interest on the Advance Payment, taking into account such amounts, which have been repaid by the Contractor from time to time in accordance with the terms of payment of the said Contract, as certified by you.

This Guarantee shall remain in full force from the date upon which the said Advance Payment is received by the Contractor up to sixty (60) days beyond the date on which the entire Advance Payment along with the accrued interest if any due thereon has been fully adjusted in terms of the Contract i.e., up to sixty (60) days beyond the date of Completion of the Facilities under the Contract. This Guarantee may be extended from time to time, as may be desired by M/s Solar Energy Corporation of India Limited on whose behalf this Guarantee has been issued.

Any claims to be made under this Guarantee must be received by the Bank during its period of validity, i.e. upto sixty (60) days beyond the date of Completion of the Facilities by the Employer i.e. upto and inclusive of (dd/mm/yy).

Notwithstanding anything contained herein:

1. Our liability under this Bank Guarantee shall not exceed _____ (value in figures) _____
[_____ (value in words) _____].
2. This Bank Guarantee shall be valid upto _____ (validity date) _____.
3. We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only & only if we receive a written claim or demand on or before _____ (validity date) _____.

For and on behalf of the Bank

[Signature of the authorised signatory(ies)]

Signature _____

Name _____

Designation _____

POA Number _____

Contact Number(s): Tel. _____ Mobile _____

Fax Number _____

email _____

Common Seal of the Bank _____

Witness:

Signature _____

Name _____

Address_____

Contact Number(s): Tel._____Mobile_____

email _____

Note:

1. For the purpose of executing the Bank Guarantee, the non-judicial stamp papers of appropriate value shall be purchased in the name of Bank who issues the 'Bank Guarantee'.
2. The Bank Guarantee shall be signed on all the pages by the Bank Authorities indicating their POA nos. and should invariably be witnessed.

Form F-22

LIST OF BANKS

(For Reference Purpose)

SBI AND ASSOCIATES	OTHER PUBLIC SECTOR BANKS
1. State Bank of India	1. IDBI Bank Limited
2. State Bank of Indore	FOREIGN BANKS
	1. Bank of America NA
	2. Bank of Tokyo Mitsubishi UFJ Ltd.
	3. BNP Paribas
	4. Calyon Bank
	5. Citi Bank N.A.
NATIONALISED BANKS	6. Deutsche Bank A.G
1. Allahabad Bank	7. The HongKong and Shanghai Banking Corpn. (HSBC) Ltd.
2. Andhra Bank	8. Standard Chartered Bank
3. Bank of India	9. Societe Generale
4. Bank of Maharashtra	10. Barclays Bank
5. Canara Bank	11. Royal Bank of Scotland (RBS)
6. Central Bank of India	12. Bank of Nova Scotia
7. Corporation Bank	13. Development Bank of Singapore (DBS)
8. Dena Bank	14. Credit Agricole Corporate and Investment Bank
9. Indian Bank	SCHEDULED PRIVATE BANKS
10. Indian Overseas Bank	1. Federal Bank Limited
11. Oriental Bank of Commerce	2. Kotak Mahindra Bank Limited
12. Punjab National Bank	3. Axis Bank Limited
13. Punjab & Sind Bank	4. ICICI Bank Limited
14. Syndicate Bank	5. HDFC Bank Limited
15. Union Bank of India	6. Yes Bank Limited
16. United Bank of India	7. IDFC Bank Limited
17. UCO Bank	8. IndusInd Bank
18. Vijaya Bank	9. Karur Vysya Bank
19. Bank of Baroda	10. South Indian Bank
	11. RBL

Form F-23

SHAREHOLDING CERTIFICATE

(To be submitted on the Letter Head of the Bidder)

Name of the Equity Holder	Type and Number of Shares Owned	% of Equity Holding	Extent of Voting Rights

Yours faithfully

(Signature and Stamp of Authorized Signatory of Bidder)

Name:

Date:

Place:

(Signature and Stamp of Company Secretary/ Director/ Chartered Accountant)

Form F-24

POWER OF ATTORNEY FOR BIDDING COMPANY

*(To be stamped in accordance with Stamp Act, the Non-Judicial Stamp Paper of Appropriate Value
should be in the name of the Bidder)*

Know all men by these presents, We (name and address of the registered office of the Bidding Company as applicable) do hereby constitute, appoint and authorize Mr./Ms. (name & residential address) who is presently employed with us and holding the position of as our true and lawful attorney, to do in our name and on our behalf, all such acts, deeds and things necessary in connection with or incidental to submission of our Bid for (insert details of Tender) in response to the Tender No dated issued by Solar Energy Corporation of India Limited (SECI), New Delhi including signing and submission of the Bid and all other documents related to the Bid, including but not limited to undertakings, letters, certificates, acceptances, clarifications, guarantees or any other document which the SECI may require us to submit. The aforesaid Attorney is further authorized for making representations to the Solar Energy Corporation of India Limited, New Delhi and providing information/ responses to SECI, New Delhi representing us in all matters before SECI, New Delhi and generally dealing with SECI, New Delhi in all matters in connection with Bid till the completion of the bidding process as per the terms of the above mentioned Tender.

We hereby agree to ratify all acts, deeds and things done by our said attorney pursuant to this Power of Attorney and that all acts, deeds and things done by our aforesaid attorney shall be binding on us and shall always be deemed to have been done by us.

All the terms used herein but not defined shall have the meaning ascribed to such terms under the Tender.

Signed by the within named

..... (Insert the name of the executant company)

through the hand of

Mr.

duly authorized by the Board to issue such Power of Attorney

**Dated this day of
Accepted**

.....
Signature of Attorney
(Name, designation and address of the Attorney)

Attested

.....

(Signature of the executant)
(Name, designation and address of the executant)

.....
Signature and stamp of Notary of the place of execution

Common seal of has been affixed in my/ our presence pursuant to Board of
Director's Resolution dated.....

WITNESS

1.
(Signature)

Name.....

Designation
2.
(Signature)

Name.....

Designation

Notes:

The mode of execution of the power of attorney should be in accordance with the procedure, if any, laid down by the applicable law and the charter documents of the executant(s) and the same should be under common seal of the executant affixed in accordance with the applicable procedure. Further, the person whose signatures are to be provided on the power of attorney shall be duly authorized by the executant(s) in this regard.

The person authorized under this Power of Attorney, in the case of the Bidding Company/ Lead Member being a public company, or a private company which is a subsidiary of a public company, in terms of the Companies Act, 1956, with a paid-up share capital of more than Indian Rupees Five Crores, should be the Managing Director/ Whole Time Director/ Manager appointed under section 269 of the Companies Act, 1956. In all other cases the person authorized should be a director duly authorized by a board resolution duly passed by the Company.

Also, wherever required, the executant(s) should submit for verification the extract of the chartered documents and documents such as a Board resolution/ power of attorney, in favour of the person executing this power of attorney for delegation of power hereunder on behalf of the executant(s).



Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of
5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years
Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding



5 MW (AC) Solar PV Power
Plant Project

Tender No
SECI/C&P/NIT/2017/BDL5MW-2

SAMPLE
FORMS
Page 40 of 40

Signature of Bidder



SECTION - VII

SCOPE OF WORK

&

TECHNICAL

SPECIFICATIONS

Contents

1	Design Philosophy	9
Detailed Specifications: Electrical system (DC & AC systems)		
2	Photovoltaic Modules	10
2.1	Standards and Codes	10
2.2	Technical Requirements	11
2.3	Component Specifications	11
2.4	Warranty.....	13
2.5	Approval	13
2.6	Manufacturing and Inspection	13
2.7	Transportation, Handling, Storage and Installation.....	14
3	String Monitoring Unit.....	14
3.1	Standards and Codes	14
3.2	Construction	14
3.3	Warranty.....	15
3.4	Approval	15
3.5	Tests.....	16
4	Solar and DC Cables	16
5	Power Conditioning Unit.....	17
5.1	Standards and Codes	17
5.2	Technical Requirements	18
5.3	Construction	19
5.4	Operating Modes.....	20
5.5	Protection Features.....	20
5.6	Grid Support Functions	21
5.6.1	Active power regulation.....	21
5.6.2	Reactive power control.....	21
5.6.3	Voltage Ride Through	21
5.7	Warranty.....	21
5.8	Approval	22
5.9	Tests.....	22
6	Inverter Transformer and Auxiliary Transformer	22
6.1	Standards and Codes	22
6.2	Technical Requirements	22
6.3	Construction	24

6.4	Warranty.....	25
6.5	Approval	26
6.6	Testing and Inspection	26
7	HT Switchgear	27
7.1	Standards and Codes	27
7.2	Technical Parameters	28
7.3	Switchgear Panel	29
7.4	Circuit Breakers.....	30
7.5	Relays	31
7.6	Instrument Transformers.....	33
7.7	Earthing	33
7.8	Bus bar	34
7.9	Measuring Instruments.....	34
7.10	Wiring and Terminal blocks.....	35
7.11	Warranty.....	35
7.12	Approval	35
7.13	Testing and Inspection	36
8	AC Cables	37
9	Auxiliary supply system	39
10	Distribution Switchgear	39
10.1	Standards and Codes	39
10.2	Technical Parameters	40
10.3	Constructional Details	41
10.4	Warranty.....	42
10.5	Approval	42
10.6	Testing.....	42
11	Uninterrupted Power Supply (UPS)	42
11.1	Standards and Codes	42
11.2	General Requirements	43
11.3	System Description	43
11.4	Warranty.....	44
11.5	Approval	45
11.6	Tests.....	45
12	Battery and Battery Charger	45
12.1	Standards and Codes	45

12.2	General.....	45
12.3	Battery	46
12.4	Battery charger.....	46
12.5	DC distribution board (DCDB).....	47
12.6	Warranty.....	47
12.7	Approval	47
12.8	Tests.....	47
13	Metering System	47
14	Earthing	50
14.1	Standards and Codes	50
14.2	General Requirements	50
14.3	Earthing of PV array field	51
14.4	PCU Earthing	51
14.5	Transformer Earthing	52
14.6	Inverter Room and Main Control Room Earthing.....	52
14.7	Switchyard Earthing	52
14.8	Approval	52
14.9	Tests.....	52
15	Lightning Protection System	52
16	Communication Cables	53
16.1	Optical Fibre Cables.....	53
16.2	Communication Cable (Modbus).....	54
17	SCADA	54
17.1	General Requirements	54
17.2	Programmable Logic based control system at Main Control Room.....	55
17.3	Human Machine Interface System (HMIS)	55
17.4	Programming Functionalities.....	56
17.5	Software Requirements.....	56
17.6	System Spare Capacity.....	56
17.7	Data Communication System (DCS).....	56
17.8	Operator Interface Displays/Logs/Reports.....	57
17.9	Historical Storage and Retrieval System (HSRS).....	57
17.10	Control and Power Supply Scheme	57
17.11	Control Cabinets / Panels / Desks at Main Control Room	57
17.12	Software Licences	58

17.13	Hardware at Main Control Room.....	58
17.14	Factory Acceptance Test (FAT)	59
18	Illumination	59
18.1	Standards and Codes	59
18.2	General specification.....	59
18.3	Lighting Levels	60
18.4	LED Luminaire.....	60
18.5	Warranty.....	61
18.6	Approval	61
19	Weather Monitoring System.....	62
19.1	Pyranometer.....	62
19.2	Temperature Sensor	62
19.3	Anemometer.....	63
19.4	Data logger and Data Acquisition System	63
20	CCTV Camera.....	64
21	Fire alarm System	65
22	Testing Instruments.....	66
22.1	Earth resistance tester	66
22.2	Array tester	66
22.3	Insulation tester	67
22.4	Digital Multimeter	67
22.5	Clamp meter.....	68
22.6	Infra-red thermal imaging camera.....	68
22.7	Digital lux meter.....	69
23	Power evacuation system	69
Civil, Mechanical & Plumbing Works		
24	General Requirement.....	70
25	Topographical Survey	71
26	Geotechnical Investigations	72
27	Other Investigations	75
28	Site Levelling and Grading	75
29	Roads	76
30	Surface/ Area drainage	77
31	Peripheral boundary Wall/Fence.....	78
32	Plant Layout	79

33	Design Loads	80
34	Foundations.....	81
35	Module Mounting Structure (MMS)	82
35.1	Standards and Codes	82
35.2	General Requirement.....	82
35.3	Galvanization.....	83
35.4	Fasteners	84
36	Concrete Works.....	84
37	Miscellaneous Steel Works	85
38	Buildings.....	85
38.1	General Requirement.....	85
38.2	Main Control Room (MCR) Building.....	85
38.3	Local/ Inverter Control Room Building	86
38.4	Security Room/ Watchman Cabin	86
39	Flooring, Skirting and Dado.....	87
40	Doors and Windows	87
41	Roofing	88
42	Plinth protection and drain	89
43	Plinth filling for buildings.....	89
44	Sanitary Works	89
45	Painting & Other Finishes	90
45.1	Painting	90
45.2	Air conditioning & Ventilation for MCR and Other Buildings	90
45.3	Fire Extinguishers	90
45.4	Sign Boards and Danger Boards	91
46	Masonry Work	91
47	Plastering, Pointing & Coping Works.	91
48	Building Water Supply & Plumbing Works	92
49	Pipe & Cable Trenches	92
50	Transformer Yard Civil Works	92
51	Water Supply & Cleaning of Modules	93
52	Underground/ Overground Water Tank	94
Performance Measurement Procedure		
53	Performance ratio.....	87
54	Capacity Utilization Factor (CUF)	87

55	Scope of Work	96

DISCLAMIER:

1. Though adequate care has been taken while preparing the Bidding documents, the Bidders/Applicants shall satisfy themselves that the document is complete in all respects. Intimation of any discrepancy shall be given to this office immediately. If no intimation is received from any Bidder within twenty (20) days from the date of notification of NIT/ Issue of the NIT documents, it shall be considered that the NIT documents are complete in all respects has been received by the Bidder.
2. Solar Energy Corporation of India (SECI) on behalf of M/s Bharat Dynamics Limited (BDL), The Employer, reserves the right to modify, amend or supplement this NIT documents including all formats and Annexures.
3. While this bidding documents have been prepared in good faith, neither Employer or its authorized representatives nor their employees or advisors make any representation or warranty, express or implied, or accept any responsibility or liability, whatsoever, in respect of any statements or omissions herein, or the accuracy, completeness or reliability of information, and shall incur no liability under any law, statute, rules or regulations as to the accuracy, reliability or completeness of this bidding documents, even if any loss or damage is caused by any act or omission on their part.
4. The specifications mentioned for all the equipment which include Solar modules, PCU, combiner boxes, DC cables, module mounting structures, transformer, CT, PT, LT/ HT cables, interfacing panels, switch gears & other associated equipment etc., to complete the power generation and evacuation to the designated substation, in the present bidding documents are for the **reference** only. It is subject to revise/ alter as per the design/ planning/ good engineering practices etc., to be carried out by the selected bidder, to the satisfaction of the Employer or its authorized representatives. It is advised that the bidders must satisfy himself with the prevailing site conditions before design/ plan. The design must be optimized as per the site conditions and directed to achieve the maximum output from the installed capacity at all times. Moreover, the components not separately mentioned, but are required to complete the plant for operation is also included in the scope of bidder and shall be vetted by the Employer or its authorised representatives.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 8 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Place:

(Signature)

Date:

Name and Designation of bidder

1 Design Philosophy

- 1.1 The main objective of the design philosophy is to construct the plant with in-built Quality and appropriate redundancy to achieve high availability and reliability with minimum maintenance efforts. In order to achieve this, the following principles shall be adopted while designing the system.
 - 1.1.1 Adequate capacity of SPV modules, PCUs, Junction boxes etc. to ensure generation of power as per design estimates. This will be done by applying liberal de-rating factors for the array and recognizing the efficiency parameters of PCUs, transformers, conductor losses, system losses, site conditions etc.
 - 1.1.2 Use of equipment and systems with proven design and performance that have high availability track records under similar service conditions.
 - 1.1.3 Selection of the equipment and adoption of a plant layout to ensure ease of maintenance.
 - 1.1.4 Strict compliance with approved and proven quality assurance (QA) systems and procedures during different stages of the project, starting from sizing, selection of make, shipment, storage (at site), during erection, testing and commissioning.
 - 1.1.5 Proper monitoring of synchronization and recording, to ensure availability of power to the grid.
 - 1.1.6 The plant instrumentation and control system should be designed to ensure high availability and reliability of the plant to assist the operators in the safe and efficient operation of the plant with minimum effort.
 - 1.1.7 It should also provide the analysis of the historical data and help in the plant maintenance people to take up the plant and equipment on predictive maintenance.
 - 1.1.8 System design shall have intelligent protection mechanism which may include very fast responsive microprocessor based relays etc., so that any disturbance from the grid will not cause any damage to the equipment of the Solar Power Plant.
- 1.2 The basic and detailed engineering of the plant shall aim at achieving high standards of operational performance especially considering following:
 - 1.2.1 SPV power plant should be designed to operate satisfactorily in synchronization with the grid within permissible limits of high voltage and frequency fluctuation conditions. It is also extremely important to safeguard the system during major disturbances, internal and external surge conditions while ensuring safe operation of the plant.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 9 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 1.2.2 SPV arrays are commonly fixed at an optimum tilted angle facing the equator. Trackers can also be used for tracking the sun on daily or seasonal basis. In case of fixed tilt, the tilt angle shall be defined in such a way that optimum generation is achieved at all times.
- 1.2.3 Shadow free plant layout to ensure minimum losses in generation during the day time.
- 1.2.4 Higher system voltage and lower current options to be followed to minimise ohmic losses.
- 1.2.5 Selection of PCUs with proven reliability and minimum downtime. Ready availability of requisite spares.
- 1.2.6 Careful logging of operational data / historical information from the Data Monitoring Systems, and periodical analysis of the same to identify any abnormal or slowly deteriorating conditions.
- 1.2.7 The designed array capacity at STC shall be suitably determined to meet the proposed guaranteed generation output at the point of interconnection by the contractor in his bid. The contractor shall take care of first year degradation also by installing additional DC capacity as the CUF calculations will not factor the first year degradation of the modules.
- 1.2.8 Each component offered by the bidder shall be of established reliability. The minimum target reliability of each equipment shall be established by the bidder considering its mean time between failures and mean time to restore, such that the availability of complete system is assured. Bidder's recommendation of the spares shall be on the basis of established reliability.
- 1.2.9 Bidder shall design the plant and equipment in order to have sustained life of 25 years with minimum maintenance efforts.
- 1.2.10 The work execution planning for supply, erection, commissioning and all other allied works for SPV Power Plant shall be such that it is completed within stipulated time from the date of order/ LOI/ NTP.
- 1.3 The specifications provided with this bid document are functional ones; any design provided in this document is only meant as an example. **The Contractor must submit a detailed design philosophy document for the project to meet the functional requirements based upon their own design in-line with the above.** The bidders are advised to visit the site and satisfy themselves before bidding.

Detailed Specifications: Electrical system (DC & AC systems)

2 Photovoltaic Modules

2.1 Standards and Codes

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 10 of 105</u>	<u>Signature of Bidder</u>

Photovoltaic Modules shall comply with the specified edition of the following standards and codes.

Standard	Description
IEC 61215 Ed.2	Crystalline silicon terrestrial photovoltaic (PV) modules - Design qualification and type approval
IEC 61730-1 Ed.1.2	Photovoltaic (PV) module safety qualification - Part 1: Requirements for construction
IEC 61730-2 Ed.1.1	Photovoltaic (PV) module safety qualification - Part 2: Requirements for testing
IEC 61701 Ed.2	Salt mist corrosion testing of photovoltaic (PV) modules (Applicable for coastal and marine environment)
IEC 62716 Ed.1	Photovoltaic (PV) modules - Ammonia corrosion testing
IEC TS 62804-1 Ed.1	Photovoltaic (PV) modules - Test methods for the detection of potential-induced degradation - Part 1: Crystalline silicon

2.2 Technical Requirements

Parameter	Specification
Cell type	Mono-crystalline or Multi-crystalline
Rated power at STC	Minimum 250 Wp No negative tolerance is allowed.
Module Efficiency	More than 18% for mono-crystalline More than 16% for multi-crystalline
Temperature co-efficient of power	Not more than 0.45%/°C
Ambient temperature	-10°C to +50°C
Relative humidity	Up to 85%
Wind speed	Suitable for site condition
Application Class as per IEC 61730	Class A

2.3 Component Specifications

- 2.3.1 The glass used to make the PV modules shall be toughened low iron glass with minimum thickness of 4.0 mm for 72 cell module and 3.2 mm for 60 cell module. The glass used shall have transmittance of above 90%.
- 2.3.2 The back sheet used in the PV modules shall be of three layered or mono layered structure. The back sheet should be durable for humid – hot conditions with properties of moisture barrier, elongation retention and UV resistance. The back sheet shall have the following properties.

Parameter	Value

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 11 of 105</u>	Signature of <u>Bidder</u>

Material thickness	≥ 300 micron
Water vapour transmission rate	< 2 g/m ² /day
Partial discharge test voltage	≥ 1000 V
Elongation at break	$> 100\%$
Adhesion strength with encapsulant	> 70 N/cm
Interlayer adhesion strength	> 5 N/cm

The Employer reserves the right to conduct Pressure Cooker (PC) test/ Highly Accelerated Stress Test (HAST) to confirm the durability of the back sheet in accelerated conditions.

- 2.3.3 The encapsulant used for the PV modules should be UV resistant in nature. No yellowing of the encapsulant with prolonged exposure shall occur. The encapsulant shall have the following properties.

Parameter	Value
Gel content	$> 75\%$
Volume resistivity	$> 1 \times 10^{15}$ Ω .cm
Peeling strength with glass	> 60 N/cm

- 2.3.4 The sealant used for edge sealing of PV modules shall have excellent moisture ingress protection with good electrical insulation (Break down voltage > 15 kV/mm) and with good adhesion strength. Edge tapes for sealing are not allowed.
- 2.3.5 The module frame shall be made of anodized Aluminium, which shall be electrically & chemically compatible with the structural material used for mounting the modules. It is required to have provision for earthing to connect it to the earthing grid. The anodization thickness shall not be less than 15 micron.
- 2.3.6 The material used for junction box shall be UV resistant to avoid degradation during module life. The degree of protection of the junction box shall be at least IP67. Minimum three number of bypass diodes and two number of MC4 connectors with appropriate length of TUV 2Pfg 1169/08.2007 certified 4 sq.mm Cu cable shall be provided. The cable length shall be in accordance with the PV Module wiring strategy and adequate to ensure that the cable bending radius standard is not exceeded.
- 2.3.7 Each PV Module shall be provided a bar code which is embedded inside the module lamination and must be able to withstand harsh environmental conditions. The bar code data base shall contain the following information. Bar code scanner and database of all the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 12 of 105</u>	<u>Signature of</u> <u>Bidder</u>

modules containing the following information shall also be provided.

- (i) Name of the manufacturer of PV Module
- (ii) Name of the Manufacturer of Solar cells
- (iii) Type of cell: Mono / Multi
- (iv) Month and year of the manufacture (separately for solar cells and module)
- (v) Country of origin (separately for solar cells and module)
- (vi) I-V curve for the module
- (vii) Peak Wattage, I_m , V_m and FF for the module
- (viii) Unique Serial No. and Model No. of the module.
- (ix) Date and year of obtaining IEC PV module qualification certificate
- (x) Name of the test lab issuing IEC certificate
- (xi) Other relevant information on traceability of solar cells and modules as per ISO 9000 series.

2.4 Warranty

- 2.4.1 PV modules must be warranted with linear degradation rate of power output except for first year and shall guarantee 80% of the initial rated power output at the end of 25 years.
- 2.4.2 The modules shall be warranted for minimum of 10 years against all material/ manufacturing defects and workmanship.

2.5 Approval

- 2.5.1 The Contractor shall provide commercial datasheet and Guaranteed Technical Particular datasheet
- 2.5.2 The Contractor shall provide the Bill of Materials (BOM) of the module that is submitted for approval along with the datasheets of each component. The component datasheet shall contain all the information to substantiate the compliance for component specifications mentioned above. The Contractor shall also provide complete test reports and certifications for the module proposed as per above. The BOM proposed shall be the subset of Constructional Data Form (CDF)'s of all the test reports.
- 2.5.3 The Contractor shall obtain the approval of the proposed module make & model prior to manufacturing/ inspection call.

2.6 Manufacturing and Inspection

- 2.6.1 The Contractor shall inform the module manufacturing schedule to the Employer at least 7 (seven) working days before the start of proposed schedule.
- 2.6.2 The Employer shall perform material inspection at the Manufacturer's factory before the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 13 of 105</u>	<u>Signature of</u> <u>Bidder</u>

start of proposed manufacturing schedule. Proof of procurement of components as per the approved BOM mentioning manufacturer name, manufacturing date and relevant test certificate shall be submitted during material inspection for verification.

- 2.6.3 The Manufacturing shall start only after the clearance by the Employer after the material inspection.
- 2.6.4 The cells used for module making shall be free from all defects like edge chipping, breakages, printing defects, discoloration of top surface etc. Only Class A solar cell shall be used.
- 2.6.5 The modules shall be uniformly laminated without any lamination defects.
- 2.6.6 Current binning of modules shall be employed so that current mismatch of modules in a pallet does not exceed 2% of current at Maximum Power (Imp). Different colour codes shall be provided on the modules as well as pallet for identification of different bins.
- 2.6.7 Pre-dispatch inspection of modules shall be performed as per the inspection protocol attached in Annexure – A.

2.7 Transportation, Handling, Storage and Installation

- 2.7.1 Transportation, handling, storage and installation of modules shall be in accordance with the manufacturer manual so as not to breach warranty conditions. The Standard Operating Procedure (SOP) for the same shall be shared by the Contractor prior to dispatch.
- 2.7.2 It is required to construct a temporary platform (graded) while keeping the modules at least above the highest flood level. If the contractor scheduled/ planned to mount the modules immediately after the receipt at site, then the module shall be kept in common storage area with proper arrangement.
- 2.7.3 The stacked modules, in any case, shall be stacked as per the manufacturer's recommendation only and shall be covered with tarpaulin sheet.

3 **String Monitoring Unit**

3.1 Standards and Codes

Standard/Code	Description
IEC 60529	Enclosure Ingress Protection
IEC 62262	Enclosure Impact Protection
IEC 60296	Fuse
IEC 61643-12	Surge Protection Device
IEC 62852 or EN 50521	Solar cable connector

3.2 Construction

- 3.2.1 Enclosure shall be made of UV resistant, fire retardant, thermoplastic material. Enclosure

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> SECI/C&P/NIT/2017/BDL5MW-2	<u>SoW & TS</u> Page 14 of 105	<u>Signature of</u> Bidder

degree of protection shall be at least IP65 and mechanical impact resistance shall be at least IK07.

- 3.2.2 Not more than two strings can be connected in parallel to a single input of SMU. One spare input terminal along with connector shall be provided for each SMU.
- 3.2.3 Every SMU input shall be provided with fuses on both positive and negative side. The rating of the fuses shall be selected such that it protects the modules from reverse current overload. The fuses shall be 'gPV' type conforming to IEC 60269-6. It should also have a reverse blocking diode at either of the incomer.
- 3.2.4 DC disconnect switch of suitable rating shall be provided at SMU output to disconnect both positive and negative side simultaneously.
- 3.2.5 Type-II surge protective device (SPD) conforming to IEC 61643-12 shall be connected between positive/negative bus and earth.
- 3.2.6 Resistance Temperature Detector (RTD) type or semiconductor type temperature sensor shall be provided to monitor the cabinet temperature.
- 3.2.7 MC4 connector conforming to IEC 62852 or EN 50521 shall be provided at each SMU input. Cable gland (double compression metallic) of suitable size for DC cables shall be provided at the SMU output.
- 3.2.8 UV resistant printed cable ferrules for solar cables & communication cables and punched/ embossed aluminium tags for DC cables shall be provided at cable termination points for identification.
- 3.2.9 Suitable communication interface shall be provided to communicate the data to SCADA. The following parameters shall be measured/ monitored and made available at SCADA.
 - (i) String current
 - (ii) Bus voltage
 - (iii) Output current
 - (iv) Cabinet temperature
 - (v) DC disconnect switch ON/OFF status
 - (vi) SPD operating status

3.3 Warranty

The SMU unit shall be warranted for minimum of 5 (five) years against all material/ manufacturing defects and workmanship.

3.4 Approval

3.4.1 Documents/Drawings

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 15 of 105</u>	<u>Signature of Bidder</u>

- (i) Guaranteed Technical Particular (GTP) Datasheet.
- (ii) Bill of Materials for the proposed SMU along with the datasheet of each component
- (iii) General Arrangement (GA) drawing
- (iv) Quality Assurance Plan (QAP)

3.4.2 Test Certificates/Reports

- (i) Test certificates of fuse, SPD and solar cable connector
- (ii) Enclosure ingress protection and impact protection test certificates

3.5 Tests

Routine tests and acceptance tests for the assembled unit shall be as per the Quality Assurance Plan (QAP) approved by the Employer.

4 Solar and DC Cables

4.1 Standards and Codes

Cable	From	To	Conductor/ Insulation	Voltage Rating	Applicable Standard
Solar Cable*	Module	SMU	Copper/ XLPO	1.1 kV DC	TUV 2 PfG 1169/08.2007
DC Cable	SMU	Power Conditioning Unit	Copper or Aluminium/ XLPE	1.1 kV DC	IS 7098 Part I
* Cable used for module interconnection shall also be referred as solar cable.					

- 4.2 Solar cable outer sheath shall be flame retardant, UV resistant and black in colour. Solar cable with positive polarity should have marking of red line on black outer sheath.
- 4.3 DC cables shall be single core, armoured, Flame Retardant Low smoke (FRLS), PVC outer sheath conforming to IS 7098-I. DC cable with positive polarity should have marking of red line on black outer sheath.
- 4.4 In addition to manufacturer's identification on cables as per relevant standard, following marking shall also be provided over outer sheath.
 - (i) Cable size and voltage grade
 - (ii) Word 'FRNC/ FRLS' (as applicable) at every metre
 - (iii) Sequential marking of length of the cable in metres at every metre
- 4.5 Cables shall be sized based on the following considerations:
 - (i) Rated current of module
 - (ii) The average voltage drop in the cables (Modules to Inverter) shall be limited to 1.5 % of the rated voltage. Contractor shall provide voltage drop calculations in excel sheet.

5 MW (AC) Solar PV Power Plant Project	Tender No SECI/C&P/NIT/2017/BDL5MW-2	SoW & TS Page 16 of 105	Signature of Bidder

(iii) Short circuit withstand capability

(iv) De-rating factors according to laying pattern

4.6 Warranty

The cables (Solar and DC) shall be warranted for minimum of 1 (one) year against all material/ manufacturing defects and workmanship.

4.7 Approval

4.7.1 Documents/Drawings

- (i) Guaranteed Technical Particular (GTP) Datasheet.
- (ii) Solar and DC Cable sizing calculation
- (iii) Quality Assurance Plan (QAP)

4.7.2 Test Certificates/Reports

- (i) Solar cable type test certificate as per TUV 2 PfG 1169/08.2007
- (ii) DC cable type test certificate as per IS 7098-1

4.8 Tests

Routine test and acceptance tests requirements shall be as per TUV specification 2PfG 1169/08.2007 for solar cables and IS 7098-1 for DC cables.

4.9 Installation

4.9.1 Cable installation shall be as per IS 1255.

4.9.2 Only terminal cable joints shall be accepted. No cable joint to join two cable ends shall be accepted.

4.9.3 Solar cables shall be provided with UV resistant printed ferrules and DC cables shall be provided with punched/ embossed aluminium tags. The marking shall be done with good quality letter and numbers of proper size so that the cables can be identified easily.

4.9.4 Cable terminations shall be made with properly crimped lugs and passed through cable glands at the entry & exit point of the cubicles. Bimetallic lugs shall be used for connecting Cu bus bar and Al cables or vice-versa.

4.9.5 Solar cables, wherever exposed to direct sunlight and buried underground, shall be laid through Double Wall Corrugated (DWC) HDPE conduits.

4.9.6 Solar cables shall be aesthetically tied to Module Mounting Structure using UV resistant cable-ties suitable for outdoor application.

5 **Power Conditioning Unit**

5.1 Standards and Codes

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 17 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Power Conditioning Unit (PCU) shall comply with the specified edition of the following standards and codes.

Standard	Description
IEC 61683 Ed. 1	Photovoltaic systems - Power conditioners - Procedure for measuring efficiency
EN 50530:2010 with 2013 Amendment 1	Overall efficiency of grid connected photovoltaic inverters
IEC 62109-1 Ed. 1	Safety of power converters for use in photovoltaic power systems - Part 1: General requirements
IEC 62109-2 Ed. 1	Safety of power converters for use in photovoltaic power systems - Part 2: Particular requirements for inverters
IEC 61000-6-2 Ed. 2	Electromagnetic compatibility (EMC) - Part 6-2: Generic standards - Immunity standard for industrial environments
IEC 61000-6-4 Ed. 2.1	Electromagnetic compatibility (EMC) - Part 6-4: Generic standards - Emission standard for industrial environments
IEC 62116 Ed. 2	Utility-interconnected photovoltaic inverters - Test procedure of islanding prevention measures
IEEE 1547:2003 with 2014 Amendment 1	IEEE Standard for Interconnecting Distributed Resources with Electric Power Systems
IEC 60068-2-1:2007	Environmental testing - Part 2-1: Tests - Test A: Cold
IEC 60068-2-2:2007	Environmental testing - Part 2-2: Tests - Test B: Dry heat
IEC 60068-2-14:2009	Environmental testing - Part 2-14: Tests - Test N: Change of temperature
IEC 60068-2-30:2005	Environmental testing - Part 2-30: Tests - Test Db: Damp heat, cyclic (12 h + 12 h cycle)
CEA Technical Standards for Connectivity to the Grid Regulations 2007 with 2013 Amendment	

5.2 Technical Requirements

Parameter	Specification
Rated AC power	As per design
Maximum input voltage	1000 V
Rated AC output voltage	As per design

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 18 of 105</u>	<u>Signature of Bidder</u>

Tolerance on rated AC output voltage	+/-10%
Rated frequency	50 Hz
Operating frequency range	47.5 Hz to 52 Hz
Power factor control range	0.9 lag to 0.9 lead
European efficiency	Minimum 98%
Maximum loss in Sleep Mode	0.05% of rated AC power
Total Harmonic Distortion	Less than 3% at 100% load
Degree of protection	IP 20 (Indoor)/IP 54 (Outdoor)

- 5.2.1 The rated/ name plate AC capacity of the PCU shall be AC power output of the PCU at 50°C.
- 5.2.2 Maximum power point tracker (MPPT) shall be integrated in the PCU to maximize energy drawn from the Solar PV array. The MPPT voltage window shall be sufficient enough to accommodate the output voltage of the PV array at extreme temperatures prevailing at site.
- 5.2.3 The PCU output shall always follow the grid in terms of voltage and frequency. The operating voltage and frequency range of the PCU shall be sufficient enough to accommodate the allowable grid voltage and frequency variations.

5.3 Construction

- 5.3.1 Power Conditioning Unit (PCU) shall consist of an electronic three phase inverter along with associated control, protection, filtering, measurement and data logging devices.
- 5.3.2 Every DC input terminal of PCU shall be provided with fuse of appropriate rating. The combined DC feeder shall have suitably rated isolators for safe start up and shut down of the system.
- 5.3.3 Type-II surge protective device (SPD) conforming to IEC 61643-12 shall be connected between positive/ negative bus and earth.
- 5.3.4 In case external auxiliary power supply is required, standalone UPS shall be used to meet auxiliary power requirement of PCU. It shall have a backup storage capacity of 2 hours.
- 5.3.5 Circuit Breaker of appropriate voltage and current rating shall be provided at the output to isolate the PCU from grid in case of faults.
- 5.3.6 The PCU shall be tropicalized and the design shall be compatible with conditions prevailing at site. Suitable number of exhaust fan with proper ducting shall be provided for cooling keeping in mind the extreme climatic condition of the site as per the recommendations of OEM to achieve desired performance and life expectancy.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 19 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 5.3.7 All the conducting parts of the PCU that are not intended to carry current shall be bonded together and connected to dedicated earth pits through protective conductor of appropriate size. DC negative terminal shall be grounded.
- 5.3.8 Dedicated communication interface shall be provided to monitor the PCU from SCADA.
- 5.3.9 PCU front panel shall be provided with LCD/ LED to display all the relevant parameters related to PCU operation and fault conditions. It shall include, but not limited to, the following parameters.
- (i) DC input power
 - (ii) DC input voltage
 - (iii) DC input current
 - (iv) AC output power
 - (v) AC output voltage (all the 3 phases and line)
 - (vi) AC output current (all the 3 phases and line)
 - (vii) Frequency
 - (viii) Power Factor

5.4 Operating Modes

Operating modes of PCU shall include, but not limited to, the following modes. These operating modes and conditions for transition are indicative only. The Contractor shall provide the detailed flow chart indicating the various operating modes and conditions for transition during detailed engineering.

5.4.1 Standby Mode

The PCU shall continuously monitor the input DC voltage and remain on Standby Mode until it reaches the pre-set value.

5.4.2 MPPT Mode

When the input DC voltage is above the pre-set value and AC grid connection conditions are fulfilled, the PCU shall enter into MPPT mode.

5.4.3 Sleep Mode

When the AC output power/DC input voltage decreases below the pre-set value for pre-set time delay, the PCU shall switch into Sleep Mode.

5.5 Protection Features

The PCU shall include appropriate self-protective and self-diagnostic feature to protect itself and the PV array from damage in the event of PCU component failure or from parameters beyond the PCU's safe operating range due to internal or external causes. The self-protective

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 20 of 105</u>	<u>Signature of Bidder</u>

features shall not allow signals from the PCU front panel to cause the PCU to be operated in a manner which may be unsafe or damaging. Faults due to malfunctioning within the PCU, including commutation failure, shall be cleared by the PCU protective devices.

The PCU shall provide protection against the following type of faults, among others.

- (i) DC/AC over current
- (ii) DC/AC over voltage
- (iii) DC reverse polarity
- (iv) DC earth fault
- (v) AC under voltage
- (vi) AC under frequency/over frequency
- (vii) Islanding
- (viii) Over temperature
- (ix) Lightning surges
- (x) Cooling fan failure
- (xi) Auxiliary supply failure

5.6 Grid Support Functions

5.6.1 Active power regulation

The PCU shall be able to limit the active power exported to the grid based on the set point provided through PCU front control panel. The PCU shall also be able to automatically limit the active power after an increase in grid frequency above a pre-set value. The ramp rate shall be adjustable during operation and start-up after fault. The applicability of the requirement shall be as per CEA regulation and compliance.

5.6.2 Reactive power control

The PCU shall be able to inject /absorb reactive power to/ from the grid based on the set point provided through PCU front control panel. The same shall be performed automatically with adjustable ramp rate based on dynamic changes in grid voltage or reactive power reference.

5.6.3 Voltage Ride Through

The PCU shall remain connected to the grid during temporary dip or rise in grid voltage as per the LVRT and HVRT requirements of CEA Technical Standards for Connectivity to the Grid Regulations. The PCU shall also be able to inject reactive power during the period of voltage dip.

5.7 Warranty

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 21 of 105</u>	<u>Signature of</u> <u>Bidder</u>

The complete Power Conditioning Unit shall be warranted for minimum of 5 (five) years against all material/ manufacturing defects and workmanship.

5.8 Approval

5.8.1 Documents/Drawings

- (i) Guaranteed Technical Particular (GTP) Datasheet.
- (ii) General Arrangement (GA) drawing and Foundation details
- (iii) Single Line Diagram and Bill of Materials
- (iv) Transformer Requirements
- (v) Quality Assurance Plan (QAP)

5.8.2 Test Certificates/Reports

All the test certificates as per the standards mentioned above shall be submitted for approval. The tests should have been conducted at a test laboratory compliant with ISO 17025 for testing and calibration and accredited by an ILAC member signatory. Laboratory accreditation certificate or weblink along with scope of accreditation shall also be submitted. It is the responsibility of the Contractor to substantiate the compliance for CEA Regulations using test reports.

5.9 Tests

Routine tests and acceptance tests shall be as per the Quality Assurance Plan (QAP) approved by the Employer.

6 **Inverter Transformer and Auxiliary Transformer**

6.1 Standards and Codes

Inverter transformer and auxiliary transformer, wherever applicable, shall comply with the latest edition of the following standards and codes including amendments.

Standard	Description
IS:2026, IEC:60076	Specification of Power Transformers
IS:2099, IEC:60137	Bushings for alternate voltage above 1000 V
IS: 335, IEC 60296	Insulating oil
IS: 3639	Fittings and Accessories for Power Transformers

6.2 Technical Requirements

Parameters	Inverter Transformer	Auxiliary Transformer
VA Rating	As per system requirement and SLD	

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 22 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Voltage Ratio	33 kV/ Inverter output voltage	33 kV/0.415 kV
Duty, Service & Application	Continuous Solar Inverter application and converter Duty (Outdoor)	Continuous application (Outdoor/Indoor)
Winding	As per system design requirement	2
Frequency	50 Hz	50Hz
Nos. of Phase	3	3
Vector Group & Neutral earthing	As per system/inverter manufacturer requirement and SLD	Dyn11
Cooling	ONAN	ONAN/ AN
Tap Changer	OCTC, No. of steps shall be as per the SLD and system requirement	
Impedance at 75°C	As per Inverter Manufacturer requirement and SLD	As per system requirement and SLD
Permissible Temperature rise over an ambient of 50°C (irrespective of tap)		
Top Oil	50°C	50°C
Winding	55°C	55°C
SC withstand time (thermal)	2 second	2 second
Fault Level & Bushing CT	25 kA for 3 second	
Termination	As per system requirement and SLD	
Bushing rating, Insulation class (Winding & bushing)	HV side - 36 kV porcelain bushings LV side – 1.1 kV porcelain bushings	
Noise level	As per NEMA TR-1	
Loading Capability	Continuous operation at rated MVA on any tap with voltage variation of +/-3%, also transformer shall be capable of being loaded in accordance with IEC 60076-7	
Flux density	Not to exceed 1.9 Wb/sq.m. at any tap position with combined frequency and voltage variation from rated V/f ratio by 10% corresponding to the tap. Transformer shall also withstand following over fluxing conditions due to	

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 23 of 105</u>	<u>Signature of Bidder</u>

	combined voltage and frequency fluctuations: a) 110% for continuous rating b) 125% for at least one minute c) 140% for at least five seconds. Bidder shall furnish over fluxing characteristic up to 150%
Air Clearance	As per CBIP
* Single Line Diagram (SLD) will be finalized during detailed engineering.	

6.3 Construction

- 6.3.1 The transformer shall be provided with conventional single compartment conservator with prismatic toughened glass oil gauge. The top of the conservator shall be connected to the atmosphere through indicating type cobalt free silica gel breather with transparent enclosure. Silica gel shall be isolated from atmosphere by an oil seal. Inverter transformers shall be provided with Magnetic Oil Gauge (MOG) with low oil level alarm contact.
- 6.3.2 It is the responsibility of the Contractor to ensure that the inverter transformer comply with all the requirements of inverter provided by the inverter manufacturer.
- 6.3.3 Inverter Transformer shall be designed for at least 5% total harmonic distortion (THD) to withstand distortion generated by the inverter as well as possible outside harmonics from the network.
- 6.3.4 The transformer shall be suitable for continuous operation with a frequency variation of $\pm 2.5\%$ from nominal frequency of 50 Hz without exceeding the specified temperature rise.
- 6.3.5 Inverter Transformer shall have shield winding between LV & HV windings. Each LV winding must be capable of handling non-sinusoidal voltage with voltage gradient as specified by the inverter manufacturer. Also, shield winding shall be taken out from tank through shield bushing and the same shall be brought down to the bottom of the tank using copper flat and support insulator for independent grounding.
- 6.3.6 Neutral bushing of Inverter duty transformer shall be brought outside the tank for the testing purpose. It shall be covered with MS sheet and a sticker "For testing purpose only. Do not earth". Neutral bushing of auxiliary transformer shall be brought outside the tank for earthing.
- 6.3.7 Transformer shall have 150 mm dial type Oil Temperature Indicator (OTI) and Winding temperature Indicator (WTI) with alarm and trip contacts. All indicators shall have accuracy class of ± 2 deg. For inverter transformers, WTI shall be provided for all the windings.
- 6.3.8 The radiators shall be detachable type, mounted on the tank with shut off valve at each

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 24 of 105</u>	<u>Signature of</u> <u>Bidder</u>

point of connection to the tank, lifts, along with drain plug/ valve at the bottom and air release plug at the top.

- 6.3.9 Marshalling Box shall be of sheet steel, dust and vermin proof provided with proper lighting and thermostatically controlled space heaters. The degree of protection shall be IP 55. Marshalling Box of all transformers shall be preferably Tank Mounted. One dummy terminal block in between each trip wire terminal shall be provided. At least 10% spare terminals shall be provided on each panel. The gasket used shall be of neoprene rubber. Wiring scheme (TB details) shall be engraved in a stainless steel plate with viewable font size and the same shall be fixed inside the Marshalling Box door.
- 6.3.10 Buchholz relay, double float type with alarm and trip contacts, along with suitable gas collecting arrangement shall be provided.
- 6.3.11 Inverter transformer shall be provided with spring operated Pressure Relief Device (with trip contacts) with suitable discharge arrangement for oil. For Auxiliary transformers, diaphragm type explosion vent shall be provided.
- 6.3.12 Filter valve at top the tank and drain cum sampling valve at bottom of the tank shall be provided.
- 6.3.13 All external surface of the transformer shall be painted with two coats of epoxy based paint of colour shade RAL 7032. Internal surface of cable boxes and marshalling box shall be painted with epoxy enamel white paint. The minimum dry film thickness (DFT) shall be 100 micron.
- 6.3.14 LV and HV cable box shall be provided with disconnecting chamber to facilitate the movement of transformer without disturbing cable box and termination.
- 6.3.15 Air release plug, bi-directional wheel/skids, cover lifting eyes, transformer lifting lugs, jacking pads, towing holes, core and winding lifting lugs, inspection cover, rating plate, valve schedule plate, accessories and terminal marking plates, two nos. of earthing terminals shall be provided.
- 6.3.16 Rain hoods to be provided on Buchholz, MOG & PRD. Entry points of wires shall be suitably sealed.
- 6.3.17 The accessories listed above are indicative only. Accessories which are not mentioned above but required for satisfactory operation of the transformers are deemed to be included in the contract without extra charges.

6.4 Warranty

The transformer shall be warranted for minimum of 5 (five) years against all material/ manufacturing defects and workmanship.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 25 of 105</u>	<u>Signature of</u> <u>Bidder</u>

6.5 Approval

6.5.1 Documents/Drawings

- (i) Guaranteed Technical Particular (GTP) Datasheet.
- (ii) General Arrangement (GA) Drawing of complete transformer, cable boxes, marshalling box
- (iii) Foundation details
- (iv) Rating plate and Valve schedule plate
- (v) Marshalling box wiring diagram
- (vi) Manufacturer acceptance for inverter requirements
- (vii) Quality Assurance Plan (QAP)

6.5.2 Test Certificates/Reports

Type test and Special test reports as mentioned in the following clause shall be submitted for approval.

6.6 Testing and Inspection

6.6.1 Type Tests and Special Tests

The following type test and special test reports shall be submitted during detailed engineering. The tests should have been conducted on the similar transformer by NABL accredited laboratory.

A. Type Tests

- (i) Lightning impulse (Full & Chopped Wave) test on windings as per IEC 60076-3
- (ii) Temperature Rise test at a tap corresponding to maximum losses as per IEC 60076-2

B. Special Tests

- (i) Measurement of zero-sequence impedance as per IEC 60076-1
- (ii) Measurement of harmonics of no-load current as per IEC 60076-1
- (iii) Measurement of acoustic noise level as per NEMA TR-1

In case the contractor is not able to submit the test reports during detailed engineering, the contractor shall submit the reports of type/special tests either conducted by NABL accredited laboratory or witnessed by Employer.

6.6.2 Routine Tests

Each completed transformer shall be subjected to following routine tests as per the latest edition of IEC 60076 unless specified otherwise.

- (i) Measurement of winding resistance at each tap

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 26 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- (ii) Measurement of voltage ratio between HV and LV windings at each tap
- (iii) Check of vector group
- (iv) Measurement of no-load loss and no-load current
- (v) Measurement of short-circuit impedance and load loss
- (vi) Magnetic balance test as per CBIP manual publication no. 295
- (vii) Separate source voltage withstand test
- (viii) Induced over voltage withstand test
- (ix) Measurement of insulation resistance
- (x) Marshalling box functional test
- (xi) IR Measurement on wiring of marshalling box
- (xii) Breakdown voltage test on transformer oil as per IS 335
- (xiii) Oil leakage test on completely assembled transformer along with radiators

6.6.3 Tests at Site

After erection at site all transformer(s) shall be subjected to the following tests.

- (i) Measurement of voltage ratio
- (ii) Check of vector group
- (iii) Magnetic balance test
- (iv) Measurement of insulation resistance
- (v) Breakdown voltage test on transformer oil

In case the equipment is not found as per the requirements of the Technical Specifications of NIT, all expenses incurred during site testing will be to the Contractor's account and the equipment shall be replaced by him at free of cost.

7 HT Switchgear

7.1 Standards and Codes

All equipment provided under HT switchgear shall comply with latest editions and amendments of the relevant IEC standards and IS codes. In particular, the switchgear shall comply with the following standards and codes.

Standard/Code	Description
IS/IEC 62271-1	High Voltage Switchgear and Control gear - Part 1: Common Specifications
IS/IEC 62271-100	High Voltage Switchgear and Control gear - Part 100: AC Circuit Breakers

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 27 of 105</u>	<u>Signature of</u> <u>Bidder</u>

IS/IEC 62271-102	High Voltage Switchgear and Control gear - Part 102: AC Disconnectors and Earthing Switches
IS/IEC 62271-200	High Voltage Switchgear and Control gear - Part 200: AC Metal Enclosed Switchgear and Control gear for Rated Voltages Above 1 kV and Up to and Including 52 kV
IEC 61869	Instrument Transformers
IS 3231	Electrical relays for power systems protection
IEC 60255	Measuring relays and protection equipment
IEC 61850	Communication networks and systems for power utility automation
IEC 61131-3	Programmable controllers - Part 3: Programming languages
IS 9385	High voltage fuses
IS 9431	Indoor post insulators of organic material for systems with nominal voltages greater than 1000 V up to and including 300 kV
IEC 60099-4	Surge arresters - Part 4: Metal-oxide surge arresters without gaps for A.C. systems
IS 3070-3	Lightning Arresters for Alternating Current Systems - Part 3 : Metal Oxide Lightning Arresters Without Gaps
IEC 62052-11	Electricity metering equipment (A.C.) - General requirements, tests and test conditions - Part 11: Metering equipment
IEC 62053	Electricity metering equipment (A.C.) - Particular requirements
IS 14697	AC Static Transformer Operated Watthour and Var-hour Meters, Class 0.2S and 0.5S

7.2 Technical Parameters

Parameter	Specification
System Parameters	
Highest system voltage	36 kV
Rated system voltage	33 kV
Rated frequency	50 Hz
Number of phases	3
Power frequency withstand voltage	70 kV (r.m.s.)
Lightning impulse withstand voltage	170 kV (peak)

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 28 of 105	Signature of Bidder

System fault current	25 kA for 1s
Circuit Breaker	
Type	Vacuum type
Operating duty cycle	O – 0.3sec – CO – 3min – CO
Short circuit breaking current	25 kA
Short circuit making current	63 kA
Re-strike performance class	C2
Mechanical endurance class	M1
Current Transformer	
Accuracy class	0.2 for metering (0.2s for metering at outgoing feeder) 5P20 for protection
Rated VA burden	As per requirement
Insulation class	Class E
Voltage Transformer	
Accuracy class	0.2 for metering 3P for protection
Rated VA burden	As per requirement
Insulation class	Class E

7.3 Switchgear Panel

- 7.3.1 The switchgear panel shall be free standing, floor mounted, single front, single tier fully compartmentalized, metal enclosed construction. Each panel shall have separate compartments for circuit breaker, bus bars, cable termination and auxiliary circuit.
- 7.3.2 The circuit breakers shall be mounted on horizontally withdrawable trucks with locking facility in SERVICE and TEST positions.
- 7.3.3 The panel enclosure shall be constructed with CRCA steel/Aluzinc sheet. The thickness of load bearing members shall be minimum 3 mm and that of non-load bearing members shall be minimum 2 mm.
- 7.3.4 All external surface shall be painted with two coats of epoxy based paint of colour shade RAL 7032. Internal surface shall be painted with epoxy enamel white paint. The minimum dry film thickness (DFT) shall be 100 micron.
- 7.3.5 The circuit breaker and auxiliary circuit compartments provided on the front side shall have separate concealed hinged doors. Cable and bus bar compartments provided on the rear

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 29 of 105</u>	<u>Signature of</u> <u>Bidder</u>

side shall have separate bolted covers. All doors and covers shall be provided with neoprene/synthetic rubber gaskets to prevent entry of vermin and dust.

- 7.3.6 Pressure relief device shall be provided in each high voltage compartment of a panel to safely vent the gases in the event of internal arc. Seal-off bushing arrangement shall be provided between the breaker compartment and bus bar/cable compartments to prevent transfer of arc from one compartment to other.
- 7.3.7 Automatic safety shutters shall be provided to cover up the fixed high voltage contacts on bus bar and cable sides when the truck is moved to TEST position.
- 7.3.8 Degree of protection shall not be less than IP 5X for auxiliary circuit compartment. However, for remaining compartments it shall not be less than IP 5X.
- 7.3.9 Mechanical /Electrical interlocks shall be provided to prevent mal-operation and in particular to ensure the following.
- (i) The breaker shall be operated only if it is in SERVICE or TEST position.
 - (ii) Movement of the breaker truck between SERVICE and TEST positions shall be possible only if the breaker is OFF.
 - (iii) It shall be possible to open the door only when the breaker is in TEST position.
- 7.3.10 Each switchgear panel shall be provided with thermostatically controlled space heaters, separately for breaker, cable and bus bar compartments, to prevent condensation within the compartment. The space heater shall be connected to 240 V, 50 Hz, single phase AC supply through suitable switch and fuse.
- 7.3.11 240 V, 15 A, SPN industrial socket-outlet with ON/OFF switch shall be provided in each panel.
- 7.3.12 Each panel shall be provided with LED lamp rated for 240 V, 50 Hz, single phase AC supply for interior illumination controlled by door switch.
- 7.3.13 Gapless, metal-oxide surge arrestors shall be provided between line and earth in cable compartment of the switchgear panel.
- 7.3.14 Suitable lifting hooks shall be provided for each panel.

7.4 Circuit Breakers

- 7.4.1 Circuit breakers shall be of vacuum type. It shall comprise of three separate identical single pole units operated through the common shaft and shall be fully interchangeable both electrically and mechanically.
- 7.4.2 The circuit breaker operating mechanism shall be based on motor operated spring charging and it shall be re-strike free, trip free both electrically and mechanically, with anti-pumping feature.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 30 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 7.4.3 The rated control voltage of the spring charging motor shall be 110 VDC/230 VAC. Closing coil shall operate at all values of voltages between 85% and 110% of rated voltage. Opening coil shall operate correctly under all operating conditions of the circuit breaker up to the rated breaking capacity and at all values of supply voltage between 70% and 110% of rated voltage.
- 7.4.4 The spring charging motor shall have adequate thermal rating such that continuous sequence of the closing and opening operations is possible as long as power supply is available to the motor. It shall also be possible to charge the spring manually and close the breaker in the event of failure of motor / control supply to motor. Operating handle shall be provided for charging the operating mechanism. After failure of control supply to the motor, one open-close-open operation shall be possible with the energy contained in the operating mechanism.
- 7.4.5 The motor rating shall be such that it requires not more than 30 seconds for full charging of the closing spring. Closing action of the circuit breaker shall compress the opening spring ready for tripping. When closing springs are discharged after closing the breaker, they shall be automatically charged for the next operation.
- 7.4.6 Mechanical indicators shall be provided to indicate OPEN/CLOSED positions of the circuit breaker and CHARGED/ DISCHARGED positions of the closing spring. An operation counter shall also be provided. These indicators and counter shall be visible from the panel front door without opening it.

7.5 Relays

- 7.5.1 All relays shall be microprocessor based numerical type. However, auxiliary relays can be static or electromechanical type. The relays shall be flush mounted on panel front with connections from the inside.
- 7.5.2 Auxiliary voltage of the relays shall be 110 VDC and the relays shall be capable of operating continuously between 80 – 120% of auxiliary voltage.
- 7.5.3 All numerical relays shall have adequate number of freely configurable, optically isolated, Binary Inputs (BI) and potential free Binary Outputs (BO).
- 7.5.4 All numerical relays shall have minimum four no. of current inputs, three for phase current and one for earth current, suitable for CT secondary current of 1A. The current inputs shall be compatible with both residual connected CT and Core Balance CT (CBCT). In addition, numerical relay in main outgoing feeder shall have three no. of voltage inputs for Under Voltage/Over Voltage protection.
- 7.5.5 All I/O's shall have galvanic isolation. Analog inputs shall be protected against switching

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 31 of 105</u>	<u>Signature of</u> <u>Bidder</u>

surges and harmonics.

- 7.5.6 Making, breaking and continuous capacity of the relay contacts shall be adequate enough for the circuits in which they are used.
- 7.5.7 The numerical relay shall have the following protection functions with at least two independent protection setting groups. The protection functions shall be selectable from any of the IEC characteristic curves.
- (i) Definite time (DT) phase over current protection
 - (ii) Inverse Definite Minimum Time (IDMT) phase over current protection
 - (iii) Definite time (DT) earth fault current protection
 - (iv) Inverse Definite Minimum Time (IDMT) earth fault current protection
 - (v) Under Voltage protection
 - (vi) Over Voltage protection
- 7.5.8 Transformer feeder protection relay shall have provision for the following protection functions.
- (i) Buchholz alarm & trip
 - (ii) Oil Temperature Indicator (OTI) alarm & trip
 - (iii) Winding Temperature Indicator (WTI) alarm & trip
 - (iv) Pressure Relief Valve (PRV) trip
 - (v) Magnetic Oil Gauge (MOG) alarm
- 7.5.9 All numerical relays shall have provision for measurement and storage of electrical parameters such as voltage, current, frequency, active power, reactive power etc.
- 7.5.10 The numerical relay shall be able to record faults and events in non-volatile memory.
- (i) Fault record – At least 5 recent faults including the protection function operated, operating phase(s), voltages and currents along with date and time stamp.
 - (ii) Event record – At least 200 events with date and time stamp.
- 7.5.11 The numerical relay shall have trip circuit supervision facility to monitor the circuit breaker trip circuit both in pre-trip and post-trip conditions. The relay shall also be able to provide circuit breaker monitoring, CT and VT supervision.
- 7.5.12 The numerical relay shall have self-diagnostic feature with separate output contact for indication of any internal relay failure.
- 7.5.13 The numerical relay shall have RS-232/RS-485/RJ-45/USB ports on front side for local communication with PC and on rear side for remote communication to SCADA system.
- 7.5.14 The numerical relay shall have feature for time synchronization through the SCADA System

/ networking.

- 7.5.15 The numerical relay shall be provided with backlit alphanumeric LCD to access protection settings, measurement parameters, fault and event records. Read and write access to protection settings shall be password protected.

7.6 Instrument Transformers

- 7.6.1 Instrument transformers shall be completely encapsulated cast resin type, suitable for continuous operation at the ambient temperature prevailing inside the switchgear enclosure, when the switchgear is operating at its rated load and the outside ambient temperature is 50°C.
- 7.6.2 Polarity marks shall indelibly be marked on each instrument transformer and at the lead terminals at the associated terminal block.
- 7.6.3 Voltage transformers shall be single phase units. Bus voltage transformers shall be housed in a separate panel on withdrawable truck.
- 7.6.4 HRC fuses of suitable rating shall be provided on primary side of voltage transformers. For secondary side, four pole Miniature Circuit Breakers (MCB) shall be provided.

7.7 Earthing

- 7.7.1 An earth bus made of copper or aluminium shall be provided throughout the length of the panel. It shall be bolted to the framework of each panel and brazed to each breaker earthing contact bar.
- 7.7.2 The earth bus shall have sufficient cross section to carry maximum fault current without exceeding the allowable temperature rise.
- 7.7.3 All non-current carrying conductors of the panel shall be connected to the earth bus. All joints to the earth bus shall be made through at least two bolts. Hinged doors shall be earthed through flexible earthing braid of adequate cross section. Suitable provision shall be provided at each end of the earth bus for connection with Owner's Earth conductor.
- 7.7.4 Positive earthing of the breaker truck and frame shall be maintained when it is in the connected position and in all other positions whilst the auxiliary circuits are not totally disconnected.
- 7.7.5 All metallic cases of relays, instruments and other panel mounted equipment shall be connected to earth bus by independent copper wires of size not less than 2.5 sq. mm with green colour insulation.
- 7.7.6 Instrument transformer secondary neutral point shall be earthed at one place only on the terminal block. Such earthing shall be made through links so that earthing of one circuit may

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 33 of 105</u>	<u>Signature of</u> <u>Bidder</u>

be removed without disturbing the earthing of other circuits.

7.7.7 Separate earthing trucks shall be provided for earthing of busbars and incoming/outgoing feeders. The trucks shall have voltage transformer to indicate presence of voltage prior to earthing. An audible alarm shall also be provided in case of voltage on the earthing terminal. Integral earth switches may also be considered instead of earthing trucks. The earthing truck/switch shall have short circuit withstand capability equal to that of the associated switchgear panel.

7.7.8 The interlocks shall be provided to ensure the following.

- (i) It is not possible to rack-in the earthing truck/close the earthing switch when the breaker truck is in SERVICE position.
- (ii) It is not possible to rack-in the breaker truck into SERVICE position when earthing truck is connected/earthing switch is in closed position.

7.8 Bus bar

7.8.1 Bus bar shall be made of copper or aluminium with uniform cross section throughout their length. They shall be adequately supported on insulators to withstand electrical and mechanical stresses due to specified short circuit current.

7.8.2 All bus bars joints shall be thoroughly cleaned and anti-oxide grease shall be applied. Plain and spring washers shall be provided to ensure good contacts at the joints and taps. Wherever aluminium to copper connections are required, suitable bimetallic connectors or clamps shall be used.

7.8.3 Bus bars shall be provided with heat shrinkable sleeves of suitable insulation class throughout their length with proper colour coding. All bus bar joints and taps shall be shrouded.

7.8.4 Bus bar support insulators shall be made of non-hygroscopic, arc and track resistant, high strength material suitable to withstand stresses due to over voltage and short circuit current.

7.8.5 The Contractor shall submit busbar sizing calculation for specified continuous and short time current ratings during detailed engineering.

7.9 Measuring Instruments

7.9.1 All the measuring instruments shall be digital, flush mounting type with communication facility.

7.9.2 All feeders except main outgoing feeder shall be provided with digital Multi-Function Meter (MFM). Tri Vector Meter (TVM) shall be provided for the main outgoing feeder (in the HT Panel). Accuracy class of MFM shall be 0.2 and that of TVM shall be 0.2S.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 34 of 105</u>	<u>Signature of Bidder</u>

7.9.3 Measuring instruments shall have provision to display the following parameters.

- (i) Line and phase voltages
- (ii) Line and phase currents
- (iii) Active power, Reactive power, Apparent power
- (iv) Frequency
- (v) Power factor
- (vi) Total Harmonic Distortion (THD)

7.10 Wiring and Terminal blocks

7.10.1 All internal wiring shall be done with 650 V grade, 1.5 sq.mm. PVC insulated stranded flexible copper wire. For CT secondary circuits, 2.5 sq.mm copper wire shall be used.

7.10.2 Wire terminations shall be made with solderless crimping type tinned copper lugs, which shall firmly grip the conductor. Insulation sleeves shall be provided at all the wire terminations.

7.10.3 Printed identification ferrules, marked to correspond with panel wiring diagram shall be provided at both ends of each wire. The ferrules shall be firmly located on each wire so that they cannot move or turn freely on the wire. Wire identification shall be done in accordance with IS 11353.

7.10.4 The Contractor shall be solely responsible for the completeness and correctness of the internal wiring and for the proper functioning of the connected equipment.

7.10.5 All internal wiring to be connected to the external equipment shall terminate on terminal blocks. Terminal blocks shall be rated for 650 V, 10 A and made of non-inflammable material.

7.10.6 CT and VT secondary circuits shall be terminated on stud type, non-disconnecting terminal blocks.

7.10.7 At least 10% spare terminals shall be provided on each panel and these spare terminals shall be distributed on all terminal blocks.

7.11 Warranty

The HT panel unit shall be warranted for minimum of 5 (five) years against all material/manufacturing defects and workmanship.

7.12 Approval

7.12.1 Documents/Drawings

- (i) Guaranteed Technical Particular (GTP) Datasheet
- (ii) General Arrangement (GA) Drawing and Foundation details

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 35 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- (iii) Schematic diagram
- (iv) Bus bar sizing calculation
- (v) Bill of Materials
- (vi) Quality Assurance Plan (QAP)

7.12.2 Test Certificates/ Reports

Type test reports as mentioned in the following clause shall be submitted for approval.

7.13 Testing and Inspection

7.13.1 Type Tests

The switchgear panel shall be of type tested design. The following type test reports shall be submitted during detailed engineering. The tests should have been conducted on the similar equipment by NABL accredited laboratory.

Test	Standard	Relevant IEC Clause
Switchgear Panel		
Dielectric tests		
Power frequency voltage test	IEC 62271-200	6.2.6.1
Lightning impulse voltage test	IEC 62271-200	6.2.6.2
Dielectric tests on auxiliary and control circuits	IEC 62271-200	6.2.10
Measurement of the resistance of the main circuit	IEC 62271-200	6.4.1
Temperature-rise tests	IEC 62271-200	6.5
Short-time withstand current and peak withstand current tests	IEC 62271-200	6.6
Verification of the IP coding	IEC 62271-200	6.7.1
Verification of making and breaking capacities	IEC 62271-200	6.101
Mechanical operation test	IEC 62271-200	6.102
Internal arc test	IEC 62271-200	6.106
Circuit Breaker		
Mechanical operation test at ambient air temperature (M2 Class)	IEC 62271-100	6.101.2
Basic short-circuit test-duties	IEC 62271-100	6.106
Relays		
Vibration tests	IEC 60255-21-1	

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 36 of 105	Signature of <u>Bidder</u>

Shock and bump tests	IEC 60255-21-2	
Seismic tests	IEC 60255-21-3	
Electromagnetic compatibility requirements	IEC 60255-26	
Product safety requirements	IEC 60255-27	
Common requirements	IEC 60255-1	
Functional requirements	Relevant parts of IEC 60255-100 series	
Communication requirements	IEC 61850	
Current Transformers		
Temperature-rise test	IEC 61869-2	7.2.2
Impulse voltage withstand test on primary terminals	IEC 61869-2	7.2.3
Tests for accuracy	IEC 61869-2	7.2.6
Short-time current tests	IEC 61869-2	7.2.201
Voltage Transformer		
Temperature-rise test	IEC 61869-3	7.2.2
Impulse voltage withstand test on primary terminals	IEC 61869-3	7.2.3
Electromagnetic Compatibility tests	IEC 61869-3	7.2.5
Test for accuracy	IEC 61869-3	7.2.6
Short-circuit withstand capability test	IEC 61869-3	7.2.301

In case the contractor is not able to submit the test reports during detailed engineering, the contractor shall submit the reports of type/special tests either conducted by NABL accredited laboratory or witnessed by Employer.

7.13.2 Routine Tests

Routine tests and acceptance tests shall be as per the Quality Assurance Plan (QAP) approved by the Employer.

8 AC Cables

8.1 Standards and Codes

All AC Cables shall conform to the following standards and codes.

IS 7098	Crosslinked polyethylene insulated PVC sheathed cables, Part 1: For working voltage up to and including 1100 V

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 37 of 105	Signature of Bidder

IS 7098	Crosslinked Polyethylene Insulated Thermoplastics Sheathed Cables Part 2: for Working Voltages from 3.3 kV up to and Including 33 kV

- 8.2 All AC cables shall be flame retardant, low smoke (FRLS) type designed to withstand all mechanical, electrical and thermal stresses develop under steady state and transient operating conditions.
- 8.3 Only terminal cable joints shall be accepted. No cable joint to join two cable ends shall be accepted. However, cable joints may be allowed if the route length is more than maximum available drum length subject to Employer's approval.
- 8.4 In addition to manufacturer's identification on cables as per relevant standard, following marking shall also be provided over outer sheath.
- (i) Cable size and voltage grade
 - (ii) Word 'FRLS' at every metre
 - (iii) Sequential marking of length of the cable in metres at every metre
- 8.5 Cables shall be sized based on the following considerations:
- (i) Rated current the equipment
 - (ii) Maximum voltage drop in LT cable (from inverter to inverter transformer) shall be limited to 0.5% of the rated voltage. For HT cables (from inverter transformer to interconnection point), maximum voltage drop shall be limited to 0.5 % of the rated voltage. Successful Bidder shall provide voltage drop calculations in excel sheet.
 - (iii) Short circuit withstand capability as per design for 1s.
 - (iv) De-rating factors according to laying pattern
- 8.6 Warranty
- All cables shall be warranted for minimum of 1 (one) year against all material/ manufacturing defects and workmanship.
- 8.7 Approval
- 8.7.1 Documents/Drawings
- (i) Guaranteed Technical Particular (GTP) Datasheet
 - (ii) Cable sizing calculation
 - (iii) Quality Assurance Plan (QAP)
- 8.7.2 Test Certificates/ Reports
- Type test certificates as per the standards mentioned above shall be submitted for approval.
- 8.8 Testing

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 38 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Routine test and acceptance tests requirements shall be as per relevant standards for all cable sizes.

8.9 Installation

8.9.1 Cable installation shall be as per IS 1255.

8.9.2 LT cable (from inverter to inverter transformer) shall laid through RCC cable trench with supports.

8.9.3 Cable terminations shall be made with properly crimped lugs and passed through cable glands at the entry & exit point of the cubicles. Bimetallic lugs shall be used for connecting Cu bus bar and Al cables or vice-versa.

8.9.4 All AC cables shall be provided with punched/embossed aluminium tags. The marking shall be done with good quality letter and numbers of proper size so that the cables can be identified easily.

9 Auxiliary supply system

9.1 Scheme for Auxiliary supply system shall be submitted by contractor during detailed engineering for the approval by Employer.

9.2 It shall mainly comprise of auxiliary transformer, AC distribution board(s) (ACDB), Battery & battery charger system, emergency lighting network, Uninterrupted power supply (UPS), distribution cables and metering & protective devices.

9.3 Following consideration shall be taken into account while sizing the auxiliary transformer:

- (i) 20% future load margin
- (ii) 20% design margin
- (iii) Total connected load at 0.8 power factor

10 Distribution Switchgear

10.1 Standards and Codes

All equipment provided under distribution switchgear shall comply with latest revisions and amendments of the relevant IEC standards and IS codes. In particular, the switchgear shall comply with the following standards and codes.

Standard/Code	Description
IEC 61439-1	Low-voltage switchgear and control gear assemblies - Part 1: General rules
IEC 61439-2	Low-voltage switchgear and control gear assemblies - Part 2: Power switchgear and control gear assemblies
IEC 60947-1	Low-voltage switchgear and control gear - Part 1: General rules

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 39 of 105</u>	<u>Signature of</u> <u>Bidder</u>

IEC 60947-2	Low-Voltage Switchgear and Control gear: Circuit Breakers
IEC 60947-3	Low voltage switchgear and control gear: Part 3 Switches, disconnectors, switch-disconnectors and fuse combination units
IEC 60947-4-1	Low-voltage switchgear and control gear - Part 4-1: Contactors and motor-starters - Electromechanical contactors and motor-starters
IEC 60947-5-1	Low-voltage switchgear and control gear - Part 5-1: Control circuit devices and switching elements - Electromechanical control circuit devices
IEC 62052-11	Electricity metering equipment (a.c.) - General requirements, tests and test conditions - Part 11: Metering equipment
IS 694	Polyvinyl chloride insulated unsheathed-and sheathed cables/ cords with rigid and--flexible conductor for rated voltages--up to and including 450/750V
IEC 61869	Instrument Transformers
IS 3043	Code of practice for earthing
IEC 60255	Measuring relays and protection equipment - Part 1: Common requirements

10.2 Technical Parameters

System Details	
Rated system voltage	415V+10%,3 Phase, 50Hz, 4 wire , Neutral Solidly Earthed
Digital Multifunctional Meter (MFM)	
Accuracy class	0.5 class for main distribution board at main control room and 0.5 class for DB at inverter room(s)
Communication with SCADA	RS485 communication with Modbus RTU
Current transformer (CT)	
Type	Cast Resin Bar Primary
Voltage class and frequency	650V, 50Hz
CT Secondary Current	1 A
Class of insulation	E or better
Accuracy class & burden	
a) For Protection	5P20, 5VA PS Class for REF and core balance CT (CBCT)
b) For Metering	Class 0.5, 5VA (min)
Minimum primary earth fault current to be detected by CBCT	1 A

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 40 of 105</u>	Signature of <u>Bidder</u>

Instrument Security Factor for metering CT	5
Voltage transformer (VT)	
Type	Cast Resin
Accuracy class	0.5
Rated Voltage factor	1.1 continuous, 1.5 for 30 seconds
Class of insulation	E or better
Moulded case circuit breaker (MCCB)	
Rated voltage	415V
Release	Thermal-Magnetic/Microprocessor
Rated current	As per system requirement
Poles	4 poles
Rated insulation level	690V
Rated ultimate and service short circuit breaking Capacity	As per system requirement
Rated Making capacity (as per system requirement)	2.1 X Short circuit breaking Capacity
Utilization category	A

10.3 Constructional Details

- 10.3.1 The panel shall be metal enclosed, free standing, floor mounted, modular type with compartmentalized construction having degree of protection of IP 54 as per IS 2147. All doors and covers shall be provided with neoprene gaskets to prevent entry of vermin and dust.
- 10.3.2 All switches, push buttons etc. shall be operated front and shall be flush/semi-flush mounted.
- 10.3.3 The panel shall be fabricated from 2 mm CRCA sheet steel for frame & load bearing surfaces. Partitions may be fabricated from 1.6 mm CRCA if no components are mounted on them.
- 10.3.4 Cable entries shall be from bottom. The opening of cable entry shall be covered by 3mm thick gland plates with proper sealing to avoid water and rodent entry.
- 10.3.5 Earthing bus bar of suitable cross section shall be provided throughout the length of panel.
- 10.3.6 The panel shall be duly wired with suitable size of 1.1kV, PVC insulated cable and terminals shall be brought out for cable connections. 10% spare terminals subjected to minimum one

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 41 of 105</u>	<u>Signature of Bidder</u>

of each rating shall be provided on each distribution switchgear. All wire shall have ferrules as per wiring diagram.

10.3.7 The panel shall be painted with 2 coats of primer after pre-treatment and 2 coats of Polyurethane / epoxy paint with shade as decided by the Owner.

10.3.8 The panel shall be of dead front construction suitable for front operated and back maintained functioning.

10.3.9 240 V, 15 A, 3 pin industrial socket-outlet with ON/OFF switch shall be provided in each panel.

10.3.10 Each panel shall be provided with LED lamp rated for 240 V, 50 Hz, single phase AC supply for interior illumination controlled by door switch.

10.3.11 Suitable lifting hooks shall be provided for each panel.

10.3.12 Each switchgear panel shall be provided with thermostatically controlled space heaters to prevent condensation within the enclosure. The space heater shall be connected to 240 V, 50 Hz, single phase AC supply through suitable switch and fuse.

10.3.13 Earth leakage relay with Core balance CTs (CBCT) shall be provided on main incoming feeders having phase CT ratio more than 50/1A. CBCT's shall be circular window type with window size based on the overall diameter of the cables, to be finalized during detailed engineering.

10.4 Warranty

Distribution panels (ACDB and DCDB) shall be warranted for minimum of 1 (one) year against all material/ manufacturing defects and workmanship

10.5 Approval

Schematic diagram and General Arrangement (GA) drawing shall be submitted for approval.

10.6 Testing

Routine test and acceptance tests requirements shall be as per relevant standards for all cable sizes.

11 **Uninterrupted Power Supply (UPS)**

11.1 Standards and Codes

Standard/Code	Description
IEC 62040-1	Uninterruptible power systems (UPS) - Part 1: General and safety requirements for UPS
IEC 62040-2	Uninterruptible power systems (UPS) - Part 2: Electromagnetic compatibility (EMC) requirements

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 42 of 105</u>	<u>Signature of Bidder</u>

IEC 62040-3	Uninterruptible power systems (UPS) - Part 3: Method of specifying the performance and test requirements

11.2 General Requirements

11.2.1 The Uninterrupted Power Supply (UPS) system shall be designed to supply power to following loads (but not limited to).

- (i) Data logger / SCADA
- (ii) Fire Detection/ Alarm Panel
- (iii) HMI of SCADA
- (iv) Emergency Lighting
- (v) Inverter's Auxiliary supply (if applicable)
- (vi) HT panel auxiliary
- (vii) CCTV

11.2.2 Sizing of UPS shall be done considering the above-mentioned load at power factor of 0.8 lagging inclusive of 10% design margin at 50 °C.

11.3 System Description

11.3.1 The UPS shall automatically provide continuous, regulated AC power to critical loads under normal and abnormal conditions, including loss of input AC power. The UPS system shall consist of the following major equipment.

- (i) UPS Module
 - (a) Insulated Gate Bipolar Transistor (IGBT) Converter
 - (b) Insulated Gate Bipolar Transistor (IGBT) Inverter
 - (c) Digital Signal Processor (DSP) using Pulse Width Modulation (PWM) for Direct Digital Control (DDC) of all UPS control and monitoring functions
 - (d) Static bypass switch
- (ii) Battery system for 2 hours
- (iii) Battery protective and disconnect device
- (iv) Maintenance bypass switch
- (v) LCD display panel and LED indications
- (vi) Integrated UPS Communications Protocols capable of communicating with SCADA system

11.3.2 The UPS shall meet the following minimum specifications.

Parameter	Specification
Topology	Online double conversion UPS

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 43 of 105	Signature of Bidder

Input	
Voltage	415V $\pm$ 10% AC
Frequency	50 $\pm$ 5 Hz
Power factor	0.95
Output	
Voltage	230V $\pm$ 1% AC
Frequency	50 Hz
Power factor	0.8
Battery	
Type	Sealed, Maintenance-Free (AGM) battery
Capacity	100% UPS load for 2 hours
Monitoring and communication	
LED Indicators	Load on Inverter, Battery operation, Load on Bypass, Overload, LCD Fault, UPS Fault
Electrical contacts	Closing contacts for each of the following conditions: 1. Unit on Battery 2. Low Battery 3. Summary Alarm 4. UPS On 5. Input Fail
Local Display	LCD/ LED
SCADA communications	RS-232 & RS-485 Interface Port
Overall efficiency	>90%
Electrical Protection	Input/ output under voltage, over temperature, overload, Short circuit, battery low trip

11.3.3 The UPS shall be forced air cooled by internally mounted fans. The fans shall be redundant in nature to ensure maximum reliability. The fans shall be easily replaceable without the use of special tools.

11.3.4 Contractor shall provide the Operation & Maintenance Manual and mandatory spare parts list along with the equipment

11.4 Warranty

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 44 of 105</u>	<u>Signature of Bidder</u>

UPS shall be warranted for minimum of 5 (five) years and batteries shall be warranted for a minimum of 2 (two) years against all material/ manufacturing defects and workmanship

11.5 Approval

11.5.1 Documents/Drawings

- (i) Technical Datasheet
- (ii) UPS sizing calculation
- (iii) Single line diagram
- (iv) General Arrangement (GA) drawing
- (v) Quality Assurance Plan

11.5.2 Test Certificates/Reports

Type test certificates as per the standards mentioned above shall be submitted for approval.

11.6 Tests

11.6.1 Routine tests and acceptance tests on final product shall be done as per QAP approved by the Employer.

11.6.2 On completion of installation and commissioning of the equipment on site tests shall be carried out with the max. available load, which does not exceed the rated continuous load. An on-site test procedure shall be submitted by contractor include a check of controls and indicators after installation of the equipment.

12 **Battery and Battery Charger**

12.1 Standards and Codes

Standard/Code	Description
IEC 60896-22:2004	Stationary lead-acid batteries - Part 22: Valve regulated types - Requirements
IEC 60896-21:2004	Stationary lead-acid batteries - Part 21: Valve regulated types - Methods of test
IS 1652	Specification for stationary cells and batteries, lead acid type (with plante positive plates)
IS 8320	General requirements and methods of tests for lead acid storage batteries.
IS 15549	Stationary Regulated Lead Acid Batteries

12.2 General

110 V DC system (Battery, Battery Charger & DCDB) in accordance with this specification and standards stated herein, shall comprise of the following.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 45 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- (i) Sealed Maintenance Free (VRLA) Battery complete with racks & accessories.
- (ii) One No. Float charger.
- (iii) One No. Float cum Boost charger.
- (iv) DC Distribution Board (DCDB)

12.3 Battery

12.3.1 Battery shall be used to supply the following loads with back up of two hours in case of complete power failure:

- (i) Trip and closing coil of HT circuit breaker
- (ii) Spring charging motors for HT circuit breaker
- (iii) Annunciator and Indication circuit of HT panel
- (iv) Auxiliary supply to protection relays

12.3.2 The battery sizing shall account for suitable temperature correction factors, ageing factors of 1.25, design margin of 1.25 & depth of discharge of 80%.

12.3.3 The design of the battery bank and sizing calculation along with the data sheet for the battery and battery charger shall be submitted for approval.

12.3.4 Battery voltage – 220V dc or 110V dc

12.4 Battery charger

12.4.1 The Float Charger shall be used to supply normal DC loads and float charging current of charged battery. The Float cum Boost charger shall be designed to supply boost charging current requirement of the associated battery as well as to supply normal DC load. After full discharge of battery bank, the Float Cum boost charger shall be capable of charging the battery to its full capacity in 8 hours duration while supplying normal DC load.

12.4.2 The float charger shall have both auto and manual voltage regulation arrangements with provision of selector switch.

12.4.3 Suitable filter circuits shall be provided in all the chargers to limit the ripple content (peak to peak) in the output voltage and current to 2 % and 5 % respectively.

12.4.4 Digital Outputs shall be configured for connection to the SCADA to monitor the outputs like charger output current, output voltage, float/boost mode, etc.

12.4.5 The charging equipment shall be housed in a free standing, floor mounted compartmentalized panels. Panel shall have provision for bottom cable entry with removable undrilled cable gland plate of 3.0 mm thickness.

12.4.6 The panel shall be of CRCA sheet steel construction having thickness of at least 2.0 mm. Degree of protection provided by the enclosure to the internals of charger shall be IP-42.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 46 of 105</u>	<u>Signature of</u> <u>Bidder</u>

12.4.7 The instruments, switches and indicating lamps shall be flush mounted on the front panel.

12.5 DC distribution board (DCDB)

12.5.1 DCDB shall be a separate panel, but shall form an integral part of a battery charger panel board.

12.5.2 Doors and covers shall be provided with neoprene gaskets to prevent entry of vermin and dust. Also, door shall be provided with lock and key arrangement to prevent unauthorized access to the board.

12.5.3 DCDB shall have adequate number of outgoing feeders with double pole, DC MCBs. At least 20% feeders shall be provided as spare.

12.6 Warranty

Batteries and battery charger shall be warranted for minimum of 2 (two) years against all material/ manufacturing defects and workmanship.

12.7 Approval

12.7.1 Documents/Drawings

- (i) Technical Datasheet
- (ii) Battery sizing calculation

12.7.2 Test Certificates/Reports

Type test certificates as per the standards mentioned above shall be submitted for approval.

12.8 Tests

Routine tests and acceptance tests shall be as per the Quality Assurance Plan (QAP) approved by the Employer.

13 **Metering System**

13.1 Standards and Codes

Standard/Code	Description
IEC 62052-11:2003	Electricity metering equipment (AC) - General requirements, tests and test conditions - Part 11: Metering equipment
IEC 62053-22:2003	Electricity metering equipment (AC) - Particular Requirements - Part 22: Static meters for active energy (classes 0,2 S and 0,5 S)
IS 14967	AC Static Transformer Operated Watthour and Var-hour Meters, Class 0.2 S and 0.5 S

13.2 ABT energy meter shall be provided as approved by state DISCOM under the metering scheme, to measure the delivered quantum of energy to the grid for sale. The responsibility of arranging for the meter, its inspection/ calibration/ testing charges etc. rests with the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 47 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Contractor. All charges incurred on Meter testing, shall be borne by the Contractor. ABT energy metering system is to be approved by state DISCOM.

- 13.3 Meter must be provided with the necessary data cables.
- 13.4 The Contractor shall provide ABT compliant meters at the interface points.
- 13.5 Interface metering shall conform to the CEA (Installation and Operation Meters) Regulation 2006 and amendment thereof Commercial settlement of solar Photovoltaic Grid Interactive based power project.
- 13.6 Meter shall be suitable for interfacing for synchronizing the built-in clock of the meter by GPS time synchronization equipment existing at the station either through a synchronization pulse received from the time synchronization equipment or through a remote PC synchronized to GPS clock shall also be in the scope of Contractor.
- 13.7 All charges for testing and passing of the meter with relevant government agency shall be borne by Contractor, the Employer will assist Contractor for necessary document as and when required. Contractor has to intimate the required documents at least 7 days prior of such requirements.
- 13.8 ABT compliant Energy Meters shall have technical specification as given below (not limited to specified requirement, Contractor can provide Meter with latest facilities).
 - 13.8.1 Meters shall carry out measurement of active energy (both import and export) and reactive energy (both import and export) by 3-phase, 4-wire principle suitable for balanced/unbalanced 3 phase load.
 - 13.8.2 Meters shall have an accuracy of energy measurement of at least Class 0.2S for active energy and at least Class 0.5 for reactive energy, and shall be connected to Class 0.2 CT cores and Class 0.2 VT windings or as per state grid regulations. The active and reactive energy shall be directly computed in CT & VT primary ratings.
 - 13.8.3 Meters shall compute the net MWh and MVARh during each successive 15-minute block metering interval along with a plus/ minus sign, instantaneous net MWh, instantaneous net MVARh, average frequency of each 15 minutes, net active energy at midnight, net reactive energy for voltage low and high conditions at each midnight.
 - 13.8.4 Each energy meter shall have a seven digit display unit. It shall display the net MWh and MVARh with a plus/minus sign and average frequency during the previous metering interval; peak MW demand since the last demand reset; accumulated total (instantaneous) MWh and MVARh with a plus/minus sign, date and time; and instantaneous current and voltage on each phase.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 48 of 105</u>	<u>Signature of</u> <u>Bidder</u>

13.8.5 All the registers shall be stored in a non-volatile memory. Meter registers for each metering interval, as well as accumulated totals, shall be downloadable. All the net active/reactive energy values displayed or stored shall be with a plus /minus sign for export/import.

13.8.6 At least the following data shall be stored before being over-written for the following parameters.

S. No.	Parameters	Details	Min. No. of days
1	Net MWh	15 min. block	90 days in meter
2	Average Frequency	15 min. block	90 days in meter
3	Net MVARh for > 103%	15 min. block	90 days in meter
4	Cumulative net MWh	At every mid night	30 days in meter/ 90 days in PC
5	Cumulative net MVARh for >103%	At every mid night	30 days in meter/ 90 days in PC
6	Date & time blocks for VT failure on any phase		

13.8.7 The meter shall have a built in clock and calendar with an accuracy of less than 15 seconds per month drift without assistance of external time synchronizing pulse.

13.8.8 Date/time shall be displayed on demand. The clock shall be synchronized by GPS time synchronization equipment existing at the station provided by Contractor.

13.8.9 The meter shall be suitable to operate with power drawn from the VT supplies. The burden of the meters shall be less than maximum 2VA.

13.8.10 The power supply to the meter shall be healthy even with a single- phase VT supply. An automatic backup, in the event of non-availability of voltage in all the phases, shall be provided by a built in long life battery and shall not need replacement for at least 10 years with a continuous VT interruption of at least 2 years. Date and time of VT interruption and restoration shall be automatically stored in a non-volatile memory.

13.8.11 Even under the absence of VT input, energy meter display shall be available and it shall be possible to download data from the energy meters.

13.8.12 Meters shall have an optical port on the front of the meter for data collection from either a hand held meter reading instrument (MRI) having a display for energy readings or from a notebook computer with suitable software.

13.8.13 The meter shall have means to test MWh and MVARh accuracy and calibration at site in-situ and test terminal blocks shall be provided for the same.

13.9 The Employer/ Owner shall have the right to carry out surprise inspections of the Metering

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 49 of 105</u>	<u>Signature of Bidder</u>

Systems from time to time to check their accuracy.

13.10 The Contractor must comply with the relevant grid regulations, DISCOM's, State TRANSCO's & CEA's guidelines with respect to all the works corresponding to power evacuation, transmission, termination along with metering at DISCOM's substation.

14 Earthing

14.1 Standards and Codes

Earthing system shall comply with latest revisions and amendments of the relevant IEC standards and IS codes. In particular, earthing system shall comply with the following standards and codes.

Standard/Code	Description
IS 3043	Code of Practice for Earthing
IEEE 80	IEEE Guide for Safety in AC Substation Grounding
IEEE 142	IEEE Recommended Practice for Grounding of Industrial and Commercial Power Systems
Indian Electricity Rules	

14.2 General Requirements

14.2.1 Earthing system shall be designed based on system fault current and soil resistivity value obtained from geo-technical investigation report. Earth grid shall be formed consisting of number of earth electrodes sufficient enough to dissipate the system fault current interconnected by earthing conductors.

14.2.2 The earth electrode shall be made of high tensile low carbon steel rod, molecularly bonded by high conductivity copper on outer surface with coating thickness not less than 250 micron as per relevant standards. Suitable earth enhancing material shall be filled around the electrode to lower the resistance to earth. Inspection chamber and lid shall be provided as per IS 3043.

14.2.3 Earth conductors shall be made of copper bonded steel or galvanized steel of sufficient cross section to carry the fault current and withstand corrosion.

14.2.4 Earth conductors buried in ground shall be laid minimum 600 mm below ground level unless otherwise indicated in the drawing. Back filling material to be placed over buried conductors shall be free from stones and harmful mixtures. Earthing conductor shall be buried at least 2000 mm outside the fence of electrical installations.

14.2.5 Earth electrodes shall not be situated within 1.5m from any building whose installation system is being earthed. Minimum distance between earth electrodes shall be the driven

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 50 of 105</u>	Signature of <u>Bidder</u>

depth of the electrode.

14.2.6 Every alternate post of the transformer yard and switchyard fence shall be connected to the earth grid by one GS flat and gates by flexible lead to the earthed post.

14.2.7 All welded connections shall be made by electric arc welding. For rust protection the welds should be treated with red lead compound and afterwards thickly coated with bitumen compound.

14.3 Earthing of PV array field

14.3.1 All PV Modules, Module Mounting Structures (MMS) and String Monitoring Unit (SMU) structures in the PV array field shall be bonded to the earthing system by two distinct connections.

14.3.2 Each PV Module frame shall be earthed using copper wire of sufficient cross section. The copper wire shall be connected to the earth hole provided in the module frame using suitable arrangement in line with the manufacturer recommendation. The earthing arrangement shall use stainless washers to prevent galvanic corrosion between aluminium frame and copper wire. In order to achieve effective earthing, serrated washers shall be employed to penetrate the anodization layer of the module frame.

14.3.3 Continuous copper earthing wire shall be run to connect a group of modules and both ends of the loop shall be bolted to the DC earth grid using bimetallic lugs and stainless-steel fasteners. The copper earthing wire shall be routed in such a way to avoid physical contact with the module aluminium frame.

14.3.4 The connection between MMS and DC earth grid shall be bolted or welded. Portion of the MMS which undergoes welding at site shall be coated with two coats of cold galvanising and anti-corrosion paint afterwards.

14.3.5 Earth electrodes of the DC earth grid shall be uniformly distributed throughout the PV array field so that optimum earth resistance is offered to leakage current flowing from any module frame or MMS.

14.3.6 SMU equipment earthing point shall be connected to the DC earth grid using flexible copper cable of sufficient cross section as recommended by the manufacturer. The connection with the DC earth grid shall be done using suitable bimetallic lugs and stainless-steel fasteners.

14.4 PCU Earthing

DC negative bus bar of the PCU shall be earthed to avoid Potential Induced Degradation (PID). DC negative bus bar and PCU equipment earth shall be bonded to the PCU earth bus and connected to earth electrodes through flexible copper cable of sufficient cross section as

mentioned by the manufacturer. The interconnection of PCU earth electrodes with DC earth grid shall be as per PCU manufacturer recommendation.

14.5 Transformer Earthing

14.5.1 Inverter transformer neutral shall be floating, not to be earthed. Transformer tank, cable box, marshalling box and all other body earth points shall be earthed.

14.5.2 Inverter transformer shield shall be earthed separately using minimum two no. of earth electrodes. Earthing conductor between shield bushing and earth electrodes shall be copper flat of suitable size not less than 25 x 6 mm.

14.5.3 Neutral and body of the auxiliary transformer shall be earthed.

14.6 Inverter Room and Main Control Room Earthing

14.6.1 Metallic enclosure of all electrical equipment inside the inverter room and main control room shall be connected to the earth grid by two separate and distinct connections.

14.6.2 Cable racks and trays shall be connected to the earth grid at minimum two places using galvanized steel flat.

14.6.3 SCADA and other related electronic devices shall be earthed separately using minimum two no. of earth electrodes.

14.7 Switchyard Earthing

The metallic frame work of all switchyard equipment and support structures shall be connected to the earth grid by means of two separate and distinct connections.

14.8 Approval

14.8.1 Documents/ drawings

- (i) Technical datasheet
- (ii) Earthing Design calculation

14.9 Tests

On completion of installation, continuity of earth conductors and efficiency of all bonds and joints shall be checked. Earth resistance at earth terminations shall be measured and recorded.

15 **Lightning Protection System**

15.1 Lightning Protection System for entire plant against direct lightning strokes shall be provided with Early Streamer Emission (ESE) Air Terminal as per NFC 17-102:2011.

15.2 Protection Level for the entire plant shall be level – I.

15.3 Each ESE air terminal shall be provided with following accessories.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 52 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- (i) Highly insulated poly-plastic adaptor to fix the ESE air terminal with the FRP mast
 - (ii) Fiberglass Reinforced Plastic (FRP) mast
 - (iii) Coupler to connect FRP mast with GI mast
 - (iv) Galvanized Iron mast with base plate and guy wire kit
 - (v) Down-conductor: PVC insulated flexible copper cable of suitable size complying with EN 50164-2 or equivalent standard. It shall be routed along the mast with suitable fixings and connectors
 - (vi) Test joint with each down conductor
 - (vii) Lightning event counter complying with EN 50164-6 or equivalent standard. It shall be fixed at suitable height in series with the down conductor.
 - (viii) Earth termination system in accordance with NFC 17-102. Earth electrodes shall comply with the EN 50164-2 or equivalent standard. Earth enhancing compounds complying with EN 50164-7 or equivalent standard, may be used where soil resistivity is higher and making it impossible to achieve system resistance within specified limit.
- 15.4 Accessories listed above are indicative only and any other fittings or accessories, which are usual or necessary for satisfactory operation of the lightning protection shall be provided by the Contractor without extra charges.
- 15.5 Necessary foundation/anchoring for holding the lightning mast in position to be made after giving due consideration to shadow on PV array, maximum wind speed and maintenance requirement at site in future.
- 15.6 The product shall be warranted for minimum of 2 (two) years against all material/ manufacturing defects and workmanship.
- 15.7 Type test reports as per NFC 17-102:2011 shall be submitted during detailed engineering for approval.

16 Communication Cables

16.1 Optical Fibre Cables

- 16.1.1 Optic Fibre cable shall be 4/8/12 core, galvanized corrugated steel taped armoured, fully water blocked with dielectric central member for outdoor/ indoor application so as to prevent any physical damage.
- 16.1.2 The cable shall have multiple single-mode or multimode fibres on as required basis so as to avoid the usage of any repeaters.
- 16.1.3 The outer sheath shall have Flame Retardant, UV resistant properties and are to be identified with the manufacturer's name, year of manufacturing, progressive automatic

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 53 of 105</u>	<u>Signature of</u> <u>Bidder</u>

sequential on-line marking of length in meters at every meter on outer sheath.

- 16.1.4 The cable core shall have suitable characteristics and strengthening for prevention of damage during pulling.
- 16.1.5 All testing of the optic fiber cable being supplied shall be as per the relevant IEC, EIA and other international standards.
- 16.1.6 The Contractor shall ensure that minimum 100% cores are kept as spare in all types of optical fibre cables.
- 16.1.7 Cables shall be suitable for laying in conduits, ducts, trenches, racks and underground buried installation.
- 16.1.8 Spliced/ Repaired cables are not acceptable. Penetration of water resistance and impact resistance shall be as per IEC standard.

16.2 Communication Cable (Modbus)

- 16.2.1 Data (Modbus) Cable to be used shall be shielded type with stranded copper conductor. Cable shall have minimum 2 pair each with conductor size of 0.5 Sq.mm. Cable shall be flame retardant according to IEC 60332-1-2.
- 16.2.2 Cable shall be tested for Peak working voltage of not less than 300 V and shall be suitable for serial interfaces (RS 422 and RS 485).

17 **SCADA**

17.1 General Requirements

- 17.1.1 The Contractor shall provide complete SCADA system with all accessories, auxiliaries and associated equipment and cables for the safe, efficient and reliable operation of entire solar plant and its auxiliary systems.
- 17.1.2 The Contractor shall provide all the components including, but not limited to, Hardware, Software, Panels, Power Supply, HMI, Laser Printer, Gateway, Networking equipment and associated Cables, firewall etc. needed for the completeness.
- 17.1.3 SCADA System shall have the provision to perform the following functions.
- (i) Real-time acquisition and display of data, status, alarms and trends.
 - (ii) Display of status of major equipment in Single Line Diagram(SLD) format with string level monitoring capability
 - (iii) Display and storage of measured values
 - (iv) Display and storage of derived/ calculated/ integrated values
 - (v) Generate, store and retrieve user configurable Sequence of Event (SOE) Reports

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 54 of 105</u>	<u>Signature of</u> <u>Bidder</u>

(vi) Remote monitoring of essential parameters on the web using standard modem (Internet connection for transferring data to web shall be taken by Contractor in the name of Employer for O&M period).

17.1.4 It shall be possible to remove/ replace redundant controller or various modules (like any I/O module, interface module, etc.) from its slot for maintenance purpose without switching off power supply to the corresponding rack without releasing any spurious signal to controller and causing disturbance or loss of controller functions for other controller.

17.1.5 The Control system shall be designed to operate in non-air-conditioned area. However, the Contractor shall provide a Package/ Split AC of suitable capacity decided by heat load requirement in SCADA room at Main Control Room.

17.2 Programmable Logic based control system at Main Control Room

17.2.1 Bidder shall provide PLC based SCADA at Main Control Room. For other locations such as Inverter room, Sub Pooling Switchgear Room (if applicable) bidder may offer IO modules/ RTU/ PLC for completeness of SCADA.

17.2.2 PLC Processor

The processor unit shall be capable of executing the following functions.

- (i) Receiving binary and analog signals from the field to server.
- (ii) Implementing all logic functions for protection and annunciation of the equipment and systems.
- (iii) Providing supervisory information for alarm, various types of displays, status information, trending, historical storage of data etc.

17.2.3 The SCADA shall be OPC version 2.05a compliant and implement an OPC- DA 2.05a server as per the specification of OPC Foundation. All data should be accessible through this OPC server. SCADA shall have OPC connectivity for other systems.

17.3 Human Machine Interface System (HMIS)

17.3.1 Graphical Interface Unit (GIU) / Operator work station (OWS) shall perform monitoring and operation of all devices interacting with PLC based system.

17.3.2 The system shall have built-in safety features that will allow/ disallow certain functions and entry fields within a function to be under password control to protect against inadvertent and unauthorized use of these functions. The system security shall contain various user levels with specific rights as finalized by the Employer during detailed engineering. However, no. of user levels, no. of users in a level and rights for each level shall be changeable by the programmer (Administrator).

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 55 of 105</u>	<u>Signature of</u> <u>Bidder</u>

17.3.3 Bidder has to provide suitable hardware and software based firewall for network security to restrict unauthorized access to HMI/Solar SCADA PCs and system.

17.4 Programming Functionalities

Programming of the PLC Processor / controller as well as programming of HMIS shall be user friendly with graphical user interface. All programming functionalities shall be password protected to avoid unauthorized modification.

17.5 Software Requirements

17.5.1 All necessary software required for implementation of control logic, operator station displays / logs, storage & retrieval and other functional requirement shall be provided.

17.5.2 Industry standard operating system like WINDOWS (latest version) etc. to ensure openness and connectivity with other system in industry shall be provided. SCADA system shall support following standard protocols (included but not limited to) to communicate with different sub system/Devices:

- (i) Modbus (TCP/IP, RTU, ASCII)
- (ii) Sub Station Protocol like IEC-61850
- (iii) IEC 60870 – 5 – 101/ 104
- (iv) Any other protocol on which the offered equipment (by Contractor) will communicate with SCADA.

17.5.3 The Contractor shall provide software locks and passwords to Employer for all operating & application software. Also, the Contractor shall provide sufficient documentation and program listing so that it is possible for the Employer to carry out modification at a later date.

17.6 System Spare Capacity

17.6.1 Over and above the equipment and accessories required to meet the fully implemented system as per specification requirements, Control System shall have spare capacity of 10% along with the necessary hardware/equipment/accessories to meet the future expansion requirement.

17.7 Data Communication System (DCS)

The DCS shall have the following minimum features.

17.7.1 Redundant communication controllers shall be provided to handle the communication between I/O Modules (including remote I/O) and PLCs and between PLCs and operator work station.

17.7.2 The design shall be such as to minimize interruption of signals. It shall ensure that a single

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 56 of 105</u>	Signature of <u>Bidder</u>

failure anywhere in the media shall cause no more than a single message to be disrupted and that message shall automatically be retransmitted. Any failure or physical removal of any station/module connected to the system bus shall not result in loss of any communication function to and from any other station/module.

17.7.3 Built-in diagnostics shall be provided for easy fault detection. Communication error detection and correction facility (ECC) shall be provided at all levels of communication. Failure of one bus and changeover to the standby system bus shall be automatic and completely bump less and the same shall be suitably alarmed/logged.

17.7.4 Data transmitting speed shall be sufficient to meet the responses of the system in terms of displays, control etc. plus 20% spare capacity shall be available for future expansion.

17.7.5 Contractor shall employ redundant Fiber optic backbone for data communication between Inverter rooms and main control room.

17.7.6 The Contractor shall furnish details regarding the communication system like communication protocol, bus utilization calculations etc.

17.8 Operator Interface Displays/Logs/Reports

Suitable Operator Interface Displays/Logs/Reports for control operation & monitoring shall be provided. The details shall be furnished and finalized during detailed engineering stage.

17.9 Historical Storage and Retrieval System (HSRS)

17.9.1 The HSRS shall collect, store and process system data from man-machine interface system and plant information system (MMIPIS) data base. The data shall be saved online on hard disk and automatically transferred to erasable long-term storage media once in every 24 hours periodically for long term storage. Provision shall be made to notify the operator when hard disk is certain percentage full. The disk capacity shall be sufficient to store at least seven days data.

17.9.2 The data to be stored in the above system shall include alarm and event list, periodic plant data, selected logs/reports. The data/information to be stored and frequency of storage and retrieval shall be finalised during detail engineering stage.

17.10 Control and Power Supply Scheme

Contractor shall provide the UPS/DC Power supply of suitable rating to cater all the load requirements of SCADA system and its auxiliaries. The power backup for the entire system should be at least for 02 hours.

17.11 Control Cabinets / Panels / Desks at Main Control Room

17.11.1 The cabinets shall be IP-22 protection class. The Contractor shall ensure that the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 57 of 105</u>	<u>Signature of</u> <u>Bidder</u>

temperature rise is well within the safe limits for system components even under the worst condition and specification requirements for remote I/O cabinets.

- 17.11.2 The cabinets shall be totally enclosed, free standing type and shall be constructed with minimum 2 mm thick steel plate frame and 1.6 mm thick CRCA steel sheet or as per supplier's standard practice for similar applications.

17.12 Software Licences

The Contractor shall provide software license for all software being used in Contractor's System. The software licenses shall be provided for the project and shall not be hardware/machine-specific.

17.13 Hardware at Main Control Room

- 17.13.1 The Hardware as specified shall be based on latest state of the art Workstations and Servers and technology suitable for industrial application & power plant environment.
- 17.13.2 All the peripherals shall conform to the following minimum requirement but the exact make & model shall be as approved by Employer during detailed engineering. The LAN to be provided shall support TCP/IP protocol (Ethernet connectivity) with OPC RDI for interface with PLCs/other systems and shall have data communication speed of min. 100 Mbps. All network components of LAN and Workstations shall be compatible to the LAN, without degrading its performance.

Processor	64 Bit
Hard disk	1 TB - RAID 1
Memory	8 GB RAM upgradable to 16 GB
Monitor	Min 22" LED Flat Monitor with non-interfaced refresh rate min. 75 Hz. Communication port-2 Serial bus, one parallel Dual 10/100/1000 Mbps. Ethernet Graphic Memory=16 MB Expansion slot=3
Screen display unit	Min 50" LED Flat Monitor with wall mounted arrangement for the display of SCADA screen
Removable bulk storage drive (DVD / DAT)	6 GB (minimum)
Removable Bulk Storage Media for above (with each server/ work-station)	10 nos.
DVD R/W	16x or higher
Intelligent UPS (on line) with remote monitoring for each workstation/ server	1 no. with 30 mins. Battery backup on machine load

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 58 of 105</u>	<u>Signature of Bidder</u>

Keyboard	ASCII
Pointing Device	Mouse
Colour Laser Printer	Heavy duty type with resolution of 600 dpi Resolution

17.14 Factory Acceptance Test (FAT)

FAT procedure shall be submitted by bidder for approval. SCADA shall communicate with all third devices which are part of solar plant and same shall be demonstrated during the FAT.

18 **Illumination**

18.1 Standards and Codes

LED luminaires shall be tested at independent laboratory as per the following test standards.

Standard/Code	Description
LM79-08	Electrical and Photometric Measurements of Solid-State Lighting Products
LM 80-15:	Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays and Modules

18.2 General specification

18.2.1 This specification covers design, supply and installation of uniformly Illumination system along the peripheral & internal roads, main control room & inverter rooms, switchyard and other facilities including entry points/gate(s) inside the plant area.

18.2.2 All indoor LED luminaires shall be supplied with proper diffuser to avoid direct visibility of LED with thermal management for longer life.

18.2.3 The contractor shall furnish Guaranteed Technical Particulars of the LED luminaires, from renowned brands available in the market for approval of Employer.

18.2.4 All outdoor lighting system shall be automatically controlled by synchronous timer or photocell. Provision to bypass the timer or photocell shall be provided in the panel.

18.2.5 Lighting system shall work on the auxiliary supply and same shall be incorporated in auxiliary loads. Contractor shall provide minimum 20% of total lighting points as emergency lighting points, fed from UPS DB or DCDB as per scheme adopted by the Contractor. Indoor and outdoor emergency lights shall be provided at each inverter room, main control room, security room and main gate.

18.2.6 GI Lighting pole of suitable diameter capable of withstanding system and wind load, shall be provided with average Zn coating thickness of 80micron. The street light poles shall have loop in loop out arrangement for cable entry and light fixture / wiring protected with suitably

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 59 of 105</u>	<u>Signature of</u> <u>Bidder</u>

rated MCB.

18.2.7 Lighting panels shall be earthed by two separate and distinct connections with earthing system. Switch boxes, junction boxes, lighting fixtures, fans, single phase receptacles etc. shall be earthed by means of separate earth continuity conductor. Cable armour shall be connected to earthing system at both the ends. Proper earthing of street light poles shall be ensured.

18.2.8 Junction box for lighting shall be made of fire retardant material. The degree of protection shall be IP55 for outdoor JB.

18.2.9 Cables, wherever exposed to direct sunlight, shall be laid through Double Wall Corrugated (DWC) HDPE conduits.

18.3 Lighting Levels

18.3.1 The average LUX level of 10 lm is to be maintained in switchyard. However, a lux level of 20 lm ((10+10) additional switchable on requirement only) is to be maintained in switchyard on transformer.

18.3.2 The lighting system for outdoor and indoor areas of solar power plant shall be designed in such a way that uniform illumination is achieved. Average LUX level to be maintained in different areas shall be as under:

Area	LUX
Control Room and equipment rooms	500
Office	300
Battery & other rooms	150
Other areas including periphery wall	10
Transformer yard	20
H – pole and metering point	10

18.3.3 The lighting level shall take into account appropriate light output ratio of luminaires, coefficient of utilization maintenance factor (of 0.7 or less) to take into account deterioration with time and dust deposition.

18.4 LED Luminaire

18.4.1 LED luminaires shall meet the following parameters:

Parameter	Specified Value
Input voltage	170-260 V
Input Frequency	50 HZ +/-1 HZ
Power Factor	0.95 (Minimum)

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 60 of 105	Signature of Bidder

Power Efficiency	>96%
LED chip efficacy	>130 lumens per watt
Luminaire efficacy	>90 lumens per watt
Dispersion Angle	Minimum 120°
Total Harmonic Distortion	< 15 %
Working Temperature	-5° to +50° C
Working Humidity	10% - 90% RH (Preferably Hermetically sealed unit)
Degree of Protection	Minimum IP 65 (for Outdoor fixtures)
Luminaire Casing	Powder coated metal / Aluminium.
Colour Temperature	5700o K (cool day light)
Colour Rendering Index	>75
Electrical Connector	Lead wire with 2 meter long – or as required by the customer at site.
Moisture protection in case of casing damage	IP 65 (driver unit shall preferably be totally encapsulated)

18.4.2 The LED luminaire housing, heat sink, pole mounting bracket, individual LED reflectors and front heat resistant tempered glass should be provided.

18.4.3 The LED luminaire housing should be made of non-corrosive high pressure die cast aluminium and the housing should be power coated grey, so as to ensure good weatherability. Each individual LED source should be provided with an asymmetrical distribution high reflectance aluminized reflector, which should ensure that the light distribution of the luminaire is suitable for road lighting applications (wide beam distribution) and should ensure high pole to pole spacing.

18.4.4 The luminaire should be provided with in built power unit and electronic driver. The luminaire should be so constructed to ensure that the driver and LED modules are replaceable, if required.

18.4.5 The luminaire should be suitable for both standard street light poles with a typical pole diameter of 50 mm – 60 mm and should be suitable for side entry and bottom entry (post top).

18.5 Warranty

All luminaires shall be warranted for minimum of 2 (two) years against all material/ manufacturing defects and workmanship.

18.6 Approval

18.6.1 Documents/ drawings

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 61 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- (i) Lux level calculations
- (ii) Building and street lighting layout
- (iii) Luminaire data sheet
- (iv) Test certificates

19 Weather Monitoring System

As a part of weather monitoring system, the Contractor shall provide the following measuring instruments with all necessary software and hardware required to integrate with SCADA.

19.1 Pyranometer

19.1.1 The Contractor shall provide minimum 4 (four) number of secondary standard pyranometers (ISO 9060 classification) along with necessary accessories for measuring the incidental solar radiation at horizontal and inclined plane of array.

19.1.2 Specification of the pyranometer shall be as follows.

Parameter	Specification
Spectral Response	0.31 to 2.8 micron
Sensitivity	Minimum 8 micro-volt/W/m ²
Time response (95%)	Maximum 15s
Nonlinearity	±0.5%
Temperature Response	±2%
Tilt error	<±0.5%
Zero offset thermal radiation	±7 W/m ²
Zero offset temperature change	±2 W/m ²
Operating temperature range	0°C to +80°C
Uncertainty (95% Confidence Level)	Hourly Max-3% Daily Max-2%
Non-stability	Maximum ±0.8%
Resolution	Minimum +/- 1W/m ²
Input Power for Instrument & Peripherals	230V AC (If required)

19.1.3 Each instrument shall be supplied with necessary cables. Calibration certificate with calibration traceability to World Radiation Reference (WRR) or World Radiation Centre (WRC) shall be furnished along with the equipment. The signal cable length shall not exceed 20m. The Contractor shall provide instrument manual in hard and soft form.

19.2 Temperature Sensor

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 62 of 105	Signature of Bidder

The Contractor shall provide minimum 6 (six) temperature sensors (1 (one) for ambient temperature measurement with shielding case and 5 (five) for module temperature measurement). The temperature sensor shall be Resistance Temperature Detector (RTD)/ Semiconductor type with measurement range of 0°C to 80°C. The instrument shall have valid calibration certificate.

19.3 Anemometer

Contractor shall provide minimum one no. ultrasonic wind sensor (no moving parts) for wind speed and direction monitoring.

Details	Values
Velocity range with accuracy limit	0-60m/s with +/-2% accuracy @12 m/s; Resolution: 0.01m/s
Wind direction range with accuracy limit	0 to 360° (No dead band) with +/-2° accuracy @12 m/s; Resolution: 1°
Mounting Bracket	Anodized Aluminium bracket to reduce corrosion, all mounting bolts of SS
Protection Class	IP66
Output	RS232 and RS485

19.4 Data logger and Data Acquisition System

Data logger for the weather monitoring station should have the following features:

19.4.1 Provision for analog, digital and counter type inputs for interfacing with various type of sensors:

(i) Analog Input

- Adequate nos. for all analog sensors with redundancy
- Provision for operation in different current and voltage ranges as per connected sensors
- Accuracy of +/-0.1% of FS

(ii) Digital Inputs

- Adequate no. of Digital inputs and outputs for the application

(iii) Provision for RS232 and RS485 serial outputs

(iv) Built-in battery backup

(v) Connectivity and Data transmission:

- Built-in GSM/ GPRS modem for wireless data transmission to SCADA/ cloud server (procurement of GPRS enabled SIM Card and connection subscription to be the

responsibility of Contractor). It should be possible to remotely communicate with the device for configuration settings.

- RS485 MODBUS interface for data collection and storage on SCADA
- Web interface with provision for user login to enable viewing and downloading of weather data in XLS/ CSV format
- Communication protocol should support fast data transmission rates, enable operation in different Frequency bands and have an encryption based data security layer for secure data transmission

(vi) Display Settings: Graphic LCD screen which should be easily accessible and should display relevant details like all sensor values, battery strength, network strength etc.

(vii) Provision of Time synchronization from telecom time or server time

(viii) Data Storage: Provision for at least 2 MB internal Flash Memory and at least 8 GB Micro SD card (expandable)

(ix) Protection level: IP65

20 CCTV Camera

20.1 CCTV Cameras along with monitoring stations (sufficient numbers) and all other accessories required for its proper operation must be installed to have complete coverage of following areas.

- (i) Main entry: Covering all the entry/exit 24 hours
- (ii) Along the Plant Perimeter: Covering complete perimeter of Plant Area to capture all possible intrusion
- (iii) Control Rooms: Covering Entry/Exit and activities within Control Rooms

The Contractor has to propose the locations and number of cameras required for the Plant during bidding, however Employer's decision on number of cameras shall be final.

20.2 Monitoring stations of the CCTV Network shall be installed in Main Control Room.

20.3 The CCTV system shall be designed as a standalone IP based network architecture. System shall use video signals from different cameras at defined locations, process the video signals for viewing on monitors at control room and simultaneously record all video streams using latest compression techniques.

20.4 Camera shall be colour, suitable for day and night surveillance (even under complete darkness) and network compatible.

20.5 It shall be possible to control all cameras i.e., PTZ auto/ manual focus, selection of pre-sets,

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 64 of 105</u>	<u>Signature of</u> <u>Bidder</u>

video tour selection etc. The software shall support flexible 1/2/4 windows split screen display mode or scroll mode on the display monitor for live video.

20.6 The system shall support video analytics in respect of the following:

- (i) Video motion detection
- (ii) Object tracking
- (iii) Object classification

Camera server shall be provided with sufficient storage space to storage recordings of all cameras at HD mode for a period of 15 days. All recordings shall have camera ID, location, date and time of recording.

21 Fire alarm System

21.1 Standards and Codes

Standard/Code	Description
IS 2189	Selection, Installation and Maintenance of Automatic Fire Detection and Alarm System Code of Practice
IS 2171	Portable Fire Extinguishers, Dry Powder (Cartridge Type)
IS 8149	Functional requirements for twin CO ₂ fire extinguishers (trolley mounted)
IS 2546	Galvanized mild steel fire bucket
National Building code 2005	

21.2 Contractor shall ensure the compliance of fire detection and alarm system as per relevant standards and regulations. The installation shall meet all applicable statutory requirements and safety regulations of state/central fire department/body or any other competent authority in terms of fire protection.

21.3 Firefighting system for the proposed power plant for fire protection shall be consisting of but not limited to:

- (i) Sand buckets
- (ii) Portable fire extinguishers (CO₂ and dry powder type)
- (iii) Microprocessor based fire alarm panel
- (iv) Multi sensor smoke detectors
- (v) Hooter cum strobe
- (vi) Manual call points
- (vii) Cables from sensor to fire Panel.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 65 of 105	Signature of Bidder

- 21.4 Minimum two numbers of fire extinguishers (CO₂ and Foam type each, of capacity 10 kg having BIS certification marking as per IS: 2171) shall be provided at every building/ enclosure, transformer yard and switchyard. However, contractor must comply with existing building code for fire protection and relevant IS codes.
- 21.5 Four numbers of stand with four sand buckets on each stand shall be provided in the Transformer Yard. Sand buckets inside the building shall be provided at strategic locations as decided during detailed engineering.
- 21.6 Digital output from the fire detection system shall be integrated with SCADA
- 21.7 Contractor shall submit the plan for fire and smoke detection system for the Employer's approval.

22 Testing Instruments

The Contractor shall provide the following set of instruments for on-site testing.

22.1 Earth resistance tester

Parameter	Specification
Display	Backlit LCD or LED display
Range	Earth Resistance: up to 2000 Ω Earth Voltage: 200 V
Accuracy	± (2% + 5)
Safety Ratings	IP 56
Programmable Limits setting	Enabled
Accessories	
Earth Ground Stakes (4 Nos)	
Three cable reels with cable length up to 20 m	
Carry Case-1 (capable of handling tester along with accessories)	
1 set of spare battery	

22.2 Array tester

Parameter	Specification
Display	Backlit LCD or LED display
Functionality	All electrical tests required by IEC 62446-1:2016
Memory	Up to 200 records & USB downloadable to Computer

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 66 of 105	Signature of Bidder

Accessories

A set of two, 4mm fused leads for extra protection during installation tests.

Leads which enable the array tester to connect directly to PV arrays

1 set of spare battery

22.3 Insulation tester

Parameter	Specification
Display	Backlit LCD or LED display
Insulation Test Range	0.1 MΩ to 10 GΩ
Test Voltage	250V, 500V, 1000V, 5000V
Test Voltage accuracy	+20% on positive side only no negative variation is allowed
Insulation Test Current	1 mA nominal
Auto Discharge	Discharge time < 0.5 Second for C = 1
Open Circuit test Voltage	>4 V, <8 V
Accessories	
Heavy duty Test Lead Set – 4 Nos.	
Carry Case with sufficient space for accommodating accessories.	

22.4 Digital Multimeter

Parameter	Specification
Display	Backlit LCD or LED display
AC/DC Current	500 μ A to 10 A (Accuracy 0.15 %)
AC/DC Voltage	50 mV to 1000 V (Accuracy 0.025 %)
Resistance	50 Ω to 5000 Ω (Accuracy 0.05 %)
Capacitance	1 nF to 100 mF (Accuracy 1.0 %)
Frequency	99.999 Hz, 999.99 Hz, 9.9999 Hz, 99.999 kHz, 999.99 kHz (Accuracy 0.005 %)
Accessories	
Temperature Probe	
Silicon Test Lead	

Alligator Clip
Carry Case with sufficient space for accommodating accessories.

22.5 Clamp meter

Parameter	Specification
Display	Backlit LCD or LED display
Jaw Opening	30 mm
Maximum Wire Size	600 MCM
Current Range	0 to 400 A
Accuracy Current	2.0 %
Voltage range	0 to 600 V
Voltage Accuracy	1.5 %
Resistance Range	0 to 4000 Ω
Accessories	
Test leads	
Electrical test leads	
Probe light & extender	
Carry Case with sufficient space for accommodating accessories.	

22.6 Infra-red thermal imaging camera

Parameter	Value
Spectral response	8 μm to 14 μm (LW)
Temperature-sensitivity and calibration range	-20 $^{\circ}\text{C}$ to +120 $^{\circ}\text{C}$
Atmospheric air temperature	-10 $^{\circ}\text{C}$ to +40 $^{\circ}\text{C}$
Thermal sensitivity	NETD $\leq$ 0.1 K at 30 $^{\circ}\text{C}$
Geometric resolution	640 x 480 pixels
Photo camera resolution	Approx. 30 times of IR camera resolution
Absolute error of measurement	$< \pm 2$ K
Adjustable parameters	Emissivity, ambient temperature
Adjustable functions	Focus, temperature level and span
Measurement functions	Measuring spot, measuring area with average and maximum temperature
Calibration	The measuring system (Camera, lens, aperture and filter): The camera has to be traceably

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 68 of 105	Signature of Bidder

	calibrated at least every two years. The calibration has to be documented. If the camera is not compliant, it has to be readjusted by the manufacturer.
Documentation	Storing of the infrared picture with the radiometric data

22.7 Digital lux meter

Parameter	Specification
Range	0 – 1000 lux
Accuracy	± (2% + 5)
Resolution	1 lux
Display	3½ digits, Backlit LCD/LED

22.8 All testing equipment shall possess valid calibration certificate issued from approved NABL labs.

22.9 Instruments of superior rating is allowed after seeking consent of the Employer.

22.10 Maintenance, calibration, up keeping, repair & replacement of these tools will be in the scope of the Contractor during 5 years of O&M.

22.11 It is Contractor's responsibility to arrange for tools, tackles, logistics, test kits, manpower, experts etc. required for trouble free operation of Plant.

23 **Power evacuation system**

23.1 The contractor has to do the power evacuation and integration to and with the designated substation via either overhead transmission line or underground cables at specified grid voltage with all necessary infrastructure such as protection switchgears and metering systems as per the requirement of the Employer.

23.2 The power evacuation system for the plant shall be as per the local DISCOM requirement and appropriate approval. The contractor shall get the route approval from the Employer or concerned authorities prior to start of the construction. Any changes in the route or scheme introduced by DISCOM at any point of the time prior to commissioning shall be complied without any additional cost to the Employer.

23.3 The ROW for the TL/UG cable shall be obtained prior to the construction of the line from the concerned authorities.

23.4 Overhead Transmission Line

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 69 of 105</u>	<u>Signature of Bidder</u>

23.4.1 In case the power evacuation is planned with overhead transmission line for plant internal and external evacuation, the design of tower and its accessories shall be as per the DISCOM's requirement and the design shall be submitted to Employer for approval/ accord.

23.5 Underground cable

23.5.1 In case the power evacuation is planned with underground cable for plant internal evacuation, the cable shall be approved by the Employer. However, in case of external power evacuation, the evacuation plan shall be as per DISCOM's requirement and the same shall be submitted to Employer for approval/ accord.

Civil, Mechanical & Plumbing Works

24 General Requirement

24.1 This section of Technical Specifications describes detailed technical and functional requirements of all civil, Mechanical & Plumbing works included in the scope excluding civil works for Transmission Line towers, Tower extensions & Tower accessories.

24.2 Standards & Codes

24.2.1 All design and construction of civil works shall conform to relevant Indian standards such as BIS, IRC, MORTH, NBC etc. In general codes are as below:

IS: 800, 801 or 802	Design of steel structures with working stress method (WSD) of design
IS: 456	Design of concrete structure
IS: 3374	Design of liquid retaining structure

24.2.2 Only in case of non-availability of Indian standard, equivalent American or British standard may be used for design with prior approval of the Employer and the contractor shall submit proper justification along with his request to the Employer for his review.

24.2.3 Contractor shall either have in - house qualified and experienced engineering team to carry out engineering or shall appoint a qualified and experienced external agency to carry out the engineering subjected to clearance of SECI.

24.2.4 The design calculations for MMS, RCC structure, steel structure, foundation system, road work, drainage work, etc. shall be submitted for prior approval of Employer before commencement of construction.

24.2.5 The design calculations shall be supplemented with a neat sketch showing the structure geometry, node and member nos., lengths of various typical members, support points and

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 70 of 105</u>	<u>Signature of</u> <u>Bidder</u>

type of supports, types of materials with design properties considered, type of sections used in analysis & design.

24.2.6 The report shall also include back-up calculations for various loads adopted in design, brief write-up on primary load cases and load combinations considered and conclusions on design results with supporting sketches for easy reference and clarity.

24.2.7 Where a computer program (other than STAAD Pro) is used for analysis and design, the contractor shall also include a write-up on the computer program used along with validation check. Input and output file shall also be given in the design report to facilitate its review and approval by the Employer.

24.3 The construction methodology for MMS and its foundations, road works, drains and pile load test procedure shall also be submitted for prior approval of Employer before start of works.

24.4 Contractor has to submit the design documents, drawings, layouts, investigation reports, test reports, calculations and analysis etc. for all works to Employer for approval prior to the start of construction at site. The construction shall be done only as per approved drawings

24.5 The contractor shall submit the detailed design calculations and drawings for MMS structure, bill of materials and their specifications/ standards to the Employer for approval before start for fabrication work.

24.6 Contractor must submit the complete quality documents i.e. test certificates for all tests conducted starting from raw material stage, in process, final testing w.r.t structure

24.7 The Contractor shall submit the detailed foundation & structural design basis and the list of reference standards, in this design philosophy. Depending upon the requirement, SECI may ask the contractor to get the design vetted by a Chartered engineer.

25 Topographical Survey

25.1 The contractor shall be responsible for detailed Topographical Survey of the proposed project site. The work shall be carried out through an agency with relevant experience and shall have qualified survey team.

25.2 The Topographical survey shall be conducted at 20mx20m grid, or as directed by the Engineer, with the help of digital surveying instruments like Total Station.

25.3 The Contractor shall carry the Bench Mark from nearest GTS Bench Mark, or any other establish source like Railway station etc. as approved by the Employer, by fly-levelling and establish two permanent bench marks (PBM) at site. All subsequent transfer of levels shall be carried out with respect to these PBMs. The work shall also include constructing permanent reference pillars at suitable locations as approved by the Employer. These

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 71 of 105</u>	<u>Signature of</u> <u>Bidder</u>

reference pillars shall be labelled permanently with their respective coordinates and reduced levels for future use. The Permanent Bench Marks and reference pillars shall be shown on the survey drawings.

- 25.4 While carrying bench mark to the project site, levels shall be established on the permanent objects like culverts etc. at least on one object in every one km. if available along with route with adequate description about the objects. These levels shall be maintained at site & also mentioned in the survey report to facilitate locating these objects later on.
- 25.5 The work survey work shall be carried out in UTM grids system. The contractor shall also establish the latitudes and longitudes of the corners of the project site. At least 50m width of the adjoining plots and surrounding areas shall also be covered in the survey for correlation with adjoining plots and facilities. The grids for the survey work shall be established in N-S & E-W direction (corresponding to magnetic North) or the Plant North as directed by the Employer. Positions, both in plan and elevation, of all natural and artificial features in the area like waterways, railway tracks, trees, cultivation, houses, fences, pucca and kutcha roads including culverts and crossings, foot tracks, other permanent objects like telephone posts and transmission towers etc. are to be established and subsequently shown on survey maps by means of conventional symbols (preferably, symbols of survey of India Maps). All hills and valleys within the area/areas are to be surveyed and plotted on maps by contours. Any unusual condition or formations on the ground, locations of rock outcrops (if visible on the surface) and spring/falls, sand heap/dune, possible aggregate deposits etc. shall also be noted and plotted on contour maps.
- 25.6 The record of measurement of all Reduced Levels (RL) shall be submitted in digital format, (in x, y z coordinate system) along with preliminary contour plan of the site, for Employer's review before submission of final contour Map. The contour interval shall be as required for proper representation of the topography however it shall not be more than 0.5m. The Contractor shall submit survey maps of the site in 1:10,000 scale indicating grid lines and contour lines, demarcating all permanent features like roads, railways, waterways, buildings, power lines, natural streams, trees, sand dunes etc. Present use of the site i.e. mining, quarrying, agriculture etc, existing drainage pattern of the site, possibility of water logging and high flood level of the area shall also be captured in the document. The project plot boundary with coordinates of all corner points along with coordinate grid of 50x50M interval shall be marked on the contour map

26 Geotechnical Investigations

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 72 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 26.1 The contractor shall be responsible for detailed soil investigations at the proposed project site for the purpose of foundation design for various buildings, structures, HT lines, MMS etc. and other design/ planning requirements.
- 26.2 The investigation work shall be carried out through any Govt. approved/ NABL accredited/IIT's/NIT's Labs, which are authorized to carry out such tests. The contractor shall submit the credentials of the proposed agency along with relevant certificates in support thereof for verification/ approval by the Employer.
- 26.3 The scope of work includes execution of complete soil exploration including boring and drilling, standard penetration test (SPT), collecting disturbed(DS) and undisturbed samples (UDS), collecting ground water samples, electrical resistivity tests (ERT) and conducting laboratory tests on collected samples of soil, ground water analysis, preparation and submission of report.
- 26.4 The field investigations shall mainly include drilling of min. 5 m deep boreholes (50% of total No. of boreholes shall be 10m deep), conducting SPT and collecting Disturbed (DS) and Undisturbed samples (UDS); conducting in-situ CBR test for internal roads & peripheral road; ERT and Trial pits. Number and location of bore holes, CBR tests and trial pits shall be decided as per the project layout, site topography and soil conditions in consultation with the Employer. However, there shall be minimum 1 (one) borehole per 5 (five) acres of the area or per MW of capacity while number of samples for laboratory investigations shall not be less than 50.
- 26.5 The proposed Geotechnical investigation plan indicating proposed locations of Trial pits (minimum 3 nos.), Bore holes and CBR tests (minimum 7 nos.) shall be submitted to the Employer for review and approval before start of work.
- 26.6 Laboratory tests shall be conducted on DS & UDS samples and water samples in sufficient no. and shall include, Soil classification, Grain size analysis including Hydrometer analysis, determination of Bulk and dry density, Specific gravity, Natural moisture content, Atterberg limits, Tri-axial shear tests (UU), Undrained shear test (Cu), Consolidation tests, Unconfined compression tests, Free swell index, chemical analysis of soil and water samples to determine the carbonates, sulphates, chlorides, nitrates, pH, Organic matter and any other chemicals harmful to concrete and reinforcement/ steel. Laboratory tests on rock samples shall be carried out for Hardness, Specific Gravity, Unit Weight, Uniaxial Compressive Strength (in-situ & saturated), Slake Durability etc.
- 26.7 After completion of field and laboratory work, the contractor shall submit a Geotechnical

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 73 of 105</u>	<u>Signature of</u> <u>Bidder</u>

Investigation Report for Employer's approval. All bore log details and lab test results shall be presented in the report as per provisions of relevant BIS standards. The report shall include a Map showing the locations of various field tests including coordinates, calculations and recommendations for foundation type and safe bearing capacity (SBC) for buildings, switch yard structures, Sub-Station, Transformer foundation, HT lines, MMS foundation etc. corresponding to settlement of 25mm

26.8 In case the contractor wishes to adopt pile foundation for MMS supports the report shall also include the calculations for pile capacity for direct compression, lateral and pull out capacity and recommended depth and dia. The contractor shall carry out field trials for initial load test on pile to verify the pile design & finalize the safe load carrying capacity under direction compression, lateral load and pull out. The no. of piles to be tested under each category shall be finalized corresponding to geotechnical characteristics at site, plot area etc. However, minimum 5 no. of piles shall be tested under each category of load. The locations of test piles shall be finalized in consultation with Employer. The adequacy of provided pile reinforcement in job (working) pile corresponding to the set of test loads shall be reviewed by the contractor for any additional requirement of reinforcement steel and the shall provide the same, the revised drawings for pile details, if any, shall be submitted to Employer for his approval before casting. The load test on pile shall be conducted after min. of 28 days from the date of casting. In case the contractor desires to conduct the test earlier than 28 days, he may use suitable higher grade of concrete or if substantial evidence from earlier cube test results on design grade concrete to demonstrate the early gain of required compressive strength prior to application of the test load. However, no pile test shall be conducted before 7 days of casting the pile. All the dial gauges and hydraulic jack assembly shall be properly calibrated as per the requirements of relevant IS codes and valid calibration certificate to this effect shall be submitted to the Employer before the equipment is used for the test. The contractor shall submit detailed methodology for conducting the tests in line with IS: 2911 – Part 4 for Employer's approval before commencement of any test. After completion of these tests the contractor shall compile the test results and submit the report in a proper format as specified in the IS code with recommendations/ conclusions for Employer's approval. The pile work shall start only after approval of the final pile design duly verified/ confirmed with initial load test results.

26.9 All building, switchyard and sub-station area shall have levelled ground. No foundation for buildings, switch yard equipment & structures, sub-stations, transmission line (TL) towers shall rest on filled up ground, except minor structures like cable trench, pipe pedestal etc.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 74 of 105</u>	<u>Signature of</u> <u>Bidder</u>

with maximum safe bearing capacity of soil not more than 3 T/m².

26.10 The report shall also include ground water analysis to ascertain its suitability for construction purposes, recommendations for type of cement, grade of concrete & minimum cement content as per prevalent soil characteristics with respect to presence of aggressive chemicals, environment exposure conditions as per relevant BIS specifications. The type of cement shall be decided based on the recommendations of the soil investigation report.

27 Other Investigations

27.1 The contractor shall also obtain and study other input data at proposed project site for design of the project. This shall include data related to earthquake and wind, rainfall, maximum & minimum ambient temperature, humidity, high flood level (HFL) etc.

27.2 The contractor shall carry out Shadow Analysis at proposed site and accordingly design strings and array layout with optimum use of space, material and man power. In case of large and steep variations in topography the study shall also include the effect of topographical variations on array layout. The contractor shall submit all the details/ design to the Employer for review/ approval.

27.3 The contractor shall also identify potential quarry areas for coarse and fine aggregates to be used for concrete and shall carry out the concrete mix design for different grades of concrete to be used in the work. The concrete mix shall be designed for each source of cement and quarry as per provisions of relevant Indian Standard. The concrete mix design shall be carried out through NABL accredited Laboratory or any Gov. Engineering college as directed by the Employer.

28 Site Levelling and Grading

28.1 The work involves clearing the site, as well as activities such as, removal of bushes, trees etc. as necessary.

28.2 Mandatory permissions/ licenses/ statutory clearances from competent authorities if required for cutting of trees, blasting or mining operations, disposal of waste material etc. shall be obtained by the contractor.

28.3 The site levelling and grading can be matching with respect to the natural topography of the land. Site grading level shall be fixed with due reference to site drainage of the whole area, existing drainage pattern, maximum flood level and system requirements. It shall be ensured that the land is graded or levelled properly for free flow of surface runoff and the grade levels shall be fixed w.r.t. high flood level at site, drainage pattern and system requirements. It shall be ensured that the land is used optimally to have maximum solar power generation

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 75 of 105</u>	<u>Signature of</u> <u>Bidder</u>

considering full utilization of the plot areas. It is advisable to follow the natural flow of water at the ground.

28.4 In case the filled-up earth is brought from outside the plant, the contractor shall carry out all required soil investigations to ascertain the suitability of the soil for land development and filling purposes.

28.5 The filling for levelling/ reclaiming the ground/ area shall be done in layers as per below:

- (i) Cohesive (clayey) soils: < 150mm of compacted thickness with compacting up to 95% of modified proctor density
- (ii) Granular (sandy) soils: 250mm compacted thickness with compacting up to 80% of relative density

28.6 Fill shall normally be made up of Cohesive Non-swelling material capable of being compacted up to 95% modified proctor density. The slope at edge of graded areas shall not be flatter than 1:1.5 (1 Vertical: 1.5 Horizontal) in cutting and 1:2 (1 Vertical: 2 Horizontal) in filling.

28.7 In case of filling is done with rock material the edges shall be provided in line with provisions of relevant BIS standard.

28.8 Excess earth if any shall be disposed of properly at location as directed by the Engineer-in-charge. All buildings & switchyard area/sub-station area shall be constructed in levelled area. No foundation shall be allowed on back filled soil and in that case the depth of foundations shall reach up to NGL. Final Level will be approved in detail engineering.

28.9 It should be ensured that there shall be no water ponding and flooding occurs in low-laying area and effective drainage is provided in the entire plant. The data regarding highest flood level at proposed site shall be obtained from the metrological department by the contractor. In case of absence of this data, the contractor shall assess the required information through local site reconnaissance.

28.10A detailed drawing for site levelling and grading shall be submitted to employer for approval. The estimated volume of cutting and filling shall be marked in the submitted drawings. The finish grade levels adopted for different blocks of the plant shall be clearly marked in the site levelling and grading drawing.

29 Roads

29.1 Suitable access road from Main gate to Main control cum office room (MCR), internal access roads connecting MCR and other facilities/ buildings like Local control room(s) (LCR)/ Inverter room(s) (ICR), Substation, Switch yard etc. and internal peripheral road along the boundary fence shall be provided for safe and easy transportation of materials and equipment during

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 76 of 105</u>	<u>Signature of</u> <u>Bidder</u>

construction and maintenance phase.

- 29.2 The access road connecting Main gate and MCR and internal access road(s) connecting MCR to various facilities/ buildings shall be 3.5m wide with 0.5m wide shoulders on either side while the peripheral road shall be 2.5m wide with 0.5m shoulders on either side.
- 29.3 All roads including shoulders shall be of WBM.
- 29.4 The top of road (TOR) elevation shall be minimum 200 mm above FGL to avoid flooding of roads during rains.
- 29.5 The roads shall be provided with alongside drains as per design requirements of storm water drainage system.
- 29.6 The roads shall be designed as per IRC 37 corresponding to design vehicular traffic of 2 (two) million standard axles (msa) and critical field CBR value.
- 29.7 The details of minimum road section to be adopted shall be as follows:
- (i) Topping: 75mm thick well compacted murrum layer for access road from main gate up to Main Control Room building and other internal roads.
 - (ii) WBM, compacted 75mm thick, Grade III.
 - (iii) WBM, compacted 100mm thick, Grade II.
 - (iv) Granular sub-base, compacted 250mm thick, Grade I.
- 29.8 Well compacted sub grade under road and shoulders to achieve min. 95% of standard proctor modified dry density (MDD). CBR value of sub-grade shall not be less than 4%. In case the CBR is less than 4% in a particular stretch, then the material shall be modified with increase in GSB thickness as per IRC standard.
- 29.9 The construction of roads shall conform to relevant IRC/ MORTH standards.
- 29.10 Drain and other crossings shall be provided with RCC slab or precast concrete pipe culvert. The culvert design shall conform to relevant IRC standard. However, all cable crossings across road shall be through pipes of minimum class NP3 conforming to IS 458.
- 29.11 Maintenance pathways of minimum 1m (one) width shall be provided between SPV arrays for easy movement of maintenance staff, tools, equipment and machinery, washing of modules etc. The pathway area shall be levelled well compacted manually/ mechanically.
- 29.12 Areas of depression, valley zones or wherever there is noticeable change in topography shall be levelled matching surface with ground topography/ grade to avoid accumulation of water in the region by allowing its free flow to keep the area free from mud/ sludge.

30 Surface/ Area drainage

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 77 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 30.1 The contractor shall design and construct storm water drainage network for smooth disposal of storm water from the Plant to the nearest available drainage outlet.
- 30.2 The storm water drainage system shall be designed and planned to ensure no water stagnation in the Plant. Necessary input data for maximum hourly rainfall intensity to be taken for drainage design shall be obtained by the contractor from Indian Metrological department.
- 30.3 The drainage system shall be designed as per the provisions of relevant IRC standard and best Industry practices.
- 30.4 The drainage scheme shall be designed considering the Plant plot area and the catchment area contributing to the Plant area drainage.
- 30.5 The storm water drainage system shall be a network of open surface drains (with rectangular or trapezoidal cross section) and shall generally be designed to follow the natural flow of water and ground contours.
- 30.6 Suitable size drain shall be provided on either side of the road for quick disposal of water from road and solar blocks/plant.
- 30.7 Suitable size peripheral drain (min.500x500mm) along inside of Plant boundary shall be provided for smooth channelization of outside storm water and to avoid flooding of the Plant area.
- 30.8 All the drains shall be lined with either brick or RR masonry/ concrete or stone slabs as suitable to the site conditions. The min. thickness of the lining shall be 115mm for brick masonry, 75mm for concrete slabs, 150mm for RR masonry and 100mm for stone slabs.
- 30.9 The concrete slab/ stone cladding shall have suitable CM (1:4) bedding. The lining work shall be in CM (1:4) and the joints shall be raked and pointed with CM (1:3), however, the joints in peripheral drain lining shall be without pointing.
- 30.10 The design shall be as per provisions of relevant BIS standards and good industry practice. The drain outfall shall be connected to the nearest existing natural drain(s)/ water body outside Plant premises and it shall be ensured that the drainage water shall not encroach/ flood in the adjacent property/ plot.
- 30.11 The contractor shall provide rain water harvesting system for water conservation by constructing suitable collection wells along the drains, detention ponds etc.

31 Peripheral boundary Wall/Fence

- 31.1 The boundary wall/fence shall be provided along the Solar PV Plant boundary to demarcate the Plant boundary and to keep away the unauthorised access to the Plant. The boundary

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 78 of 105</u>	<u>Signature of</u> <u>Bidder</u>

wall/fence shall be provided with a main entry gate. The length and layout of boundary wall/fence shall be as decided by the owner during detailed engineering after approval of topography work.

31.2 The fencing shall be with 2.4m height above final grade level including 400mm dia. GI concertina wire at the top to be supported on Y shape angle brackets provided at top.

31.3 The fencing shall be of GI chain link mesh fabric, max. mesh size 40x40mm (minimum wire gauge 3.15mm), both ends twisted conforming to IS 2721 with suitable internal, corner and stay posts of GI angles along with 230 thick brick/ 300 thick RR masonry toe wall, 150mm height above GL. The G.I. chain link wire mesh will be stretched and attached by clips to 3 strands of High Tensile Spring Steel (HTSS) wire of 4 mm dia. interwoven in chain link wire mesh and kept under tension which in turn are attached to the fence post with security nuts and bolts.

31.4 Minimum size of angle for internal, corner and stay post shall be 75x75x6 mm. Spacing of intermediate posts shall not be more than 2.5m. Every 10th intermediate post shall be provided with a stay post along fence and every corner post shall be provided with two stay posts along either side fence. All MS angles and members used in posts shall also be galvanized in line with relevant IS code provisions. The minimum thickness of galvanization shall be maintained as 80 microns.

31.5 Toe wall shall be provided between the fence posts all along the run of the fence with foundation as per the approved drawing. The brick masonry toe wall shall be plastered with 15 thick CM (1:4) plaster on both faces and shall have min. 50 thick PCC (1:2:4) coping finished smooth and projecting 40mm on either side of the wall and top sloping inwards. In case of pond/ drain area suitable grid of MS angles of min. Size 50x50x6 mm shall be provided in place of toe wall.

31.6 The main gate shall be min. 5.5m wide (4m carriage way + 1.5m wicket gate).

31.7 The Main entry gate shall of rugged design with GI steel sections. The gate shall be complete with MS flat guide track, castor wheel(s), all fittings and fixtures like hinges, aldrop, locking arrangement, posts etc. All members used in gates shall be finished by cleaning of steel surfaces as per IS: 1477 (Part-II) and applying zinc chrome or zinc phosphate primer, followed by two coats of synthetic enamel paint.

32 Plant Layout

32.1 The contractor shall submit drawing showing proposed Project Plant Layout.

32.2 The Plant layout shall be a comprehensive drawing showing various requirements of the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 79 of 105</u>	<u>Signature of</u> <u>Bidder</u>

project like, Reference coordinate grid, Geographical and Plant North, Boundary fence including coordinates of all corner points, Main Entrance Gate and any other access gates as per project needs, block wise FGL, Internal and peripheral roads, Security Room/ cabin (s), All buildings with coordinates, temporary storage yard/ facility to be used by the contractor during construction, proposed Array layout, Lightning Arrester etc.

32.3 The Plant Layout drawing shall be in suitable scale to have proper representation of the information.

33 Design Loads

33.1 Unless otherwise specified elsewhere, Dead load, Live load, Wind load and Seismic load for buildings and structures shall be considered as per provisions of relevant IS standards.

33.2 The following minimum imposed load as indicated for some of the important areas shall, however be considered for the design. If actual expected load is more than the specified minimum load, then actual load is to be considered.

Area	Imposed Load
Roof	150 kg/ Sqm
Building floors	1000 kg/ Sq
RCC Floors (General)	500 kg/ Sqm
Outdoor platforms, Stairs, Landing and Balconies, Walkway, Chequered plate & Grating floor	500 kg/ Sqm
Road	As per IRC Standard
Road culverts & allied structures over drain & pipe crossings	Design for class -'AA' loading (Wheeled & Tracked both) and check for Class - 'A' loading as per IRC Standard
Underground structures such as Sumps, Pits, Trench, Drain etc.	In addition to Earth pressure and Ground water table at FGL, a surcharge of 1 T/Sqm shall also be considered
Pre-cast cover over cable trench	400 kg/ Sqm

33.2.1 Primary Loads

- (i) Dead Load (DL)
- (ii) Live Load (LL)
- (iii) Wind Load (WL) – Both along X & Z directions
- (iv) Seismic Load (EL) – Both along X & Z direction

33.2.2 WL for MMS design

- (i) Load due to fair (positive pressure) wind direction on design tilt angles of MMS members

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 80 of 105</u>	<u>Signature of</u> <u>Bidder</u>

(ii) Load due to adverse (negative pressure) wind direction on design tilt angles of MMS members

(iii) Load due to wind on side face of MMS members.

33.2.3 Design Load combinations

(i) DL+LL

(ii) DL+LL ± WLx

(iii) DL +LL± WLz

(iv) DL+LL ± ELx

(v) DL+LL ± ELz

Note - For MMS design, WL corresponding to (iii) shall be considered along with (i) & (ii), under 32.2.2, as applicable in calculation of WL under Primary Load ((iii) under 32.2.3).

33.3 All buildings, structures and foundations shall be designed to withstand loads corresponding to worst design load combinations. Unless otherwise specified elsewhere in the specifications, the DL, LL, WL and EL shall be estimated as per provisions of relevant BIS standards.

33.4 Wind Load Factors K2, K2 and K3 – As per IS 875 (Part-3). However, minimum value for K1, K2 and K3 shall be 1.0.

33.5 Unless otherwise specified elsewhere in the specifications, the Seismic Load shall be considered corresponding to Earth quake zone at site as per IS: 1893 – (Part- 4)

34 Foundations

34.1 Contractor shall design all foundations for buildings, equipment, HT line Towers, Switch yard structures, Transformer, MMS & other structures as per relevant BIS standards and recommendations of Geotechnical investigation report.

34.2 The contractor should ensure that the minimum plinth level of all buildings shall be 450mm above FGL. Module mounting structure foundation or any other pedestal shall be min. 250mm above FGL to avoid any damage to the MMS column/sub support due to direct contact of rain water/ surface run-off.

34.3 In case the contractor proposes to provide pile foundation for support of module mounting structure (MMS); the type, dia. and length of pile shall be as per recommendations of Geotechnical Investigation Report corresponding to prevalent soil characteristics at site, however the min. dia. and depth of the pile shall be 300 and 1800mm respectively except when very hard strata/ rock (N>100) is encountered at a higher level, the pile shall be extended in to the hard strata minimum 1 times the diameter of the pile or shall have total

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 81 of 105</u>	<u>Signature of</u> <u>Bidder</u>

minimum length of 1800 mm.

- 34.4 In case collapse of foundation strata during drilling of the pile bore, removal steel liner shall be used to maintain design depth and diameter of the pile for proper concreting.
- 34.5 The design pile capacity under direct compression, lateral load and pull out shall be verified through field trials by conducting initial load tests on test piles to be specially cast for this purpose. The tests shall conform to IS 2911 – Part 4. The number and location of such tests shall be as discussed and finalized with Engineer-in-charge. However, minimum 3 (three) number of tests shall be conducted under each category. In case, the site conditions demand for more number of tests to be performed, tests are required to be conducted by the contractor without extra cost.
- 34.6 Contractor shall also carry out routine tests on 0.5 % of the total no. of working piles as per provisions of IS: 2911 – Part 4.

35 Module Mounting Structure (MMS)

35.1 Standards and Codes

IS: 2062	Hot rolled Medium and High tensile structural steel
IS: 811	Cold formed light gauge structural steel sections
IS: 1161	Steel tubes for structural purposes
IS: 4923	Hollow steel sections for structural use
IS-2629, 4759 & 4736	Galvanization

35.2 General Requirement

- 35.2.1 MMS shall support SPV modules at a given orientation & tilt, absorb and transfer the mechanical loads to the ground properly.
- 35.2.2 The ground mounted module mounting structure design must follow the land profile of project site after levelling and grading
- 35.2.3 The structure shall be designed to allow easy replacement of any module and shall be in line with the site requirements.
- 35.2.4 The MMS stub/ column, rafter, purlin, ties and bracing members shall conform to Indian standards as mentioned in the list of codes and standards above.
- 35.2.5 The primary loads and load combinations for design of MMS structure shall be as specified under “Design Load” above.
- 35.2.6 The support structure design shall be as per relevant Indian standard(s) and shall be with working stress method considering appropriate factor of safety. No increase in permissible stress under wind/ Seismic load combination shall be permitted.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 82 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 35.2.7 In case of fundamental time period of MMS table structure is more than 1 Sec, then structure design shall be checked against dynamic effects of wind as per provisions of IS – 875 (Part-3).
- 35.2.8 The array structure shall be so designed that it will occupy minimum space without sacrificing the output from SPV panels at the same time.
- 35.2.9 The Contractor shall specify installation details of the PV modules and the support structures with appropriate diagram and drawings.
- 35.2.10 The Contractor should design the structure height considering highest flood level at the site and the finished grade level. The minimum clearance between the lower edge of the module or SMU, as the case may be, and the finished grade shall be the higher of;
- Highest flood level (HFL) + 100mm
 - 500 mm.
- 35.2.11 Welding of structure at site shall not be allowed and only bolted connections shall be used.
- 35.2.12 The maximum permissible deflection/ side sway limits for various elements of MMS under serviceability conditions shall be as following:
- Lateral deflection for Column/ stub – Span/ 240
 - Vertical deflection for Rafter and Purlin – Span/ 180
- 35.2.13 The minimum thickness (BMT) of various elements of MMS structure shall be as following:
- Stub/ column – 3.15mm
 - Rafter – 2.5mm
 - Bracing/ Purlin & other members – 2.0mm
 - Final thickness of the members shall be arrived by structural analysis considering combination of all possible loads.
- 35.2.14 In case the contractor wishes to mount the string monitoring unit over the MMS, the load of the same shall also be considered while designing the MMS. The minimum clearance of the lowest part of the structure (either the module or the SMU) from ground shall be adhered.
- 35.2.15 The contractor can also propose new light gauge structural steel or structural aluminium sections other than specified above subject to approval of the Employer. In this case the contractor shall submit his proposal stating the technical advantages of the proposed sections for Employers review along with supporting literature.

35.3 Galvanization

- 35.3.1 The MMS structure shall be hot dip galvanized with minimum thickness of coating not less

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 83 of 105</u>	<u>Signature of</u> <u>Bidder</u>

than 80 microns on each side. It is to ensure that before application of this coating, the steel surface shall be thoroughly cleaned of any paint, grease, rust, scale, acid or alkali or such foreign material as are likely to interfere with the coating process. The Contractor should ensure that inner side should also be coated.

35.3.2 The galvanization shall be done after fabrication of members to ensure galvanization of all cut surfaces.

35.3.3 In case the proposed section is made up of Aluminium, anodized coating shall be Gr AC25 and shall conform to IS: 1868. 10.13

35.4 Fasteners

35.4.1 All the fasteners and washers (packing & spring) for Module Mounting Structure and Module shall be adequately protected from atmosphere and weather prevailing in the area and must sustain the adverse climatic conditions to ensure the life of the structure for at least 25 years.

35.4.2 Fasteners and washers to be used for erection of mounting structures shall be of SS 304/UNS S 20430 or equivalent.

35.4.3 Fasteners used for the fixing of Module over MMS shall be of stainless steel grade SS 316 or equivalent.

35.4.4 In case the modules on MMS are fixed with the Clamp – bolt arrangement, the material of clamps shall be Al / Steel having weather resistant properties. Clamp – bolt arrangement shall use EPDM rubber and shall be designed in such a way so as not to cast any shadow on the active part of a module.

36 **Concrete Works**

36.1 All RCC works shall be with design mix as per IS 456 : 2000 and the materials used viz. Cement, coarse & fine aggregate, Reinforcement steel etc. shall confirm to relevant BIS standards.

36.2 The contractor shall carry out concrete mix design well in advance prior to construction through NABL accredited laboratory/ Reputed Engineering Institute (IITs/NITs/ Government Engineering Institutes) or as directed by the employer.

36.3 The minimum grade of RCC shall be M25 except for liquid retaining structures like underground water tank etc. where the grade of concrete shall be min. M30. (However in case of marshy land and plant near the sea coast these minimum grade of concrete shall be read as M30 and M35 respectively.) PCC shall be of min. grade M10 (equivalent nominal Mix – 1:3:6) unless otherwise specified.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 84 of 105</u>	<u>Signature of Bidder</u>

36.4 Reinforcement steel shall be of high strength TMT bars of grade Fe500 D conforming to IS: 1786. Ductile detailing in accordance with IS: 13920 shall be adopted for superstructure and sub-structure of all RCC buildings and structures.

36.5 For grouting works anti shrink ready mix grout of approved make or cement mortar (CM) grout with non-shrink additive shall be used. The grout shall be high strength grout having min. characteristic strength of 30 N/ mm² at 28 days.

37 Miscellaneous Steel Works

37.1 Unless otherwise specified all structural steel work shall be designed as per provisions of IS: 800 with working stress method of design (WSD). Structural steel hot rolled sections, flats and plates shall conform IS: 2062. Structural Pipes shall be medium (M)/high (H) grade conforming to IS: 1161.

37.2 Chequered plate shall conform to IS: 3502 and Hollow steel sections for structural purposes shall conform to IS: 4923.

38 Buildings

38.1 General Requirement

38.1.1 Plant buildings are required to be constructed for housing the electrical equipment/ panel (Local/ Inverter Control Room Building – LCR/ ICR) and control room with office cum store facilities (Main Control Room Building - MCR) for operation and maintenance of Photovoltaic Solar Power Plant. Security room(s)/ cabin(s) shall also be required at strategic locations to secure the Plant from any theft/ burglary.

38.1.2 All buildings except Security room/ cabin shall have RCC framed structure and brick/ panel/ partition walls.

38.1.3 The Plant building design shall be as per the OEM requirements to ensure desired life of equipment and plant.

38.1.4 The building layout, exterior elevations shall be aesthetically designed following good architectural practices to get a pleasing look, Horizontal/ vertical bands through projections/ grooves in external plaster may be provided to break the monotony.

38.1.5 Roof slab shall have projection of 400mm beyond external walls with 500mm parapet wall all around for smooth drainage of rain water which shall form a projected band at roof level.

38.1.6 All doors and windows shall be provided with 450mm RCC chajja for weather protection

38.1.7 The contractor shall submit the proposed layout drawings to the Employer for approval before development of Architectural drawings of buildings.

38.2 Main Control Room (MCR) Building

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 85 of 105	Signature of Bidder

38.2.1 For O&M of SPV Plant MCR building shall provide following facilities;

- (i) Inverter/ Switchgear, equipment room(s) as per requirement
- (ii) Air conditioned area (with provision of split A/C unit of adequate capacity) for SCADA room (min. 12m²) & Conference room (min. area 20m²)
- (iii) Supervisor cabin and office area (min. area 25m²)
- (iv) Store cum record room (min. area 20m²)
- (v) Battery room as per requirement &
- (vi) One toilet block with gents and ladies wash room facilities (min. area 12m²)
- (vii) There shall be suitable provision for easy/ smooth passage for O&M personnel, cable trenches etc.

38.3 Local/ Inverter Control Room Building

38.3.1 Inverter room/ LCR consists of data loggers, battery, Inverter, Electrical panels etc. as per requirement.

38.3.2 There shall be suitable provision for easy/ smooth passage for O & M personnel, cable trench, repair & replacement of the installed equipment etc.

38.4 Security Room/ Watchman Cabin

38.4.1 The security room(s)/watchman cabin(s) shall be of prefabricated structure.

38.4.2 Contractor shall provide adequate number of prefabricated watchman cabins and 1 (one) Security Room at main entry gate.

38.4.3 The minimum size of security cabin shall be 4mx4m and height 2.75m.

38.4.4 The watchman cabins shall be located at strategic locations and at corners of the plot.

38.4.5 The minimum size of watchman's cabin shall be 1.2x1.8m and height 2.5m.

38.4.6 The walls and roof of the building shall fabricated with double skin permanent colour coated insulated sandwiched Al-Zn alloy coated high tensile steel metal panels (BMT- 0.6mm, Al-Zn alloy coating -150 GSM total on both sides).

38.4.7 The insulation shall be of PUF, density 40 kg/ cum with adequate thickness.

38.4.8 Roof shall be provided with suitable slope (preferably 100) for proper drainage of rain water and shall project 300mm beyond the walls.

38.4.9 The make and colour shade of the metal panels shall be subject to approval by the Employer.

38.4.10 The security cabin shall be provided with 0.75m wide and 2.1m height Aluminium glazed door on one face and shall have Aluminium glazed sliding windows with Aluminium grill, 1.2m wide with 1.0 m height, on remaining three sides for Security Room while there shall

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 86 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- be 1 no. window on side face of watchman cabin of size 0.8mx1.0m with 1.0 m height.
- 38.4.11 All glazing shall be of clear float glass with thickness of 4mm for window and 6mm for door panel. The door and windows shall be provided with all necessary fitting and fixtures like handles, tower bolts, mortise lock for door, stays etc.
- 38.4.12 All aluminium sections for doors and windows shall be anodized (40 microns) for protection against weather. The cabin shall be installed on PCC 1:2:4 platform, 250 thick.
- 38.4.13 The PCC platform shall project 300mm beyond the walls. Special coated/ SS self-drilling screws/ fasteners conforming to class 3 as per ASTM: 3566.1 and 3566.2 shall be used. Anchor/ foundation bolts shall conform to IS: 5624 and relevant IS code.

39 Flooring, Skirting and Dado

All material samples need to be approved by employer before construction. Materials from reputed make shall only be used.

Store area, Equipment Room	40 mm thick Cement concrete (IPS) flooring (1:2:4), aggregate size 10 mm down conforming to IS 2571 with 2mm thick Heavy duty epoxy coating (Industrial grade), with 10mm thick matching skirting of 100mm height
SCADA Room, Control cum Office Room, Supervisor Room, and Lobby	40 mm thick Heavy duty vitrified tile (8mm thick) flooring with matching 100m high skirting
Battery Room	Acid/ Alkali resistant tile flooring and dado 2100 high, Floor and dado tiles - 20mm and 12 mm thick respectively. However, if the batteries are maintenance free then 40 mm thick Heavy duty vitrified tile (8mm thick) flooring with matching 100m high skirting.
Passage/Corridor	40 mm thick Heavy duty vitrified tile (8mm thick) flooring with matching 100m high skirting
Toilet	40 mm thick Ceramic tile (8mm thick) flooring and glazed tile (6mm thick) 2100 height dado
Pantry	40 mm thick heavy duty vitrified tile (8 mm thick) flooring and glazed tile (6mm thick) 2100 mm height dado
Steps	Kota stone – 20 thick/ 50 thick cement concrete (IPS) flooring conforming to IS 2571

40 Doors and Windows

- 40.1 Doors, windows and ventilators shall be made of aluminium sections (minimum average thickness 2mm), industrial grade and of reputed make, approved by Employer. All sections, fittings and fixtures shall be anodized with minimum thickness of coating as 20 microns. Where specified the sections shall be powder coated (TFT 50 microns) with approved make

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 87 of 105</u>	<u>Signature of</u> <u>Bidder</u>

& colour shade. The window and door shutters shall be with combination of compact sheet and clear float/ wired glass as per design/ functional requirements. However, all doors of toilet area shall be of steel framed solid core flush shutter conforming to IS: 2202.

- 40.2 The area of the openings shall be designed to have adequate ventilation, natural light and to meet functional requirements.
- 40.3 All doors, windows and ventilators shall be provided with all necessary fittings and fixtures like handles, tower bolts, wind stays, hinges etc. of heavy duty Aluminium.
- 40.4 All doors shall be provided with hydraulic door closure of required capacity.
- 40.5 All windows shall be provided with suitable Aluminium grill of anodized sections with adequate thickness.
- 40.6 The glazing shall be of clear float glass with minimum 4mm thickness for windows and 6mm thickness for door shutter.
- 40.7 Minimum size of all doors shall be 2.1m high and 1.2m wide except for toilet where min. width shall be 0.75m.
- 40.8 Rolling shutters of required size shall be made of cold rolled steel strips with adequate gauge thickness (min. thickness 18 gauge) and shall conform to IS 6248. Rolling shutter shall be provided with all fixtures, accessories, paintings etc.

41 Roofing

- 41.1 The roof shall be provided with min. slope of 1:100 for effective drainage of rain water. The slope shall be achieved either by application of screed concrete grade 1:2:4 (with 12.5mm down coarse aggregate) with min. 25thick CM 1:4 on top to achieve smooth surface to facilitate application of water proofing treatment.
- 41.2 The water proofing treatment shall be in situ five course water proofing treatment with APP (Atactic Polypropylene) modified Polymeric membrane over roof consisting of first coat of bitumen primer @ 0.40Kg per sqm, 2nd & 4th courses of bonding material @ 1.20 kg/sqm, which shall consist of blown type bitumen of grade 85/25 conforming to IS : 702, 3rd layer of roofing membrane APP modified Polymeric membrane 2.0 mm thick of 3.00 Kg/sqm weight consisting of five layers prefabricated with centre core as 100 micron HMHDPE film sandwiched on both sides with polymeric mix and the polymeric mix is protected on both side with 20 micron HMHDPE film.
- 41.3 The top most layer (5th layer) shall be finished with brick tiles of class designation 10 grouted with cement mortar 1:3 (1 cement: 3 fine sand) mixed with 2% integral water proofing compound by weight of cement over a 12 mm layer of cement mortar 1:3 (1 cement: 3 fine

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 88 of 105</u>	<u>Signature of</u> <u>Bidder</u>

sand) and finished neat. The roof shall be designed for minimum superimposed load to 150 kg/m².

41.4 The corners at parapet wall and slab shall be provided with 50 thick fillet/ golla in CM 1:3. Required no. of rain water down take pipes with khurra and MS grill at inlet, min. 100mm dia. PVC pipes (UV resistant), shall be provided for rain water disposal.

41.5 Pipes and associated fittings and fixtures shall conform to relevant BIS standards.

42 Plinth protection and drain

42.1 750mm wide plinth protection with min. 75mm thickness of PCC (1:3:6) over bed of dry brick ballast, 40mm nominal size well rammed and consolidated and grouted with fine sand, with min. 75mm thickness shall be provided around all the buildings.

42.2 A peripheral drain (except for Security room/ cabin) of min. size 250mm x 250mm internal size with brick walls in CM and 100mm thick PCC (1:3:6) bedding shall be provided along the periphery of the plinth protection for collection and disposal of rain water from all the building(s) roof including plastering and coping as specified elsewhere.

43 Plinth filling for buildings

43.1 Plinth beam, when provided, shall be taken minimum 200mm below FGL. The plinth filling below Ground floor (GF) for all buildings shall be provided with following specifications;

- (i) Well compacted sub-grade
- (ii) Minimum of 235 thick or above, well compacted boulder soling with interstices filled with sand.
- (iii) 75 thick PCC 1:3:6
- (iv) 100 thick PCC 1:2:4.
- (v) 40 thick floor finish

44 Sanitary Works

44.1 Toilet block with wash room facilities for both Genders shall be provided in MCR building.

The toilet block shall have following min. fittings:

- 44.1.1 Wall mounted WC (Western type) 390 mm high with toilet paper roll holder and all fittings.
- 44.1.2 Wall mounted Urinal (430 x 260 x 350 mm size) with all fittings for male toilet only.
- 44.1.3 Wash basin (550 x 400 mm) above platform with all fittings.
- 44.1.4 Bathroom mirror (600 x 450 x 6 mm thick clear float glass) with hard board backing.
- 44.1.5 CP brass towel rail (600 x 20 mm) with C.P. brass brackets.
- 44.1.6 Soap holder and liquid soap dispenser.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 89 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 44.1.7 Ventilators – Mechanical exhaust facility.
- 44.1.8 Overhead PVC water storage tank – Capacity 1000 litres
- 44.1.9 The toilet block shall have a provision for installation of Water Cooler.
- 44.1.10 One toilet room with provision of WC shall be provided at Security Room near main gate.
- 44.1.11 Necessary plumbing lines (for water supply & waste disposal) shall be provided for MCR building and Security room (near main gate).
- 44.1.12 All sanitary ware, plumbing fixtures & shall be of reputed Make and Type and approved by the Employer.
- 44.1.13 All fittings, fastener, grating shall be of CP brass conforming to relevant IS code.

45 Painting & Other Finishes

45.1 Painting

Painting and white wash/ colour wash for the buildings shall conform to relevant BIS standards. The make and colour shade of the finish shall be as advised and approved by the Employer.

Internal Walls except toilets & battery room	Acrylic emulsion (for MCR) & Oil Bound distemper (for LCR/ Security Room)
Battery room	Acid/ Alkali resistant tiled dado of 2100 mm height & Chlorinated rubber paint above dado
Toilet	Oil bound distemper
External Walls	All weather proof cement based acrylic emulsion paint, exterior grade
MMS foundations/ Earth pit Enclosure	Cement paint
Underside of roof slab	White wash
Air conditioned areas	Underside of roof slab- Under deck insulation with 50mm thick mineral wool, min. density 45 kg/ m3 and Gypsum board false ceiling with GI grid/ Gypsum tile (600x600mmx 12 thick) false ceiling with AL grid as per manufacturer's details
Battery room	Acid resistant resin based epoxy Paint

45.2 Air conditioning & Ventilation for MCR and Other Buildings

- 45.2.1 All buildings shall be equipped with appropriate numbers of fans for effective heat dissipation.
- 45.2.2 In MCR building, the supervisor room, Conference room and SCADA cabin shall have split type air conditioning units.

45.3 Fire Extinguishers

- 45.3.1 Liquefied CO₂/ foam/ ABC type fire extinguisher shall be upright type of capacity 10kg

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 90 of 105</u>	Signature of <u>Bidder</u>

having IS: 2171. 7, IS:10658 marked.

45.3.2 The fire extinguisher shall be suitable for fighting fire of Oils, Solvents, Gases, Paints, Varnishes, Electrical Wiring, Live Machinery Fires, and all Flammable Liquid & Gas.

45.3.3 Sand buckets should be wall mounted made from at least 24SWG sheet with bracket fixing on wall conforming to IS: 2546. 4 (four) number of Bucket stands with four buckets on each stand shall be provided in the Transformer Yard.

45.4 Sign Boards and Danger Boards

45.4.1 The sign board containing brief description of major components of the power plant as well as the complete power plant in general shall be installed at appropriate locations of the power plant as approved by Employer.

45.4.2 Building evacuation plan along with the direction signs shall be marked in buildings.

45.4.3 Safe assembly zones shall be marked in the plant as per the norms with reflective signs and letters.

45.4.4 Danger boards should be placed appropriately as per the norms with reflective letters.

45.4.5 All the boards shall be written in Hindi, English and local language.

46 **Masonry Work**

46.1 The masonry work shall be of bricks or concrete blocks.

46.2 All external walls of buildings shall be 230mm and internal walls shall be 230/ 115mm as per requirements. All concrete block masonry walls shall be min. 200mm thick.

46.3 Brick work shall be in cement mortar (CM) 1:6 & 1:4 for 230 mm and 115 mm thick brick wall respectively.

46.4 Bricks shall be of class designation 7.5 conforming to IS: 1077, IS: 2212 & IS: 3495.

46.5 All concrete blocks shall be of min. compressive strength of 7.5 N/mm² and shall be of Grade-A conforming to IS: 2185.

46.6 Suitable damp-proof course (DPC) shall be provided. The DPC shall be with PCC (1:2:4) using 6 down coarse aggregate and water proofing admixture. The min. thickness of DPC shall be 40mm

47 **Plastering, Pointing & Coping Works.**

47.1 All brick masonry work shall be provided with plaster.

47.2 Wall and ceiling plaster shall be in cement mortar (CM) – 1:6 and 1:3 respectively.

47.3 All joints in stone masonry shall be raked and pointed in cement mortar (CM) – 1:3 except specified otherwise. Exposed top surface of brick or stone masonry shall be provided with 50

thick plain cement concrete (PCC) coping (1:2:4) with trawl finish. All exposed coping shall be provided with suitable slope and projection for easy drainage of water.

48 Building Water Supply & Plumbing Works

- 48.1 GI/ CPVC pipes of Medium quality/class conforming to IS: 1239 (part-I)/ IS:15778 :2007 respectively shall be used for all water supply. All sewerage, waste water and ventilation pipes shall be PVC pipes conforming to IS 15328: 2003.
- 48.2 Required sewage lines shall be provided from MCR building and Security room coming to Sewage treatment/ disposal facility including all associated works like Manholes etc.
- 48.3 Sewage Treatment facility: The Contractor shall design & provide soak pit and RCC Septic tank for treatment of sewage and waste water for MCR building and Security room. However, in case of ground water within 1.5m of finished grade level or the soil strata being of low permeability, packaged sewage treatment Plant shall be provided. The packaged sewage treatment Plant shall be of proven design and of approved make. The sewage treatment facility shall be designed for total of 15 people.

49 Pipe & Cable Trenches

- 49.1 All internal trenches shall be of RCC. The min. wall and base slab thickness shall be 100mm for depth $\leq$ 750mm and 150mm for depths > 750mm. The trench shall be designed for lateral load due to external soil fill, ground water table at FGL and 50 KN/ Sqm surcharge. External trenches shall be kept min. 100mm above FGL to avoid entry of rain water.
- 49.2 Internal cable trench shall be provided with chequered plate (min. 8mm thick) covers, the trench cover (600 mm in length except at ends and bends) shall be provided with suitable lifting hooks. Both top edges of the cable trench shall be provided with min. 50x50x6 mm edge protection angle. Angle or channels shall also be grouted at distances of 600 mm across the indoor cable trenches to support the chequered plates. The design of internal and external cable/pipe trenches shall be as per the requirements of allied electrical/mechanical works.

50 Transformer Yard Civil Works

- 50.1 Transformer and equipment foundations shall be founded on piles/isolated spread footings depending on the final geotechnical investigation report.
- 50.2 Transformer foundations shall have its own pit which would cover the area of the transformer and cooler banks, so as to collect any spillage of oil or oil drainage in case of emergency.
- 50.3 The oil pit shall be filled with granite stone gravel of 40 mm size uniformly graded. The retention capacity of the transformer pit shall be min. 1/3 volume of the transformer oil which

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 92 of 105</u>	<u>Signature of</u> <u>Bidder</u>

is filled with gravel with 300mm free space above gravel fill.

- 50.4 The individual transformer oil pit shall be connected to an oil collection pit which shall be sized to accommodate full oil volume of the transformer connected to it, without backflow. The oil collection pit shall be connected to oily water drainage system. Dimensions of the discharge pipe shall consider rainfall intensity also. The water shall be discharged into the nearest drain by gravity flow or pumping.
- 50.5 Both, the transformer pit and the oil collection pit shall be of RCC. The oil collection pit shall be provided with RCC cover.
- 50.6 The area around the transformer and equipment shall be covered with gravel. The area shall be provided with galvanized chain link fence of minimum height 1.8 m along with gate. The specifications for fencing shall be similar to those specified under fencing section above except fence post which shall be 50X50X6 MS angles spaced at 2.5m c/c.
- 50.7 The Gate of size 3.5m shall be of MS pipe frame with welded wire fabric mesh including all accessories and fittings. MS angle posts shall conform to IS: 2062. The portion of the fence covering towards rail track shall be made of removable type for movement of transformer during erection /removal.
- 50.8 In addition, a small gate of 1.2 m wide shall be provided for man entry for maintenance purpose. The transformer yard fencing work shall confirm to CEIG/CEA requirements.
- 50.9 Transformer track rails shall conform to IS: 3443. The requirement of fire barrier wall between transformers shall be as per Electricity Rules and IS: 1646 recommendations. Minimum wall thickness shall be 230mm for RCC wall and 300mm for masonry wall.
- 50.10 All steel members used in preparation of yard fence shall be finished by cleaning of steel surfaces and applying zinc chrome or zinc phosphate primer, followed by two coats of synthetic enamel paint. All paints including primer shall be of reputed brand / manufacturer.

51 Water Supply & Cleaning of Modules

- 51.1 Water used for cleaning purpose shall be fit for cleaning the PV modules, cleaning procedure and pressure requirement shall be as per the recommendation of PV module manufacturer.
- 51.2 A suitable arrangement of water shall be ensured to cater the day-to-day requirement of drinking water and needs of Solar Photovoltaic Plant during entire O&M period.
- 51.3 The Contractor shall estimate the water requirements for cleaning the photovoltaic modules as per the soiling conditions prevailing at site or mutually agreed frequency, in order to operate the Plant at its guaranteed Plant performance. Also, Contractor is required to plan the water storage accordingly.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 93 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- 51.4 Contractor has to plan and install the effective module cleaning system as per the prevailing conditions at Site. The system may include the storage water tanks, pumps, laying of HDPE pipes, flexible pipes, taps/ valves, pressure gauges etc. as per the planning by the Contractor. Contractor has to submit the drawing/ plan for the proposed module cleaning system.
- 51.5 All the pipes thus laid must be buried in ground at least 150mm below FGL. Road crossings and drain crossings, the pipes must be passed through GI/ Hume pipes as applicable.
- 51.6 The pipe riser with valve for the flexible pipe terminal shall be of GI only with masonry housing.
- 51.7 There shall be 2 nos.(1 working+1 standby) suitably selected pumps with desired flow rate, pressure head etc. to meet the PV module cleaning requirements, complete with all valves and pressure gauges. The pumps and all its accessories shall be suitable for outdoor installation with minimum IP55 protection

52 Underground/ Overground Water Tank

- 52.1 The Contractor shall construct underground RCC water tank (of required capacity) with silting chamber for filtration of the water before the inlet which will match with invert level of Storm water drain. However, minimum storage capacity of the tank shall be 15000 Litres.
- 52.2 The top of the tank shall be 250 mm above FGL. Suitable sized pump shall also be installed to maintain the water pressure at the extreme ends, required for proper cleaning of modules.
- 52.3 The tank shall have clear free board of 300mm above MWL.
- 52.4 The tank bottom shall have a slope of 1:250 towards drainage sump (500x500x500 mm deep). The slope shall be provided either in structural slab or with screed concrete 1:2:4 neat finished at top.
- 52.5 1000x1000 mm size Manhole in roof slab and 20 mm GI rung ladder shall be provided for easy access to the storage tank and silting chamber for periodic cleaning. The manhole shall be covered with RCC precast cover. 50x50x6 mm MS angles shall be provided around precast cover along supporting edges for edge protection.
- 52.6 The underground RCC tank shall be designed for following load conditions:
- 52.6.1 External earth pressure + hydrostatic pressure due to ground water table to be considered at FGL for design purposes) + Surcharge of 2 T/m² and Tank Empty.
- 52.6.2 Tank full up to MWL and no Earth pressure, Hydrostatic pressure due to ground water table and surcharge from outside.
- 52.7 The design shall conform to IS: 3370 with maximum crack width of 0.1mm for Wall, bottom slab and roof slab. Min. grade of concrete shall be M30 conforming to IS: 456. PVC water

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 94 of 105</u>	<u>Signature of</u> <u>Bidder</u>

bars 230x8 mm thick, conforming to relevant IS shall be provided at all construction joints. Water proofing admixture conforming to relevant IS and of approved make shall be added to concrete.

- 52.8 The underground water tank shall be tested for water tightness as per the provisions of IS 3370. In case any leakage is noticed the same shall be repaired by injection of cement grout installing suitable nozzles around affected areas.

Performance Measurement Procedure

53 Performance Ratio (PR)

Performance Ratio (PR) test for Operational Acceptance of the plant shall be performed as per the procedure attached in Annexure.

54 Capacity Utilization Factor (CUF)

- 54.1 Capacity Utilization Factor shall be calculated as per the following formula.

$$CUF = \frac{E_{ac}}{8760 \times P_{ac} \times [1 - DF \times (N - 1)]}$$

where,

E_{ac} = is the number of units recorded in the ABT meter located at plant facilities after excluding auxiliary consumption, kWh

8760 = refers to the number of hours in non-leap year. It shall be replaced by 8784 hours during leap year.

P_{ac} = is the plant AC capacity

DF = is module degradation factor, 0.75% per year

N = is the number of years of operation after operational acceptance of the plant

- 54.2 CUF shall be calculated on annual basis from the date of operational acceptance of the plant. Module degradation factor will not be considered for first year CUF calculation. It is the Contactor's responsibility to envisage and install extra DC capacity to accommodate any degradation during first year. 0.75% per year will be considered from second year of operation.

- 54.3 It is the responsibility of the Contractor to build-in the expected variation of irradiance in their design by installing additional DC capacity to meet the committed CUF. Irradiance variation will not be considered for the calculation of CUF.

- 54.4 Grid outage hours shall be subtracted from total number of hours in a year. The Contractor shall submit grid outage certification from component authority of STU/DISCOM.

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS Page 95 of 105	Signature of Bidder

SCOPE OF WORK:

55 Introduction

55.1 Project particulars:

Particulars	Description
Proposed capacity of the solar power plant	5MW (AC) SPV plant
Technology	Mono/ Multi crystalline
Origin of manufacturer	Domestic
O&M period	5 (Five) Years
Site location and land details	
Latitude	17° 13' 23.65" N
Longitude	78° 38' 31.04" E
Altitude	373m
Village	Sheriguda
Mandal	Ibrahimpatnam
District	Rangareddy
State	Telangana
Location	Ibrahimpatnam
Type of Land	Govt. land
Owner of land	Bharat Dynamics Ltd., Ibrahimpatnam
Nearest Substation Details	33/ 11kV, Mangalpally S/s
Distance to connecting substation	15km (approx.)
Estimated life of PV Power plant	25 Years
Nearest Urban Area	Hyderabad City
Nearest Highway	NH 17 (Adjacent)
Nearest Railway Station	Falaknuma (40 km)
Nearest Domestic Airport	Hyderabad (30 km)
Minimum values of PR and CUF of the plant after netting off the auxiliary consumption.	PR : 0.77 CUF : 20.4%
Water and Power for Construction	To be arranged by the Contractor

Scope of Supply and Work

56 Brief Scope of Work

Scope of Supply & Work includes all design & engineering, procurement & supply of equipment and materials, testing at manufacturers works, multi – level inspections, packing and forwarding, supply, receipt, unloading and storage at site, associated civil works, services, permits, licences, installation and incidentals, insurance at all stages, erection, testing and commissioning of 5MW (AC) Grid Interactive Solar PV Power Plant and performance demonstration with associated equipment and materials on turnkey basis at Sheriguda Village, State: Telangana and 05 (Five) years comprehensive operation and maintenance from the date of commissioning or Operational Acceptance, whichever is later.

57 Design and Engineering:

57.1 Contractor shall prepare the detailed design basis report (DBR) along with relevant standards (with respective clause description), PERT Chart and MDL. Contractor shall submit a copy to Employer for evaluation.

57.2 Submission of basic design data, design documents, drawings and engineering information including GTP and test reports to Employer or its authorized representative for review and approval in hard copy and soft copy from time to time as per project schedule. The documents typically include, but not limited to, the following:

- Solar insolation data and basis for generation
- Detailed technical specifications (GTP) of all the equipment
- General arrangement and assembly drawings of all major equipment
- Schematic diagram for entire electrical system (DC, AC and auxiliary systems)
- GTP & G.A. drawings for all types of structures/ components, 33kV switchgears & other interfacing panels
- Test reports (for type, routine and acceptance tests)
- Relay setting charts
- Design calculations and sheets (licenced software as well as design templates)
- Geo technical investigation data and Topographical survey and plan for the area
- Overall plant layout
- GA drawings of the entire project including equipment rooms/ inverter control rooms, office cum control room, roads, storm water drainage, sewage networks, security gate,

5 MW (AC) Solar PV Power Plant Project	Tender No <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	SoW & TS <u>Page 97 of 105</u>	Signature of <u>Bidder</u>

- fire protection system, perimeter fencing, transformer yard fencing etc.
- Transmission line drawings and erection plans as per DISCOM/ STU guidelines
- Quality assurance plans for manufacturing (MQP) and field activities (FQP)
- Detailed site EHS plan, fire safety & evacuation plan and disaster management plan.
- Detailed risk assessment and mitigation plan.
- O&M Instruction's and maintenance manuals for major equipment
- As-built drawings / documents and deviation list from good for construction (GFC)

57.3 Estimation of the plant generation based on Solar Radiation and other climatic conditions prevailing at site.

57.4 Design of associated civil, structural, electrical & mechanical auxiliary systems includes preparation of single line diagrams and installation drawings, manuals, electrical layouts, erection key diagrams, electrical and physical clearance diagrams, design calculations for Earth- mat, Bus Bar & Spacers indoor and outdoor lighting/ illumination etc., GTP and GA drawings for the major equipment including transmission line, design basis & calculation sheets, and other relevant drawings and documents required for engineering of all facilities within the periphery to be provided under this contract.

57.5 All drawings shall be fully corrected to match with the actual "as – built" site conditions and submitted to Employer after commissioning of the project for record purpose. All as-built drawings must include the Good for Construction deviation list.

58 Procurement & Supply

58.1 The equipment and materials for Grid Interactive Solar PV Power Plant with associated system (Typical) shall include but not limited to the transit insurance, receipt, unloading, storage, erection, testing and commissioning of all supplied material for the following:

58.1.1 Adequate capacity of Solar PV modules of suitable rating including module mounting structures (fixed tilt/ tracker), fasteners, suitable MMS foundations and module interconnections.

58.1.2 Array Junction boxes, distribution boxes and Fuse boxes with string monitoring capabilities:

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 98 of 105</u>	<u>Signature of</u> <u>Bidder</u>

MCBs/ isolators, Surge Arrestors and with proper lugs, glands, ferrules, terminations and mounting structures.

58.1.3 DC and AC cables of appropriate sizes with adequate safety and insulation

58.1.4 Power Conditioning Units (PCU) with SCADA compatibility, common AC power evacuation panel with bus bars and circuit breakers LT & HT Power Interfacing Panels, Plant Monitoring Desk, AC & DC Distribution boards.

58.1.5 Step – up transformers (inverter duty) in relevance with state grid code and inverter manufacturer requirements.

58.1.6 Auxiliary transformer (s) along with cables and accessories for plant internal consumption.

58.1.7 Relay and protection system along with battery system.

58.1.8 LT Power and Control Cables including end terminations and other required accessories for both AC & DC power

58.1.9 Internal 415V interconnection & Indoor feeder panels to cater auxiliary needs of plant

58.1.10 Indoor/ outdoor panels having incoming and outgoing feeders with VCBs, CTs, PTs, Bus bars, cables terminals kits and Bus coupler having Main and transfer Bus. Each bay shall consist of VCB, CT, Isolators with earth switch, LAs and PT's etc.

58.1.11 ABT meters (Main and Check) with all necessary metering rated CT's and PT's at the plant take off point as well as at the substation as per CEA Metering Regulation 2006 as amended time to time and state metering code.

58.1.12 Data acquisition system with remote monitoring facilities. Provision for specific data transfer to the State Load Dispatch Centre (SLDC) shall also be provided.

58.1.13 Lightning arrestors for entire plant area.

58.1.14 PVC pipes, cable conduits, cable trays and accessories/trenches.

58.1.15 Earthing of the entire plant as per relevant standards.

58.1.16 Control room equipment

58.1.17 Testing instruments for maintenance and monitoring of equipment.

58.1.18 Spares & consumables, as required or recommended, for the complete O&M period.

58.1.19 CCTV cameras for plant surveillance

58.1.20 Fire protection system in buildings and fire extinguishers.

58.1.21 Weather monitoring station shall include but not be limited to the following:

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 99 of 105</u>	<u>Signature of</u> <u>Bidder</u>

- Pyranometers – for horizontal and tilted plane
- Ultrasonic Anemometer (wind speed and direction)
- Temperature Sensor – Ambient and module surface
- Power source to the all sensors
- Data Logger

58.1.22 Construction of suitable structures for termination of transmission line for taking off from plant end and receipt of lines at Substation end.

58.1.23 Design & construction of Transmission line/ cable from plant take off point to the designated substation including right of way (ROW).

58.1.24 Materials and accessories, which are required for satisfactory and trouble-free operation and maintenance of the above equipment.

58.1.25 Any other equipment / material, not mentioned but required to complete the Solar Power Plant facilities in all respect.

59 Construction and Erection Works

59.1 The items of civil design and construction work shall include all works required for solar PV project and should be performed specifically with respect to following but not limited to:

59.1.1 Conducting geotechnical investigation and topographical survey of the given area.

59.1.2 Earthwork for site grading, cutting, filling, levelling & compaction of land.

59.1.3 Construction and erection of perimeter fence/ boundary wall and main/ security gate(s).

59.1.4 Construction of foundation for mounting structures for SPV panels.

59.1.5 Civil foundation work of transformers, switchgears, etc.

59.1.6 Construction of motorable approach road, internal roads and peripheral roads with WBM base

59.1.7 Construction of Equipment room with necessary illumination system and finishing as required.

59.1.8 Office cum stores cum control room building with Supervisor room, pantry, wash room, conference room etc. along with requisite furniture, workstations, air conditioning, internal and external illumination, other equipment as per the specifications.

59.1.9 Security cabin (s) at strategic locations inside the boundary of the plant.

59.1.10 Suitable arrangement of water shall be ensured to cater to day-to-day requirement of drinking water and permanent water supply for module cleaning and other needs of SPV power

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 100 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

plant during entire O&M period.

59.1.11 Suitable Communication System for telemetry, SCADA with remote monitoring capabilities and internet facility

59.1.12 Construction of Storm water drainage & sewage network including rain water harvesting mechanism.

59.1.13 Erection of Perimeter lighting along with all accessories and cabling

59.1.14 Laying of underground / over ground Cables (all types, as applicable) with proper arrangements along with appropriate sized ferrules, lugs, glands and terminal blocks. Laying of cables inside the building trench and other locations as required shall be over GI cable trays with proper support and accessories.

59.1.15 Construction of transmission line from take-off point at plant end/ substation to the delivery point at STU/DISCOM substation.

59.1.16 Suitable earthing for plant along with earth pits as per standards

59.1.17 All approvals, for equipment, items and works, which are not otherwise specifically mentioned in this document but are required for successful completion of the work in all aspects, including construction, commissioning, O&M of Solar PV Power Plant and guaranteed performance are deemed to be included in the scope of the contractor.

60 Statutory Approvals

60.1 Obtaining statutory approvals /clearances/ compliances on behalf of the Employer from various Government Departments, not limited to, the following: -

60.1.1 Pollution control board clearance, if required

60.1.2 Mining Department, if required

60.1.3 Forest Department, if required

60.1.4 All other approval, as necessary for setting up of a solar power plant including CEIG/ CEA, connectivity, power evacuation, railways, PTCC etc. as per the suggested guidelines

60.1.5 All other statutory approvals and permissions and their respective compliances, not mentioned specifically but are required to carry out hassle free Construction and O&M of the plant.

60.1.6 Adequate and seamless insurance coverage during EPC and O&M period to mitigate all risks related to construction and O&M of the plant to indemnify the Employer.

60.2 The Contractor shall comply with the provision of all relevant acts of Central or State Governments including payment of Wages Act 1936, Minimum Wages Act 1948, Employer's Liability Act 1938, Workmen's Compensation Act 1923, Industrial Dispute Act 1947, Maturity

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 101 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

Benefit Act 1961, Mines Act 1952, Employees State Insurance Act 1948, Contract Labour (Regulations & Abolishment) Act 1970, Electricity Act 2003, Grid Code, Metering Code, MNRE guidelines or any modification thereof or any other law relating whereto and rules made there under or amended from time to time.

61 Operation and Maintenance

61.1 Total Operation & Maintenance of the SPV Plant shall be with the Contractor, after commissioning / operational acceptance of the plant till final acceptance or culmination of the O&M period, whichever is later, shall include deployment of engineering personnel, technicians and security personnel.

61.2 To provide a detailed training plan for all O&M procedures to Employer's nominated staff, which shall have prior approval from the Employer.

61.3 Employ and coordinate the training of contractors' personnel who will be qualified and experienced to operate and monitor the facility and to coordinate operations of the facility with the grid system.

61.4 Discharge obligations relating to retirement/ Superannuating benefits to employees or any other benefit accruing to them in the nature of compensation, profit in lieu / in addition to salary, etc. for the period of service with the contractor, irrespective continuance of employees with the project as employees of Contractor, after conclusion of O&M period.

61.5 To maintain accurate and up-to-date operating logs, records and monthly Operation & Maintenance reports at the facility. Contractor shall keep the measured daily data at regular intervals and provide the same to Employer in electronic form, compatible in CSV format. The right to use the data shall remain with the Employer.

61.6 Procurement of spare parts, overhaul parts, tools & tackles, equipment, consumables, etc. required for smooth operation and maintenance of the plant as per prudent/ standard utility practices, OEM recommendations and warranty clauses for the entire O&M period

61.7 To upkeep all administrative offices, roads, tool room, stores room, equipment in clean, green and workable conditions.

61.8 To carry out periodic overhauls or maintenance required as per the recommendations of the original equipment manufacturer (OEM) and to furnish all such periodic maintenance schedules at the time of plant commissioning/ start of O&M contract.

61.9 Handover the system to maintain an inventory of spare parts, tools, equipment, consumables and supplies for the facility's operation along-with required details of recommended

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 102 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

spares list with all associated information regarding replacement records, supplier details, tentative cost, storage details, specifications on the basis of replacement frequency and mean time between failures and mean time to restore at the culmination of penultimate year under O&M period.

61.10 Availability of vehicles for Employer staff during construction and O&M period as per requirement may be ensured, failing which Employer shall have full right for alternate arrangement at the risk & cost of the contractor.

61.11 The contractor shall be responsible for all the required activities for the successful running, committed energy generation & maintenance of the Solar Photovoltaic Power Plant covering:

- Deputation of qualified and experienced engineers and technicians at the facility.
- Deputation of Security personnel for the complete security of plant.
- Successful running of Solar Power Plant for committed energy generation.
- Co-ordination with STU/SLDC/other statutory organizations as per the requirement on behalf of Employer for Joint Metering Report (JMR), furnishing generations schedules as per requirement, revising schedules as necessary and complying with grid requirements.
- Monitoring, controlling, troubleshooting maintaining of logs & records, registers.
- Furnishing generation data monthly to Employer by 1st week of every month for the previous month to enable Employer raise commercial bills on consumers.
- Periodic cleaning of solar modules as approved by the Employer and water quality as per the recommendations of OEM
- Replacement of Modules, Invertors/PCU's and other equipment as and when required during the O&M period without additional cost to Employer

61.12 Continuous monitoring the performance of the Solar Power Plant and regular maintenance of the whole system including Modules, PCU's, transformers, overhead line, outdoor/indoor panels/ kiosks etc. are necessary for extracting and maintaining the maximum energy output from the Solar Power Plant.

61.13 Preventive and corrective O&M of the Solar Photovoltaic Power Plant including supply of spares, consumables, wear and tear, overhauling, replacement of damaged modules, invertors, PCU's and insurance covering all risks (Fire & allied perils, earth quake, terrorists, burglary and others) as required.

61.14 The period of Operation and Maintenance will be deemed to commence from the date of completion of performance demonstration/Operational acceptance and successively the complete Solar Photovoltaic Power Plant to be handed over to the O&M contractor for operation and maintenance of the same. O&M contract shall further be extended on the mutually agreed terms and conditions for the mutually agreed period.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 103 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

61.15 All the equipment required for Testing, Commissioning and O&M for the healthy operation of the Plant must be calibrated, time to time, from the NABL accredited labs and the certificate of calibration must be provided prior to its deployment.

61.16 The Contractor shall ensure that all safety measures are taken at the site to avoid accidents to his or his sub-contractor or Employer's Workmen. This will include procurement of all safety gadgets during Construction and O&M period including but not limited to, rubber mats of appropriate grade, PPE, rubber gloves and suitable shoes etc.

62 Operation and Performance Monitoring

62.1 Operation part consists of deputing necessary manpower necessary to operate the Solar Photovoltaic Power Plant at the full capacity. Operation procedures such as preparation to starting, running, routine operations with safety precautions, monitoring etc., shall be carried out as per the manufacturer's instructions to have trouble free operation of the complete system.

62.2 Daily work of the operation and maintenance in the Solar Photovoltaic Power Plant involves periodic cleaning of Modules, logging the voltage, current, power factor, power and energy output of the Plant at different levels. The operator shall also note down time/ failures, interruption in supply and tripping of different relays, reason for such tripping, duration of such interruption etc. The other task of the operators is to check battery voltage-specific gravity and temperature. The operator shall record monthly energy output, down time, etc.

62.3 Earth resistance of Plant as well as individual earth pit is to be measured and recorded every month. If the earth resistance is high suitable action is to be taken to bring down the same.

62.4 A maintenance record is to be maintained by the operator/ O&M-in-charge to record the regular maintenance work carried out as well as any breakdown maintenance along with the reasons for the breakdowns and steps taken to attend the breakdown, duration of the breakdown etc.

62.5 The Preventive Maintenance Schedules will be drawn such that some of the jobs other than breakdown, which may require comparatively long stoppage of the Power Plant, shall be carried out preferably during the non-sunny days or evenings. Prior information shall be provided to the Employer for such preventive maintenance prior to start.

62.6 The Contractor will attend to any breakdown jobs immediately for repair/ replacement/ adjustments and complete at the earliest working round the clock. During breakdowns (not attributable to normal wear and tear) in O&M period, the Contractor shall immediately report the accidents, if any, to the Employer showing the circumstances under which it happened and the

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 104 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

extent of damage and/or injury caused.

62.7 The contractor shall at his own expense provide all amenities to his workmen as per applicable laws and rules.

62.8 If negligence / mal operation of the contractor's operator results in failure of equipment, such equipment should be repaired/replaced by the contractor free of cost.

63 Security services

The contractor has to arrange proper security system including deputation of security personnel at his own cost for the check vigil for the Solar Power Plant for the complete scope of works including complete O&M period.

The security staff may be organized to work on suitable shift system; proper checking & recording of all incoming & outgoing materials vehicles shall be maintained. Any occurrence of unlawful activities shall be informed to Employer immediately. A monthly report shall be sent to Employer on the security aspects.

All the information shown here is indicative only and may vary as per design and planning by the Contractor. The Contractor must provide the BOM of the plant as per the design during the time of submission of design basis report. The detailed technical specifications of major equipment to be followed strictly and are described in the technical specification section.

5 MW (AC) Solar PV Power Plant Project	<u>Tender No</u> <u>SECI/C&P/NIT/2017/BDL5MW-2</u>	<u>SoW & TS</u> <u>Page 105 of</u> <u>105</u>	<u>Signature of</u> <u>Bidder</u>

SCHEDULE OF RATES [SOR-2] [OPERATION AND MAINTENANCE]								
Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding								
Sl. No.	Description of Item	Year	PRICES (IN INR)					
			Yearly O&M Price (Excluding GST)	Total O&M Price (Excluding GST) in Words	Present Value Factor (PVF)	NPV of O&M Price	Total value of Applicable GST (in figures)	Yearly NPV Price including GST
1	2	3	4	5	9.08%	5 = 4 * PVF	6	7 = 6 + 5
OPERATION & MAINTENANCE								
1	Operation and Maintenance of the XXX MW Solar Roof Top Solar PV Project for FIRST YEAR	1	INR 0.00		0.917	INR 0.00		INR 0.00
2	Operation and Maintenance of the XXX MW Solar Roof Top Solar PV Project for SECOND YEAR	2	INR 0.00		0.840	INR 0.00		INR 0.00
3	Operation and Maintenance of the XXX MW Solar Roof Top Solar PV Project for THIRD YEAR	3	INR 0.00		0.770	INR 0.00		INR 0.00
4	Operation and Maintenance of the XXX MW Solar Roof Top Solar PV Project for FOURTH YEAR	4	INR 0.00		0.706	INR 0.00		INR 0.00
5	Operation and Maintenance of the XXX MW Solar Roof Top Solar PV Project for FIFTH YEAR	5	INR 0.00		0.648	INR 0.00		INR 0.00
	TOTAL NPV OF O&M FOR 5 YEARS (1+2+3+4+5)		INR 0.00			INR 0.00	INR 0.00	INR 0.00
TOTAL NPV OF O&M FOR 5 YEARS (1+2+3+4+5)		(In Words)						

NOTES

- O & M Charges on YoY basis must be in equal or in ascending order only.
- Certified that rates quoted above are as per the requirement, specification terms & condition mentioned in the Tender Document.
- Bidder to mention the NPV of O&M amount for total 5 years in CELL NO I 21 only of SOR 1 which should match with the NPV of O&M amount for total 05 years in CELL NO J 18 of SOR 2.

SCHEDULE OF RATES [SOR-1]							
Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding							
Sl. No.	Description of Item	Quantity (Ls)	PRICES (IN INR)				
			Unit FOR Destination basis Price (Excluding GST)	Unit FOR Destination basis Price (Excluding GST) in words	Total FOR Destination basis Price (Excluding GST)	Total value of Applicable GST (in figures)	Total Price including GST
1	2	3	4	5	6 = 3 * 4	7	8 = 6 + 7
A - SUPPLY							
1	Supply of PV Modules as specified in the Tender Documents	1			INR 0.00		INR 0.00
2	Supply of Inverters as specified in the Tender Documents	1			INR 0.00		INR 0.00
3	Mandatory Spares (0.25% of total supply of solar modules)	1			INR 0.00		INR 0.00
4	Manufacture & Supply of Balance of System including all Equipments, Materials, Spares, Accessories, MMS, Safety & Fire Fighting System etc. excluding 1,2 & 3 above and any other Supplies specified in the Tender Documents	1			INR 0.00		INR 0.00
	Sub Total - A		0		INR 0.00	INR 0.00	INR 0.00
B - SERVICES							

SCHEDULE OF RATES [SOR-1]							
Tender for Design, Engineering, Supply, Construction, Erection, Testing & Commissioning of 5 MW (AC) Solar PV Power Plant with Indigenous Cells & Modules including 5 Years Plant O&M at Bharat Dynamics Limited, Ibrahimpatnam, Telangana under Domestic Competitive bidding							
Sl. No.	Description of Item	Quantity (Ls)	PRICES (IN INR)				
			Unit FOR Destination basis Price (Excluding GST)	Unit FOR Destination basis Price (Excluding GST) in words	Total FOR Destination basis Price (Excluding GST)	Total value of Applicable GST (in figures)	Total Price including GST
1	2	3	4	5	6 = 3 * 4	7	8 = 6 + 7
5	Design, Engineering, Installation, Erection, Testing and Commissioning including Performance Testing in respect of all the Equipments Supplied and any other Services Specified in the Contract Documents	1			INR 0.00		INR 0.00
6	Civil and allied works including construction of Trenches, Module Mounting Structure, foundations, etc of all the Equipments Supplied.	1			INR 0.00		INR 0.00
	Sub Total - B		0		INR 0.00	INR 0.00	INR 0.00
	7						
7	Bidder to mention here the NPV of O&M amount for total 5 years in <u>CELL NO I 21 only</u> which should match with the NPV of O&M amount for total 5 years in <u>CELL NO J 23 of SOR 2.</u> <u>In case of any variation the NPV of O&M amount for total 05 years mentioned at CELL NO J 23 of SOR 2 will be considered for evaluation purpose.</u>						INR 0.00
	Sub Total - C						INR 0.00
	TOTAL EVALUATED BID VALUE (TEBV) (A+B+C)						INR 0.00
	TOTAL EVALUATED BID VALUE (TEBV) (A+B+C)	(In Words)					

NOTES

- O & M Charges on YoY basis must be in equal or in ascending order only.
- Certified that rates quoted above are as per the requirement, specification terms & condition mentioned in the Tender Document.
- Bidder to mention the NPV of O&M amount for total 5 years in CELL NO I 21 only of SOR 1 which should match with the NPV of O&M amount for total 05 years in CELL NO J 18 of SOR 2.



SECTION - VIII

SCHEDULE OF RATES (SOR)

1. **Bidders are required to quote for the Total Contract Price on Lumpsum basis in cognizance with the Tender Terms & Conditions.**
2. Bidder's quoted prices shall be strictly as per various Formats included under this Section [i.e. Section-VIII, Schedule of Rates (SOR)]. Bidder shall quote Lumpsum (LS) Price for the entire scope of work including Design, Engineering, Manufacture, Supply, Storage, Civil Work, Erection, Testing & Commissioning as per the Technical Specifications (TS) as defined under Section-VII.
3. All the Columns of quoted items in the Schedule of Rates including currency must be filled with required information, as applicable.
4. Bidder must quote the price in enclosed SOR formats only. The formats shall not be changed and/ or retyped. For any deviation to the SOR format, bid is liable for rejection.
5. Bidder to note that breakup of Lumpsum price is to be provided for assessment of Total Evaluated Bid Value (TEBV), however total price payable under the Contract shall be restricted to the Lumpsum Price/ Contract Price only.
6. The Lumpsum Price shall be considered as Total Contract Price which Employer agrees to pay and the Contractor agrees to accept as full compensation for the Contractor's full performance of the Work in accordance with the provisions of the Contract Documents. Contract Price shall not be subjected to any adjustment except in case of Change Order or Statutory Variations (as per Clauses of GCC) in accordance with the provisions of the Contract.
7. The price quoted shall be Lumpsum price on Turnkey basis. Unless the basic parameter changes or additional/ extra requirements are made, total payments to be made to the contractor shall be limited to Lumpsum price indicated, irrespective of the progressive payments made during execution based on the split up of price.
8. Obligation of the Contractor is not limited to the quantities that the Contractor may either indicate in the Schedule of Breakup of Lumpsum Prices along with his bid or in further detailed break of Lumpsum prices furnished along with the bid or after award of work. Contractor shall carry entire scope of work/ supplies as detailed in various sections/ volumes of the Tender Document within the quoted Lumpsum Price (Contract Price).
9. Lumpsum Prices quoted by the Bidder shall include cost of any other supplies/ work(s) not specifically mentioned in the Bidding Document but necessary for the efficient, trouble free commissioning & operation of the Plant and to make this package job complete. Quoted price are FIRM and fixed till complete execution of the entire order. Also variation on account of Foreign Exchange rate is not to be payable extra.
10. Spares for start-up/ commissioning and mandatory spares required are in Contractor's Scope and deemed included in the quoted Lumpsum Prices.
11. Bidder shall furnish following Forms of Schedule of Rates:-
 - a) SOR -1 is the Schedule and Breakup of Lump sum Price (Supply, Service and NPV of O&M) of the Tender. SOR -2 comprises of the yearly Breakup of the NPV of O&M price for 5 years period.

- b) Details of Goods & Service Tax (GST) as included in SOR-1
- c) Prices shall be considered for evaluation on NPV basis as per Evaluation Methodology Specified in Section III ITB of the Tender Document.
- d) Bidder to mention the NPV of O&M amount for total 05 years in CELL NO I 21 of SOR-1 which should match with the NPV of O&M amount for total 5 years in CELL NO J 18 of SOR 2.
- e) In case of any variation of the total NPV of O&M price, the NPV of O&M amount for total 5 years mentioned at CELL NO J 18 of SOR 2 will be considered for evaluation purpose.

12. INR = Indian Rupees

13. Bidder confirms that he has noted the contents of the Preamble to the Schedule of Rates, Schedule of Rate, Bid Document and quoted his Prices accordingly without any deviation.

14. O & M Charges on YoY basis must be equal or in ascending order only.